



US008964156B2

(12) **United States Patent**
Kimura

(10) **Patent No.:** **US 8,964,156 B2**
(45) **Date of Patent:** **Feb. 24, 2015**

(54) **LIQUID CRYSTAL DISPLAY DEVICE AND ELECTRONIC DEVICE**

(71) Applicant: **Semiconductor Energy Laboratory Co., Ltd.**, Atsugi, Kanagawa-ken (JP)

(72) Inventor: **Hajime Kimura**, Kanagawa (JP)

(73) Assignee: **Semiconductor Energy Laboratory Co., Ltd.**, Atsugi-shi, Kanagawa-ken (JP)

(*) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 0 days.

(21) Appl. No.: **14/322,999**

(22) Filed: **Jul. 3, 2014**

(65) **Prior Publication Data**

US 2014/0313445 A1 Oct. 23, 2014

Related U.S. Application Data

(63) Continuation of application No. 13/409,288, filed on Mar. 1, 2012, now Pat. No. 8,780,307, which is a continuation of application No. 12/977,217, filed on Dec. 23, 2010, now Pat. No. 8,130,354, which is a continuation of application No. 11/923,128, filed on Oct. 24, 2007, now Pat. No. 7,872,722.

(30) **Foreign Application Priority Data**

Oct. 31, 2006 (JP) 2006-297009

(51) **Int. Cl.**

G02F 1/1343 (2006.01)

G02F 1/1368 (2006.01)

(Continued)

(52) **U.S. Cl.**

CPC **G02F 1/136286** (2013.01); **G02F 1/134363** (2013.01)

USPC **349/141**; 349/43; 349/139

(58) **Field of Classification Search**

CPC G02F 1/134363; G02F 1/1362; G02F 1/133553; G02F 2001/134372; G02F 2001/136231; G02F 1/136286; G02F

2011/13629; G09G 3/3659; G09G 3/342;

G09G 2300/0876; H01L 27/12; H01L

27/1214; H04N 9/3102; H04N 9/3197

USPC 349/42, 43, 138, 139, 141; 257/43, 59, 257/72; 345/92

See application file for complete search history.

(56) **References Cited**

U.S. PATENT DOCUMENTS

5,870,160 A 2/1999 Yanagawa et al.

6,034,757 A 3/2000 Yanagawa et al.

(Continued)

FOREIGN PATENT DOCUMENTS

CN 001841140 A 10/2006

EP 1737044 A 12/2006

(Continued)

OTHER PUBLICATIONS

Chinese Office Action (Application No. 200710184974.X) Dated Aug. 5, 2010.

(Continued)

Primary Examiner — Dung Nguyen


Assistant Examiner — Tai Duong

(74) *Attorney, Agent, or Firm* — Fish & Richardson P.C.

(57) **ABSTRACT**

To provide a semiconductor device, a liquid crystal display device, and an electronic device which have a wide viewing angle and in which the number of manufacturing steps, the number of masks, and manufacturing cost are reduced compared with a conventional one. The liquid crystal display device includes a first electrode formed over an entire surface of one side of a substrate; a first insulating film formed over the first electrode; a thin film transistor formed over the first insulating film; a second insulating film formed over the thin film transistor; a second electrode formed over the second insulating film and having a plurality of openings; and a liquid crystal over the second electrode. The liquid crystal is controlled by an electric field between the first electrode and the second electrode.

16 Claims, 71 Drawing Sheets



- (51) **Int. Cl.**
G02F 1/139 (2006.01)
G02F 1/1362 (2006.01)

(56) **References Cited**

U.S. PATENT DOCUMENTS

6,108,066 A 8/2000 Yanagawa et al.
 6,281,953 B1 8/2001 Lee et al.
 6,433,842 B1 8/2002 Kaneko et al.
 6,462,723 B1 10/2002 Yamazaki et al.
 6,590,627 B2 7/2003 Tomioka et al.
 6,603,453 B2 8/2003 Yamazaki et al.
 6,710,835 B2 3/2004 Kurahashi et al.
 6,784,457 B2 8/2004 Yamazaki et al.
 6,914,656 B2 7/2005 Sakamoto et al.
 6,958,799 B2 10/2005 Tomioka et al.
 6,960,787 B2 11/2005 Yamazaki et al.
 6,961,111 B1 11/2005 Kuramasu
 6,970,222 B2 11/2005 Nakayoshi et al.
 7,088,409 B2 8/2006 Itou et al.
 7,247,882 B2 7/2007 Yamazaki et al.
 7,248,324 B2 7/2007 Ono et al.
 7,251,005 B2 7/2007 Ono et al.
 7,251,006 B2 7/2007 Ono et al.
 7,253,863 B2 8/2007 Ono et al.
 7,256,854 B2 8/2007 Ono et al.
 7,271,869 B2 9/2007 Ono et al.
 7,307,673 B2 12/2007 Nakayoshi et al.
 7,423,701 B2 9/2008 Nakayoshi et al.
 7,423,713 B2 9/2008 Kurasawa
 7,456,924 B2 11/2008 Ono et al.
 7,564,529 B2 7/2009 Ahn
 7,605,876 B2 10/2009 Nakayoshi et al.
 7,683,996 B2 3/2010 Ono et al.
 7,692,748 B2 4/2010 Ono et al.
 7,697,100 B2 4/2010 Ono et al.
 7,705,949 B2 4/2010 Ono et al.
 7,733,455 B2 6/2010 Ono et al.
 7,782,436 B2 8/2010 Ahn
 7,791,072 B2 9/2010 Kumomi et al.
 7,816,682 B2 10/2010 Kimura
 7,851,797 B2 12/2010 Yamazaki et al.
 7,872,696 B2 1/2011 Nakayoshi et al.
 7,928,938 B2 4/2011 Osame et al.
 7,936,429 B2 5/2011 Ono et al.
 8,035,786 B2 10/2011 Ono et al.
 8,045,116 B2 10/2011 Ono et al.
 8,072,569 B2 12/2011 Kaneko et al.
 8,203,661 B2 6/2012 Nakayoshi et al.
 8,218,118 B2 7/2012 Ono et al.
 8,218,119 B2 7/2012 Ono et al.
 8,237,166 B2 8/2012 Kumomi et al.
 8,248,548 B2 8/2012 Nakayoshi et al.
 8,248,549 B2 8/2012 Nakayoshi et al.
 8,310,641 B2 11/2012 Nakayoshi et al.
 8,338,865 B2 12/2012 Kimura
 8,345,205 B2 1/2013 Ono et al.
 8,493,522 B2 7/2013 Nakayoshi et al.
 8,493,537 B2 7/2013 Ono et al.
 8,564,752 B2 10/2013 Ono et al.
 8,648,989 B2 2/2014 Ono et al.
 2003/0001832 A1 1/2003 Yamazaki et al.
 2003/0218664 A1 11/2003 Sakamoto et al.
 2005/0105033 A1 5/2005 Itou et al.
 2005/0259207 A1 11/2005 Yang et al.
 2005/0264731 A1 12/2005 Itou et al.
 2006/0092356 A1 5/2006 Morimoto et al.
 2006/0092363 A1 5/2006 Hasegawa et al.
 2006/0187371 A1 8/2006 Nakayoshi et al.
 2006/0192912 A1 8/2006 Itou et al.
 2006/0215086 A1 9/2006 Kurasawa
 2006/0215087 A1 9/2006 Matsushima et al.
 2006/0267891 A1 11/2006 Nishimura et al.
 2007/0126968 A1 6/2007 Uochi
 2007/0126969 A1 6/2007 Kimura et al.
 2007/0146591 A1 6/2007 Kimura et al.

2007/0194379 A1 8/2007 Hosono et al.
 2007/0236640 A1 10/2007 Kimura
 2007/0284627 A1 12/2007 Kimura
 2008/0002079 A1 1/2008 Kimura
 2009/0096974 A1 4/2009 Ono et al.
 2009/0278122 A1 11/2009 Hosono et al.
 2009/0280600 A1 11/2009 Hosono et al.
 2011/0032435 A1 2/2011 Kimura
 2011/0101352 A1 5/2011 Hosono et al.
 2011/0187762 A1 8/2011 Osame et al.
 2011/0201162 A1 8/2011 Hosono et al.
 2012/0012838 A1 1/2012 Hosono et al.
 2013/0128174 A1 5/2013 Kimura
 2013/0201419 A1 8/2013 Ono et al.
 2013/0286313 A1 10/2013 Nakayoshi et al.
 2014/0043556 A1 2/2014 Ono et al.

FOREIGN PATENT DOCUMENTS

EP 1843194 A 10/2007
 EP 2226847 A 9/2010
 EP 2246894 A 11/2010
 EP 2413366 A 2/2012
 JP 08-078329 A 3/1996
 JP 10-003092 A 1/1998
 JP 2000-284326 A 10/2000
 JP 2001-051292 A 2/2001
 JP 2001-154218 A 6/2001
 JP 2001-175198 A 6/2001
 JP 2002-221736 A 8/2002
 JP 2003-068757 A 3/2003
 JP 2003-107445 A 4/2003
 JP 2003-195352 A 7/2003
 JP 3742836 2/2006
 JP 2006-106110 A 4/2006
 JP 2006-126855 A 5/2006
 JP 2006-165528 A 6/2006
 JP 2006-184325 A 7/2006
 JP 2006-276111 A 10/2006
 JP 2006-276112 A 10/2006
 JP 2006-286719 A 10/2006
 JP 2006-286772 A 10/2006
 JP 2014-002392 A 1/2014
 KR 2001-0060835 A 7/2001
 KR 2002-0041426 A 6/2002
 KR 2002-0070756 A 9/2002
 KR 2003-0031443 A 4/2003
 KR 2004-0012200 A 2/2004
 KR 2006-0079040 A 7/2006
 KR 2006-0110202 A 10/2006
 TW 589480 6/2004
 TW 200809357 2/2008
 WO WO-01/18597 3/2001
 WO WO-2005/088726 9/2005

OTHER PUBLICATIONS

Lee.S et al., "29.2: 18.1 Ultra-FFS TFT-LCD With Super Image Quality and Fast Response Time", SID Digest '01 : SID International Symposium Digest of technical papers, 2001, vol. 32, pp. 484-487.
 Song.J et al., "Electro-optic Characteristics of Fringe-Field Driven Transflective LCD with Dual Cell Gap", IDW/AD '05(Proceedings of The 12th International Display Workshops in conjunction with Asia Display), Dec. 6, 2005, vol. 1, pp. 103-106.
 Choi.M et al., "P-110: A Single Gap Transflective Display Using a Fringe-Field Driven Homogeneously Aligned Nematic Liquid Crystal Display", SID Digest '05 : SID International Symposium Digest of Technical Papers, 2005, vol. 36, pp. 719-721.
 Lu.R et al., "Transflective Liquid Crystal Display Using In-plane Switching Effect", Conference Record of The 2006 IDRC (International Display Research Conference), Sep. 1, 2006, pp. 39-42.
 Lee.G et al., "Design of Wide-Viewing-Angle Transflective IPS LCD", Conference Record of the 2006 IDRC (International Display Research Conference), Sep. 1, 2006, pp. 75-77.

(56)

References Cited

OTHER PUBLICATIONS

Aoki.N, "Advanced IPS Technology for Mobile Applications", SID Digest '06 : SID International Symposium Digest of Technical Papers, 2006, vol. 37, pp. 1087-1090.

Sakamoto.M et al., "Development of the Novel Transflective LCD Module Using Super-Fine-TFT Technology", SID Digest '06 : SID International Symposium Digest of Technical Papers, 2006, vol. 37, pp. 1669-1672.

Lee.G et al., "Optical Configurations of Horizontal-Switching Transflective LCDs in Double Cellgap Structure", IDW/AD '05(Proceedings of The 12th International Display Workshops in conjunction with Asia Display), 2005, vol. 1, pp. 111-114.

Itou.O et al., "A Wide Viewing Angle Transflective IPS LCD Applying New Optical Design", SID Digest '06 : SID International Symposium Digest of Technical Papers, 2006, vol. 37, pp. 832-835.

You.J et al., "23.4: Characteristics and Reliabilities of the Ion Beam Irradiated Polyimide as an LC Alignment Layer", SID Digest '05 : SID International Symposium Digest of Technical Papers, 2005, vol. 36, pp. 1089-1091.

Taiwanese Office Action (Application No. 96139500) Dated Oct. 21, 2013.

Korean Office Action (Application No. 2007-0109956) Dated Dec. 29, 2013.

Korean Office Action (Application No. 2014-0023558) Dated Apr. 30, 2014.

Korean Office Action (Application No. 2014-0023558) Dated Nov. 28, 2014.




FIG. 2






FIG. 3








FIG. 7




FIG. 8A




FIG. 8B




FIG. 8C




FIG. 8D




FIG. 9A




FIG. 9B




FIG. 9C





FIG. 9D







FIG. 11






FIG. 13




FIG. 14A




FIG. 14B




FIG. 15A




FIG. 15B



FIG. 15C








FIG. 15D










FIG. 18




FIG. 19A




FIG. 19B




FIG. 20A




FIG. 20B




FIG. 21A




FIG. 21B




FIG. 21C




FIG. 21D




FIG. 21E




FIG. 21F




FIG. 21G




FIG. 21H




FIG. 22




FIG. 23A





FIG. 23B






FIG. 26




FIG. 27




FIG. 28




FIG. 29A




FIG. 29B



FIG. 29C




FIG. 29D




FIG. 29E




FIG. 29F




FIG. 29G




FIG. 30




FIG. 31





FIG. 32






FIG. 34A




FIG. 34B




FIG. 34C




FIG. 35A




FIG. 35B





FIG. 36







FIG. 38






FIG. 39A




FIG. 39B




FIG. 41A




FIG. 41B




FIG. 41C




FIG. 41D




FIG. 42




FIG. 43A




FIG. 43B




FIG. 43C




FIG. 44




FIG. 45A




FIG. 45B




FIG. 46




FIG. 47




FIG. 48A




FIG. 48B




FIG. 48C




FIG. 48E




FIG. 48D




FIG. 49A




FIG. 49B




FIG. 50A




FIG. 50B




FIG. 50C




FIG. 51A




FIG. 51B




FIG. 51C




FIG. 52A




FIG. 52B




FIG. 52C




FIG. 53A




FIG. 53B




FIG. 54




FIG. 55




FIG. 56




FIG. 57A




FIG. 57B




FIG. 57C




FIG. 58




FIG. 59




FIG. 60A




FIG. 60B




FIG. 61




FIG. 62A




FIG. 62B




FIG. 62C




FIG. 63




FIG. 64




FIG. 65




FIG. 66




FIG. 67A




FIG. 67B




FIG. 68A




FIG. 68B




FIG. 69A




FIG. 69B




FIG. 69C




FIG. 70A




FIG. 70B





FIG. 71



LIQUID CRYSTAL DISPLAY DEVICE AND ELECTRONIC DEVICE

CROSS-REFERENCE TO RELATED APPLICATIONS

This application is a continuation of U.S. application Ser. No. 13/409,288, filed Mar. 1, 2012, now allowed, which is a continuation of U.S. application Ser. No. 12/977,217, filed Dec. 23, 2010, now U.S. Pat. No. 8,130,354, which is a continuation of U.S. application Ser. No. 11/923,128, filed Oct. 24, 2007, now U.S. Pat. No. 7,872,722, which claims the benefit of a foreign priority application filed in Japan as Serial No. 2006-297009 on Oct. 31, 2006, all of which are incorporated by reference.

BACKGROUND OF THE INVENTION

1. Field of the Invention

The present invention relates to a semiconductor device and a liquid crystal display device. In particular, the present invention relates to a semiconductor device and a liquid crystal display device in which liquid crystal molecules are controlled by generating an electric field having a component parallel to a substrate.

2. Description of the Related Art

One of technical development strategies of a liquid crystal display device is to widen a viewing angle. As a technique for realizing a wide viewing angle, a method is used in which a gray scale is controlled by generating an electric field parallel (i.e., in a lateral direction) to a substrate to move liquid crystal molecules in a plane parallel to the substrate.

Examples of such a method include an IPS (In-Plane Switching) mode and an FFS (Fringe-Field Switching) mode.

In an IPS mode liquid crystal display device, two comb-shaped electrodes (also referred to as comb-teeth electrodes or comb electrodes) are provided over one of a pair of substrates. Liquid crystal molecules are moved within a plane parallel to the substrate by a horizontal electric field generated by potential difference between these electrodes (one of the comb-shaped electrodes is a pixel electrode and the other thereof is a common electrode).

In an FFS mode liquid crystal display device, a second electrode (e.g., a pixel electrode in which voltage for each pixel is controlled) having an opening is provided below a liquid crystal, and a first electrode (e.g., a common electrode in which common voltage is applied to all pixel) is provided below the opening in some cases. An electric field is applied between the pixel electrode and the common electrode to control the liquid crystal. An electric field in a parallel direction is applied to the liquid crystal, so that liquid crystal molecules can be controlled using the electric field. That is, liquid crystal molecules aligned parallel to a substrate (so-called homogeneous alignment) can be controlled in a direction parallel to the substrate, so that a viewing angle is widened.

In conventional semiconductor device and liquid crystal display device which control liquid crystal molecules, a pixel electrode or a common electrode has been formed of a light-transmitting conductive film, for example, indium tin oxide (ITO) (see Patent Document 1: Japanese Patent No. 3742836).

SUMMARY OF THE INVENTION

As described above, a pixel electrode or a common electrode has been formed of a light-transmitting conductive film,

for example, ITO. In order to manufacture a semiconductor device which controls transmissive liquid crystal molecules and a transmissive liquid crystal display device, a pixel electrode and a common electrode are needed to be formed of a light-transmitting conductive film. Conventionally, after formation of a light-transmitting conductive film, the light-transmitting conductive film has been processed to form a pixel electrode and a common electrode by etching or the like. Thus, the number of manufacturing steps and the number of masks have been increased, and manufacturing cost has been increased.

In view of the above, objects of the invention are to provide a semiconductor device, a liquid crystal display device, and an electronic device which have a wide viewing angle and in which the number of manufacturing steps and the number of masks are small and manufacturing cost is low.

In the invention, a light-transmitting conductive film is formed to use as one of a pixel electrode and a common electrode of a liquid crystal display device without processing. Thus, the light-transmitting conductive film is not needed to be processed by etching or the like, so that the number of manufacturing steps and the number of masks can be reduced and manufacturing cost can be suppressed.

Note that a liquid crystal element is acceptable as long as arrangement of liquid crystal molecules controlling the amount of light can be rotated in a direction generally parallel to a substrate by a horizontal electric field generated by potential difference between a pixel electrode and a common electrode which is connected in common with a plurality of pixels in a pixel portion.

One aspect of the invention is a liquid crystal display device which includes a first electrode formed over an entire surface of one side of a substrate; a first insulating film formed over the first electrode; a thin film transistor formed over the first insulating film; a second insulating film formed over the thin film transistor; a second electrode formed over the second insulating film and having a plurality of openings; and a liquid crystal over the second electrode. The liquid crystal is controlled by an electric field between the first electrode and the second electrode.

In the invention, the thin film transistor may be a top-gate thin film transistor.

In the invention, the thin film transistor may be a bottom-gate thin film transistor.

In the invention, the first electrode and the second electrode may be light-transmitting conductive films.

In the invention, one of the first electrode and the second electrode may be a light-transmitting conductive film and the other thereof may be a reflective conductive film.

The invention also relates to an electronic device provided with a liquid crystal display device formed using the invention.

The following description is for structures applicable to a liquid crystal display device and a semiconductor device of the invention. The structures described hereinafter can be applied to a liquid crystal display device and a semiconductor device of the invention when needed.

Note that various types of switches can be used as a switch. An electrical switch, a mechanical switch, and the like are given as examples. That is, any element can be used without being limited to a particular type as long as it can control a current flow. For example, a transistor (e.g., a bipolar transistor or a MOS transistor), a diode (e.g., a PN diode, a PIN diode, a Schottky diode, a MIM (Metal Insulator Metal) diode, a MIS (Metal Insulator Semiconductor) diode, or a diode-connected transistor), a thyristor, or the like can be

used as a switch. Further, a logic circuit combining such elements can be used as a switch.

Examples of a mechanical switch include a switch formed using a micro electro mechanical system (MEMS) technology, such as a digital micro mirror device (DMD).

Such a switch includes an electrode which can be moved mechanically, and operates by controlling connection or non-connection based on movement of the electrode.

In the case where a transistor is used as a switch, polarity (a conductivity type) of the transistor is not particularly limited since it operates just as a switch. However, when off-current is preferably to be suppressed, a transistor of polarity with smaller off-current is preferably used. As a transistor with smaller off-current, a transistor having an LDD region, a transistor having a multi-gate structure, and the like are given as examples. Further, an n-channel transistor is preferably used when the transistor operates with a potential of a source terminal closer to a potential of a low potential side power supply (e.g., Vss, GND, or 0 V). On the other hand, a p-channel transistor is preferably used when the transistor operates with a potential of a source terminal close to a potential of a high potential side power supply (e.g., Vdd). This is because when the n-channel transistor operates with the potential of the source terminal close to a low potential side power supply or the p-channel transistor operates with the potential of the source terminal close to a high potential side power supply, an absolute value of a gate-source voltage can be increased; thus, the transistor can more precisely operate as a switch. This is because reduction in output voltage does not occur often since the transistor does not often perform a source follower operation.

Note that a CMOS switch may also be employed by using both n-channel and p-channel transistors. A CMOS switch can easily function as a switch since a current can flow when one of the n-channel transistor and the p-channel transistor is turned on. For example, a voltage can be output as appropriate whether a voltage of an input signal to the switch is high or low. Further, since a voltage amplitude value of a signal for turning on/off a switch can be decreased, power consumption can be reduced.

Note that when a transistor is used as a switch, the switch includes an input terminal (one of a source terminal and a drain terminal), an output terminal (the other of the source terminal and the drain terminal), and a terminal (a gate terminal) for controlling electrical conduction. On the other hand, when a diode is used as a switch, the switch does not have a terminal for controlling electrical conduction in some cases. Therefore, when a diode is used as a switch, the number of wirings for controlling terminals can be reduced compared with the case where a transistor is used as a switch.

Note that when it is explicitly described that A and B are connected, the case where A and B are electrically connected, the case where A and B are functionally connected, and the case where A and B are directly connected are included. Here, each of A and B is an object (e.g., a device, an element, a circuit, a wiring, an electrode, a terminal, a conductive film, or a layer). Accordingly, another element may be provided in a connection relationship shown in drawings and texts, without being limited to a predetermined connection relationship, for example, connection relationships shown in the drawings and the texts.

For example, when A and B are electrically connected, one or more elements which enable electrical connection of A and B (e.g., a switch, a transistor, a capacitor, an inductor, a resistor, or a diode) may be provided between A and B. In addition, when A and B are functionally connected, one or more circuits which enable functional connection of A and B

(e.g., a logic circuit such as an inverter, a NAND circuit, or a NOR circuit; a signal converter circuit such as a DA converter circuit, an AD converter circuit, or a gamma correction circuit; a potential level converter circuit such as a power supply circuit (e.g., a voltage step-up circuit or a voltage step-down circuit) or a level shifter circuit for changing a potential level of a signal; a voltage source; a current source; a switching circuit; or an amplifier circuit which can increase signal amplitude, the amount of current, or the like, such as an operational amplifier, a differential amplifier circuit, a source follower circuit, or a buffer circuit, a signal generation circuit; a memory circuit; or a control circuit may be provided between A and B. Alternatively, in the case where A and B are directly connected, A and B may be directly connected without interposing another element or another circuit therebetween.

When it is explicitly described that A and B are directly connected, the case where A and B are directly connected (i.e., the case where A and B are connected without interposing another element or another circuit therebetween) and the case where A and B are electrically connected (i.e., the case where A and B are connected by interposing another element or another circuit therebetween) are included.

In addition, when it is explicitly described that A and B are electrically connected, the case where A and B are electrically connected (i.e., the case where A and B are connected by interposing another element or another circuit therebetween), the case where A and B are functionally connected (i.e., the case where A and B are functionally connected by interposing another circuit therebetween), and the case where A and B are directly connected (i.e., the case where A and B are connected without interposing another element or another circuit therebetween) are included. That is, when it is explicitly described that A and B are electrically connected, the description is the same as the case where it is explicitly only described that A and B are connected.

Note that a display element, a display device which is a device including a display element, a light-emitting element, and a light-emitting device which is a device including a light-emitting element can employ various types and can include various elements. For example, as a display element, a display device, a light-emitting element, and a light-emitting device, a display medium, contrast, luminance, reflectivity, transmittance, or the like of which is changed by electromagnetic action, such as an EL (electroluminescence) element (e.g., an EL element including both organic and inorganic materials, an organic EL element, or an inorganic EL element), an electron emitter, a liquid crystal element, electronic ink, an electrophoretic element, a grating light valve (GLV), a plasma display panel (PDP), a digital micro-mirror device (DMD), a piezoelectric ceramic display, or a carbon nanotube can be used. Note that display devices using an EL element include an EL display; display devices using an electron emitter include a field emission display (FED), an SED-type flat panel display (SED: Surface-conduction Electron-emitter Display), and the like; display devices using a liquid crystal element include a liquid crystal display (e.g., a transmissive liquid crystal display, a transreflective liquid crystal display, a reflective liquid crystal display, a direct-view liquid crystal display, or a projection type liquid crystal display; and display devices using electronic ink include electronic paper.

Note that an EL element is an element including an anode, a cathode, and an EL layer interposed between the anode and the cathode.

Examples of the EL layer include various types of EL layers, for example, a layer utilizing light emission (fluores-

cence) from a singlet exciton, a layer utilizing light emission (phosphorescence) from a triplet exciton, a layer utilizing light emission (fluorescence) from a singlet exciton and light emission (phosphorescence) from a triplet exciton, a layer formed of an organic material, a layer formed of an inorganic material, a layer formed of an organic material and an inorganic material, a layer including a high molecular material, a layer including a low molecular material, and a layer including a low molecular material and a high molecular material.

Note that the invention is not limited thereto, and various types of EL elements can be used.

Note that an electron emitter is an element in which electrons are extracted by high electric field concentration on a pointed cathode.

For example, the electron emitter may be any one of a Spindt type, a carbon nanotube (CNT) type, a metal-insulator-metal (MIM) type in which a metal, an insulator, and a metal are stacked, a metal-insulator-semiconductor (MIS) type in which a metal, an insulator, and a semiconductor are stacked, a MOS type, a silicon type, a thin film diode type, a diamond type, a surface conduction emitter SCD type, a thin film type in which a metal, an insulator, a semiconductor, and a metal are stacked, a HEED type, an EL type, a porous silicon type, a surface-conduction electron-emitter (SED) type, and the like. However, the invention is not limited thereto, and various elements can be used as an electron emitter.

Note that a liquid crystal element is an element which controls transmission or non-transmission of light by optical modulation action of a liquid crystal and includes a pair of electrodes and a liquid crystal.

Optical modulation action of a liquid crystal is controlled by an electric field applied to the liquid crystal (including a horizontal electric field, a vertical electric field, and an oblique electric field).

The following can be used for a liquid crystal element: a nematic liquid crystal, a cholesteric liquid crystal, a smectic liquid crystal, a discotic liquid crystal, a thermotropic liquid crystal, a lyotropic liquid crystal, a low molecular liquid crystal, a polymer liquid crystal, a ferroelectric liquid crystal, an anti-ferroelectric liquid crystal, a main chain type liquid crystal, a side chain type polymer liquid crystal, a plasma addressed liquid crystal (PALC), a banana-shaped liquid crystal, a TN (Twisted Nematic) mode, an STN (Super Twisted Nematic) mode, an IPS (In-Plane-Switching) mode, an FFS (Fringe Field Switching) mode, an MVA (Multi-domain Vertical Alignment) mode, a PVA (Patterned Vertical Alignment) mode, an ASV (Advanced Super View) mode, an ASM (Axially Symmetric aligned Microcell) mode, an OCB (Optical Compensated Birefringence) mode, an ECB (Electrically Controlled Birefringence) mode, an FLC (Ferroelectric Liquid Crystal) mode, an AFLC (Anti-Ferroelectric Liquid Crystal) mode, a PDLC (Polymer Dispersed Liquid Crystal) mode, and a guest-host mode.

Note that the invention is not limited thereto, and various kinds of liquid crystal elements can be used.

Note that examples of electronic paper include a device displayed by molecules which utilizes optical anisotropy, dye molecular orientation or the like; a device displayed by particles which utilizes electrophoresis, particle movement, particle rotation, phase change, or the like; a device displayed by moving one end of a film; a device using light emission or phase change of molecules; a device using optical absorption by molecules; and a device using self-light emission by combining electrons and holes. For example, the following can be used as electronic paper: a microcapsule type electrophoresis device, a horizontal type electrophoresis device, a vertical type electrophoresis device, a device using a spherical twist-

ing ball, a device using a magnetic twisting ball, a device using a column twisting ball, a device using a charged toner, a quick-response liquid powder display, a magnetic electrophoresis type device, a magnetic heat-sensitive type device, an electrowetting type device, a light-scattering (transparent-opaque change) type device, a device using a cholesteric liquid crystal and a photoconductive layer, a cholesteric liquid crystal device, a bistable nematic liquid crystal device, a ferroelectric liquid crystal device, a liquid crystal dispersed type device with a dichroic dye, a device using a movable film, a device using coloring and decoloring properties of a leuco dye, a photochromic device, an electrochromic device, an electrodeposition device, a device using flexible organic EL, and the like.

Note that the invention is not limited thereto, and various types of electronic paper can be used.

By using a microcapsule electrophoretic device, defects of electrophoresis, which are aggregation and precipitation of phoresis particles, can be solved. Quick-response liquid powder has advantages such as high-speed response, high reflectivity, wide viewing angle, low power consumption, and memory properties.

A plasma display includes a substrate having a surface provided with an electrode, and a substrate having a surface provided with an electrode and a minute groove in which a phosphor layer is formed. In the plasma display, the substrates are opposite to each other with a narrow interval and a rare gas is sealed therein. Voltage is applied to the electrodes to generate an ultraviolet ray so as to excite the phosphor; thus, display can be performed. The plasma display panel may be a DC type PDP or an AC type PDP. As a driving method of the plasma display panel, ASW (Address While Sustain) driving, ADS (Address Display Separated) driving in which a sub-frame is divided into a reset period, an address period, and a sustain period, CLEAR (High-Contrast, Low Energy Address and Reduction of False Contour Sequence) driving, ALIS (Alternate Lighting of Surfaces) method, TERES (Technology of Reciprocal Sustainer) driving, and the like can be used. Note that the invention is not limited thereto, and various types of plasma displays can be used.

Note that electroluminescence, a cold cathode fluorescent lamp, a hot cathode fluorescent lamp, an LED, a laser light source, a mercury lamp, or the like can be used as a light source needed for a display device, such as a liquid crystal display device (a transmissive liquid crystal display, a trans-reflective liquid crystal display, a reflective liquid crystal display, a direct-view liquid crystal display, and a projection type liquid crystal display), a display device using a grating light valve (GLV), and a display device using a digital micromirror device (DMD). Note that the invention is not limited thereto, and various light sources can be used.

Note that as a transistor, various types of transistors can be employed without being limited to a certain type. For example, a thin film transistor (TFT) including a non-single crystalline semiconductor film typified by amorphous silicon, polycrystalline silicon, microcrystalline (also referred to as semi-amorphous) silicon, or the like can be used. The use of the TFT has various advantages. For example, since the TFT can be formed at temperature lower than that of the case of using single crystalline silicon, reduction in manufacturing cost or increase in size of a manufacturing device can be realized. A transistor can be formed using a large substrate with increase in size of the manufacturing device. Therefore, a large number of display devices can be formed at the same time, and thus can be formed at low cost. Further, since manufacturing temperature is low, a substrate having low heat resistance can be used. Accordingly, a transistor can be

formed over a light-transmitting substrate; thus, transmission of light in a display element can be controlled by using the transistor formed over the light-transmitting substrate. Alternatively, since the thickness of the transistor is thin, part of a film forming the transistor can transmit light; thus, an aperture ratio can be increased.

The use of a catalyst (e.g., nickel) when polycrystalline silicon is formed enables further improvement in crystallinity and formation of a transistor having excellent electrical characteristics. Thus, a gate driver circuit (a scan line driver circuit), a source driver circuit (a signal line driver circuit), and a signal processing circuit (e.g., a signal generation circuit, a gamma correction circuit, a DA converter circuit) can be formed over the same substrate.

The use of a catalyst (e.g., nickel) when microcrystalline silicon is formed enables further improvement in crystallinity and formation of a transistor having excellent electrical characteristics. At this time, the crystallinity can be improved by performing only heat treatment without laser irradiation. Thus, a gate driver circuit (a scan line driver circuit) and part of a source driver circuit (e.g., an analog switch) can be formed over the same substrate. Further, when laser irradiation is not performed for crystallization, unevenness of silicon crystallinity can be suppressed. Therefore, an image with high image quality can be displayed.

Note that polycrystalline silicon and microcrystalline silicon can be formed without using a catalyst (e.g., nickel).

Note that the crystallinity of silicon is preferably improved to polycrystal or microcrystal in the whole panel, but not limited thereto.

The crystallinity of silicon may be improved only in part of the panel. The selective increase in crystallinity can be achieved by selective laser irradiation or the like.

For example, only a peripheral driver circuit region excluding pixels may be irradiated with laser light.

Alternatively, only a region of a gate driver circuit, a source driver circuit, or the like may be irradiated with laser light.

Further alternatively, only part of a source driver circuit (e.g., an analog switch) may be irradiated with laser light.

As a result, the crystallinity of silicon only in a region necessary for high-speed operation of a circuit can be improved.

A pixel region is not especially needed to operate at high speed. Thus, even if the crystallinity is not improved, the pixel circuit can operate without problems.

Thus, since a region crystallinity of which is improved is small, manufacturing steps can be shortened, throughput can be increased, and manufacturing cost can be reduced.

Since the number of manufacturing devices needed is small, manufacturing cost can be reduced.

In addition, a transistor can be formed using a semiconductor substrate, an SOI substrate, or the like. Therefore, a small transistor with few variations in characteristics, sizes, shapes, or the like, with high current supply capacity can be formed. By using such a transistor, reduction in power consumption or high integration of circuits can be realized.

A transistor including a compound semiconductor or an oxide semiconductor such as ZnO, a-InGaZnO, SiGe, GaAs, IZO, ITO, or SnO, a thin film transistor obtained by thinning such a compound semiconductor or an oxide semiconductor, or the like can be used. Therefore, manufacturing temperature can be lowered and for example, such a transistor can be formed at room temperature. Accordingly, the transistor can be formed directly on a substrate having low heat resistance, such as a plastic substrate or a film substrate. Note that such a compound semiconductor or an oxide semiconductor can be used for not only a channel portion of the transistor but also

other applications. For example, such a compound semiconductor or an oxide semiconductor can be used as a resistor, a pixel electrode, or an electrode having a light-transmitting property. Further, since such an element can be formed at the same time as the transistor, cost can be reduced.

A transistor or the like formed by using an ink-jet method or a printing method can also be used. Accordingly, the transistor can be formed at room temperature or at a low vacuum, or can be formed using a large substrate. Since the transistor can be formed without using a mask (reticle), layout of the transistor can be easily changed. Further, since it is not necessary to use a resist, material cost is reduced and the number of steps can be reduced. Moreover, since a film is formed only in a required portion, a material is not wasted and cost can be reduced compared with a manufacturing method in which etching is performed after the film is formed over the entire surface.

A transistor or the like including an organic semiconductor or a carbon nanotube can also be used. Accordingly, a transistor can be formed using a substrate which can be bent, and thus can resist a shock.

In addition, transistors with various structures can be used.

For example, a MOS transistor, a junction transistor, a bipolar transistor, or the like can be used as a transistor.

The use of a MOS transistor can reduce the size of a transistor.

Accordingly, a plurality of transistors can be mounted.

The use of a bipolar transistor can allow large current to flow; thus, a circuit can operate at high speed.

Further, a MOS transistor, a bipolar transistor, and the like may be mixed over one substrate.

Thus, low power consumption, reduction in size, and high-speed operation can be achieved.

In addition, various other transistors can be used.

Note that a transistor can be formed using various substrates. The type of a substrate is not limited to a certain type. For example, a single crystalline substrate, an SOI substrate, a glass substrate, a quartz substrate, a plastic substrate, a paper substrate, a cellophane substrate, a stone substrate, a wood substrate, a cloth substrate (including a natural fiber (e.g., silk, cotton, or hemp), a synthetic fiber (e.g., nylon, polyurethane, or polyester), a regenerated fiber (e.g., acetate, cupra, rayon, or regenerated polyester), or the like), a leather substrate, a rubber substrate, a stainless steel substrate, a substrate including a stainless steel foil, or the like can be used as a substrate. Alternatively, a skin (e.g., epidermis or corium) or hypodermal tissue of an animal such as a human may be used as the substrate. In addition, the transistor may be formed using one substrate, and then, the transistor may be transferred to another substrate.

As a substrate to which the transistor is transferred, a single crystalline substrate, an SOI substrate, a glass substrate, a quartz substrate, a plastic substrate, a paper substrate, a cellophane substrate, a stone substrate, a wood substrate, a cloth substrate (including a natural fiber (e.g., silk, cotton, or hemp), a synthetic fiber (e.g., nylon, polyurethane, or polyester), a regenerated fiber (e.g., acetate, cupra, rayon, or regenerated polyester), or the like), a leather substrate, a rubber substrate, a stainless steel substrate, a substrate including a stainless steel foil, or the like can be used.

Alternatively, a skin (e.g., epidermis or corium) or hypodermal tissue of an animal such as a human may be used as the substrate. In addition, a transistor may be formed using a substrate, and the substrate may be thinned by polishing. As a substrate to be polished, a single crystalline substrate, an SOI substrate, a glass substrate, a quartz substrate, a plastic substrate, a paper substrate, a cellophane substrate, a stone sub-

strate, a wood substrate, a cloth substrate (including a natural fiber (e.g., silk, cotton, or hemp), a synthetic fiber (e.g., nylon, polyurethane, or polyester), a regenerated fiber (e.g., acetate, cupra, rayon, or regenerated polyester), or the like), a leather substrate, a rubber substrate, a stainless steel substrate, a substrate including a stainless steel foil, or the like can be used.

Alternatively, a skin (e.g., epidermis or corium) or hypodermal tissue of an animal such as a human may be used as the substrate. By using such a substrate, a transistor with excellent properties, a transistor with low power consumption can be formed, a device with high durability can be formed, high heat resistance can be provided, and reduction in weight or size can be realized.

Note that a structure of a transistor can employ various modes without being limited to a certain structure. For example, a multi-gate structure having two or more gate electrodes may be employed. When the multi-gate structure is used, a structure where a plurality of transistors are connected in series is provided since channel regions are connected in series. The multi-gate structure realizes reduction in off-current and improvement in reliability due to improvement in withstand voltage of the transistor. Further, by using the multi-gate structure, drain-source current does not change much even if drain-source voltage changes when the transistor operates in a saturation region; thus, the slope of voltage-current characteristics can be flat. By utilizing the characteristics in which the slope of the voltage-current characteristics is flat, an ideal current source circuit and an active load having an extremely high resistance value can be realized. Thus, a differential circuit or a current mirror circuit having excellent properties can be realized. As another example, a structure where gate electrodes are formed above and below a channel may be employed. By using the structure where gate electrodes are formed above and below the channel, a channel region is enlarged, the amount of current can be increased since the number of channel regions is increased, or a sub-threshold swing can be reduced since a depletion layer is easily formed. In the structure where the gate electrodes are formed above and below the channel, it seems that a plurality of transistors are connected in parallel.

A structure where a gate electrode is formed above a channel region, a structure where a gate electrode is formed below a channel region, a staggered structure, an inversely staggered structure, a structure where a channel region is divided into a plurality of regions, or a structure where channel regions are connected in parallel or in series can be employed. In addition, a source electrode or a drain electrode may overlap with a channel region (or part thereof). By using the structure where the source electrode or the drain electrode may overlap with the channel region (or part thereof), an unstable operation due to accumulation of charge in part of the channel region can be prevented. Further, a structure where an LDD region is provided may be employed. By providing the LDD region, off-current can be reduced or the withstand voltage of the transistor can be increased to improve reliability. Alternatively, drain-source current does not fluctuate much even if drain-source voltage fluctuates when the transistor operates in the saturation region, so that characteristics where a slope of voltage-current characteristics is flat can be obtained.

Note that various types of transistors can be used for a transistor, and the transistor can be formed using various types of substrates. Accordingly, all of circuits which are necessary to realize a predetermined function can be formed using the same substrate. For example, all of the circuits which are necessary to realize the predetermined function can be formed using various substrates such as a glass substrate,

a plastic substrate, a single crystalline substrate, or an SOI substrate. When all of the circuits which are necessary to realize the predetermined function are formed using the same substrate, cost can be reduced by reduction in the number of component parts or reliability can be improved by reduction in the number of connections between circuit components. Alternatively, part of the circuits which are necessary to realize the predetermined function may be formed using one substrate and another part of the circuits which are necessary to realize the predetermined function may be formed using another substrate. That is, not all of the circuits which are necessary to realize the predetermined function are required to be formed using the same substrate. For example, part of the circuits which are necessary to realize the predetermined function may be formed using transistors over a glass substrate and another part of the circuits which are necessary to realize the predetermined function may be formed using a single crystalline substrate, so that an IC chip formed by a transistor on the single crystalline substrate can be connected to the glass substrate by COG (Chip On Glass) and the IC chip may be provided over the glass substrate. Alternatively, the IC chip can be connected to the glass substrate by TAB (Tape Automated Bonding) or a printed wiring board. When part of the circuits are formed using the same substrate in this manner, cost can be reduced by reduction in the number of component parts or reliability can be improved by reduction in the number of connections between circuit components. Alternatively, since circuits in a portion with high driving voltage or a portion with high driving frequency consume large power, the circuits in such portions are formed using a single crystalline substrate and using an IC chip formed by the circuit instead of using the same substrate, for example; thus, increase in power consumption can be prevented.

Note that one pixel corresponds to one element brightness of which can be controlled. For example, one pixel corresponds to one color element and brightness is expressed with the one color element. Accordingly, in the case of a color display device having color elements of R (Red), G (Green), and B (Blue), the smallest unit of an image is formed of three pixels of an R pixel, a G pixel, and a B pixel. Note that the color elements are not limited to three colors, and color elements of more than three colors may be used and/or a color other than RGB may be used. For example, RGBW can be employed by adding W (white). In addition, RGB added with one or more colors of yellow, cyan, magenta, emerald green, vermilion, and the like may be used. Further, a color similar to at least one of R, G, and B may be added to RGB. For example, R, G, B1, and B2 may be used. Although both B1 and B2 are blue, they have slightly different frequency. Similarly, R1, R2, G, and B may be used. By using such color elements, display which is closer to the real object can be performed and power consumption can be reduced. As another example, in the case of controlling brightness of one color element by using a plurality of regions, one region may correspond to one pixel. For example, in the case of performing area ratio gray scale display or the case of including a subpixel, a plurality of regions which control brightness are provided in each color element and gray scales are expressed with all of the regions, and one region which controls brightness may correspond to one pixel. In that case, one color element includes a plurality of pixels. Alternatively, even when the plurality of the regions which control brightness are provided in one color element, these regions may be collected and one color element may be referred to as one pixel. In that case, one color element includes one pixel. Further, when brightness is controlled by a plurality of regions in one color element, regions which contribute to display may have dif-

ferent area dimensions depending on pixels. Alternatively, in the plurality of the regions which control brightness in one color element, signals supplied to the regions may be slightly varied to widen a viewing angle. That is, potentials of pixel electrodes included in the plurality of the regions in one color element may be different from each other. Accordingly, voltages applied to liquid crystal molecules are varied depending on the pixel electrodes. Therefore, the viewing angle can be widened.

Note that when it is explicitly described as one pixel (for three colors), it corresponds to the case where three pixels of R, G, and B are considered as one pixel. When it is explicitly described as one pixel (for one color), it corresponds to the case where the plurality of the regions are provided in each color element and collectively considered as one pixel.

Note that pixels are provided (arranged) in matrix in some cases. Here, description that pixels are provided (arranged) in matrix includes the case where the pixels are arranged in a straight line and the case where the pixels are arranged in a jagged line, in a longitudinal direction or a lateral direction. For example, in the case of performing full color display with three color elements (e.g., RGB), the following cases are included therein: the case where the pixels are arranged in stripes, the case where dots of the three color elements are arranged in a delta pattern, and the case where dots of the three color elements are provided in Bayer arrangement. Note that the color elements are not limited to three colors, and color elements of more than three colors may be employed, for example, RGBW (W corresponds to white), RGB added with one or more of yellow, cyan, magenta, and the like, or the like. Note that the size of display regions may be different between respective dots of color elements. Thus, power consumption can be reduced or the life of a light-emitting element can be prolonged.

Note that an active matrix method in which an active element is included in a pixel or a passive matrix method in which an active element is not included in a pixel can be used.

In the active matrix method, as an active element (a non-linear element), not only a transistor but also various active elements (non-linear elements), for example, a MIM (Metal Insulator Metal), a TFD (Thin Film Diode), or the like can be used. Since such an element has few number of manufacturing steps, manufacturing cost can be reduced or a yield can be improved. Since the size of the element is small, an aperture ratio can be increased, and power consumption can be reduced and high luminance can be achieved.

As a method other than the active matrix method, the passive matrix method in which an active element (a non-linear element) is not used can also be used. Since an active element (a non-linear element) is not used, the number of manufacturing steps is small, so that manufacturing cost can be reduced or the yield can be improved. Further, since an active element (a non-linear element) is not used, the aperture ratio can be increased, and power consumption can be reduced and high luminance can be achieved.

Note that a transistor is an element having at least three terminals of a gate, a drain, and a source. The transistor includes a channel region between a drain region and a source region, and current can flow through the drain region, the channel region, and the source region. Here, since the source and the drain of the transistor may change depending on a structure, operating conditions, and the like of the transistor, it is difficult to define which is a source or a drain. Therefore, in this document (the specification, the claim, the drawing, and the like), a region functioning as a source and a drain is not called the source or the drain in some cases. In such a case, one of the source and the drain may be referred to as a first

terminal and the other thereof may be referred to as a second terminal, for example. Alternatively, one of the source and the drain may be referred to as a first electrode and the other thereof may be referred to as a second electrode. Further alternatively, one of the source and the drain may be referred to as a source region and the other thereof may be referred to as a drain region.

In addition, a transistor may be an element having at least three terminals of a base, an emitter, and a collector. In this case also, one of the emitter and the collector may be referred to as a first terminal and the other terminal may be referred to as a second terminal.

A gate corresponds to all or part of a gate electrode and a gate wiring (also referred to as a gate line, a gate signal line, a scan line, a scan signal line, or the like). A gate electrode corresponds to a conductive film which overlaps with a semiconductor forming a channel region with a gate insulating film interposed therebetween. Note that part of the gate electrode overlaps with an LDD (Lightly Doped Drain) region or the source region (or the drain region) with the gate insulating film interposed therebetween in some cases. A gate wiring corresponds to a wiring for connecting a gate electrode of each transistor to each other, a wiring for connecting a gate electrode included in each pixel to each other, or a wiring for connecting a gate electrode to another wiring.

However, there is a portion (a region, a conductive film, a wiring, or the like) which functions as both a gate electrode and a gate wiring. Such a portion (a region, a conductive film, a wiring, or the like) may be called either a gate electrode or a gate wiring. That is, there is a region where a gate electrode and a gate wiring cannot be clearly distinguished from each other. For example, in the case where a channel region overlaps with part of an extended gate wiring, the overlapped portion (region, conductive film, wiring, or the like) functions as both a gate wiring and a gate electrode. Accordingly, such a portion (a region, a conductive film, a wiring, or the like) may be called either a gate electrode or a gate wiring.

Note that a portion (a region, a conductive film, a wiring, or the like) which is formed of the same material as a gate electrode and forms the same island as the gate electrode to be connected to the gate electrode may also be called a gate electrode. Similarly, a portion (a region, a conductive film, a wiring, or the like) which is formed of the same material as a gate wiring and forms the same island as the gate wiring to be connected to the gate wiring may also be called a gate wiring. In a strict sense, such a portion (a region, a conductive film, a wiring, or the like) does not overlap with a channel region or does not have a function to connect the gate electrode to another gate electrode in some cases. However, there is a portion (a region, a conductive film, a wiring, or the like) which is formed of the same material as a gate electrode or a gate wiring and forms the same island as the gate electrode or the gate wiring to be connected to the gate electrode or the gate wiring in relation to a circuit structure and the like. Thus, such a portion (a region, a conductive film, a wiring, or the like) may also be called either a gate electrode or a gate wiring.

In a multi-gate transistor, for example, a gate electrode of one transistor is often connected to a gate electrode of another transistor by using a conductive film which is formed of the same material as the gate electrode. Since such a portion (a region, a conductive film, a wiring, or the like) is a portion (a region, a conductive film, a wiring, or the like) for connecting the gate electrode and another gate electrode, it may be called a gate wiring, and it may also be called a gate electrode since a multi-gate transistor can be considered as one transistor. That is, a portion (a region, a conductive film, a wiring, or the

like) which is formed of the same material as a gate electrode or a gate wiring and forms the same island as the gate electrode or the gate wiring to be connected to the gate electrode or the gate wiring may be called either a gate electrode or a gate wiring. In addition, part of a conductive film which connects the gate electrode and the gate wiring and is formed of a material different from that of the gate electrode and the gate wiring may also be called either a gate electrode or a gate wiring.

Note that a gate terminal corresponds to part of a portion (a region, a conductive film, a wiring, or the like) of a gate electrode or a portion (a region, a conductive film, a wiring, or the like) which is electrically connected to the gate electrode.

When a gate electrode is called a gate wiring, a gate line, a gate signal line, a scan line, a scan signal line, or the like, there is the case where a gate of a transistor is not connected to a wiring. In this case, the gate wiring, the gate line, the gate signal line, the scan line, or the scan signal line corresponds to a wiring formed in the same layer as the gate of the transistor, a wiring formed of the same material of the gate of the transistor, or a wiring formed at the same time as the gate of the transistor in some cases. As examples, a wiring for storage capacitance, a power supply line, a reference potential supply line, and the like can be given.

A source corresponds to all or part of a source region, a source electrode, and a source wiring (also referred to as a source line, a source signal line, a data line, a data signal line, or the like). A source region corresponds to a semiconductor region containing a large amount of p-type impurities (e.g., boron or gallium) or n-type impurities (e.g., phosphorus or arsenic). Accordingly, a region containing a small amount of p-type impurities or n-type impurities, namely, an LDD (Lightly Doped Drain) region is not included in the source region. A source electrode is part of a conductive layer formed of a material different from that of a source region and electrically connected to the source region. However, there is the case where a source electrode and a source region are collectively called a source electrode. A source wiring is a wiring for connecting a source electrode of each transistor to each other, a wiring for connecting a source electrode of each pixel to each other, or a wiring for connecting a source electrode to another wiring.

However, there is a portion (a region, a conductive film, a wiring, or the like) functioning as both a source electrode and a source wiring. Such a portion (a region, a conductive film, a wiring, or the like) may be called either a source electrode or a source wiring. That is, there is a region where a source electrode and a source wiring cannot be clearly distinguished from each other. For example, in the case where a source region overlaps with part of an extended source wiring, the overlapped portion (region, conductive film, wiring, or the like) functions as both a source wiring and a source electrode. Accordingly, such a portion (a region, a conductive film, a wiring, or the like) may be called either a source electrode or a source wiring.

A portion (a region, a conductive film, a wiring, or the like) which is formed of the same material as a source electrode and forms the same island as the source electrode to be connected to the source electrode, or a portion (a region, a conductive film, a wiring, or the like) which connects a source electrode and another source electrode may also be called a source electrode. Further, a portion which overlaps with a source region may be called a source electrode. Similarly, a region which is formed of the same material as a source wiring and forms the same island as the source wiring to be connected to the source wiring may also be called a source wiring. In a strict sense, such a portion (a region, a conductive

film, a wiring, or the like) does not overlap with a channel region or does not have a function to connect the source electrode to another source electrode in some cases. However, there is a portion (a region, a conductive film, a wiring, or the like) which is formed of the same material as a source electrode or a source wiring and forms the same island as the source electrode or the source wiring to be connected to the source electrode or the source wiring in relation to a circuit structure and the like. Thus, such a portion (a region, a conductive film, a wiring, or the like) may also be called either a source electrode or a source wiring.

For example, part of a conductive film which connects a source electrode and a source wiring and is formed of a material which is different from that of the source electrode or the source wiring may be called either a source electrode or a source wiring.

A source terminal corresponds to part of a source region, a source electrode, or a portion (a region, a conductive film, a wiring, or the like) which is electrically connected to the source electrode.

When a source electrode is called a source wiring, a source line, a source signal line, a data line, a data signal line, or the like, there is the case in which a source (a drain) of a transistor is not connected to a wiring. In this case, the source wiring, the source line, the source signal line, the data line, or the data signal line corresponds to a wiring formed in the same layer as the source (drain) of the transistor, a wiring formed of the same material of the source (drain) of the transistor, or a wiring formed at the same time as the source (drain) of the transistor in some cases. As examples, a wiring for storage capacitance, a power supply line, a reference potential supply line, and the like can be given.

Note that a drain is similar to the source.

Note that a semiconductor device corresponds to a device having a circuit including a semiconductor element (e.g., a transistor, a diode, or a thyristor). The semiconductor device may also refer to all devices which can function by utilizing semiconductor characteristics. Alternatively, the semiconductor device refers to a device including a semiconductor material.

A display element corresponds to an optical modulation element, a liquid crystal element, a light-emitting element, an EL element (an organic EL element, an inorganic EL element, or an EL element including both organic and inorganic materials), an electron emitter, an electrophoresis element, a discharging element, a light-reflecting element, a light diffraction element, a digital micro device (DMD), or the like. Note that the present invention is not limited thereto.

A display device corresponds to a device including a display element. The display device may include a plurality of pixels having a display element. The display device may include a peripheral driver circuit for driving a plurality of pixels. The peripheral driver circuit for driving a plurality of pixels may be formed over the same substrate as the plurality of pixels. In addition, the display device may also include a peripheral driver circuit provided over a substrate by wire bonding or bump bonding, namely, an IC chip connected by so-called chip on glass (COG), TAB, or the like. Further, the display device may also include a flexible printed circuit (FPC) to which an IC chip, a resistor, a capacitor, an inductor, a transistor, or the like is attached. The display device may also include a printed wiring board (PWB) which is connected through a flexible printed circuit (FPC) and to which an IC chip, a resistor, a capacitor, an inductor, a transistor, or the like is attached. The display device may also include an optical sheet such as a polarizing plate or a retardation plate. The display device may also include a lighting device, a

housing, an audio input and output device, a light sensor, or the like. Here, a lighting device such as a backlight unit may include a light guide plate, a prism sheet, a diffusion sheet, a reflective sheet, a light source (e.g., an LED or a cold cathode fluorescent lamp), a cooling device (e.g., a water cooling device or an air cooling device), or the like.

A lighting device corresponds to a device including a backlight unit, a light guide plate, a prism sheet, a diffusion sheet, a reflective sheet, a light source (e.g., an LED, a cold cathode fluorescent lamp, or a hot cathode fluorescent lamp), a cooling device, or the like.

A light-emitting device corresponds to a device including a light-emitting element or the like. A light-emitting device including a light-emitting element as a display element is a specific example of a display device.

A reflective device corresponds to a device including a light-reflecting element, a light diffraction element, a light reflecting electrode, or the like.

A liquid crystal display device corresponds to a display device including a liquid crystal element. Liquid crystal display devices include a direct-view liquid crystal display, a projection liquid crystal display, a transmissive liquid crystal display, a reflective liquid crystal display, a transreflective liquid crystal display, and the like.

A driving device corresponds to a device including a semiconductor element, an electric circuit, or an electronic circuit. Examples of the driving device include a transistor (also referred to as a selection transistor, a switching transistor, or the like) which controls input of a signal from a source signal line to a pixel, a transistor which supplies voltage or current to a pixel electrode, a transistor which supplies voltage or current to a light-emitting element, and the like. Moreover, examples of the driving device include a circuit (also referred to as a gate driver, a gate line driver circuit, or the like) which supplies a signal to a gate signal line, a circuit (also referred to as a source driver, a source line driver circuit, or the like) which supplies a signal to a source signal line, and the like.

A display device, a semiconductor device, a lighting device, a cooling device, a light-emitting device, a reflective device, a driving device, and the like overlap with each other in some cases. For example, a display device includes a semiconductor device and a light-emitting device in some cases. Further, a semiconductor device includes a display device and a driving device in some cases.

When it is explicitly described that B is formed on A or that B is formed over A, it does not necessarily mean that B is formed in direct contact with A. The description includes the case where A and B are not in direct contact with each other, that is, the case where another object is interposed between A and B. Here, each of A and B corresponds to an object (e.g., a device, an element, a circuit, a wiring, an electrode, a terminal, a conductive film, or a layer).

For example, when it is explicitly described that a layer B is formed on (or over) a layer A, it includes both the case where the layer B is formed in direct contact with the layer A, and the case where another layer (e.g., a layer C or a layer D) is formed in direct contact with the layer A and the layer B is formed in direct contact with the layer C or D. Note that another layer (e.g., a layer C or a layer D) may be a single layer or a plurality of layers.

Similarly, when it is explicitly described that B is formed above A, it does not necessarily mean that B is in direct contact with A, and another object may be interposed between A and B. For example, when it is explicitly described that a layer B is formed above a layer A, it includes both the case where the layer B is formed in direct contact with the layer A, and the case where another layer (e.g., a layer C or a layer D)

is formed in direct contact with the layer A and the layer B is formed in direct contact with the layer C or D. Note that another layer (e.g., a layer C or a layer D) may be a single layer or a plurality of layers.

When it is explicitly described that B is formed in direct contact with A, it does not include the case where another object is interposed between A and B and includes the case where B is formed in direct contact with A.

Note that the same can be said when it is explicitly described that B is formed below or under A.

Note that explicit singular forms are preferably singular forms. However, without being limited thereto, such singular forms can include plural forms. Similarly, explicit plural forms are preferably plural forms. However, without being limited thereto, such plural forms can include singular forms.

The structures applicable to a liquid crystal display device and a semiconductor device of the invention are described above. The structures described above may be applied to a liquid crystal display device and a semiconductor device of the invention when needed.

According to the invention, a liquid crystal display device with a wide viewing angle and lower manufacturing cost than a conventional liquid crystal display device can be provided.

Since a conductive film is formed over an entire surface of a substrate in the invention, an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a liquid crystal display device with high reliability and a semiconductor device including the liquid crystal display device can be obtained.

In the invention, when a semiconductor device including a top-gate thin film transistor is formed, a potential of a back gate is stabilized; thus, a liquid crystal display device with high reliability and a semiconductor device including the liquid crystal display device can be obtained.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 is a cross-sectional view showing a structure example of a pixel portion using a top-gate thin film transistor.

FIG. 2 is a cross-sectional view showing a structure example of a pixel portion using a bottom-gate thin film transistor.

FIG. 3 is a cross-sectional view showing a structure example of a pixel portion using a top-gate thin film transistor.

FIG. 4 is a top plan view of the pixel portion shown in FIGS. 1 and 3.

FIG. 5 is a cross-sectional view of a liquid crystal display device of the invention.

FIG. 6 is a cross-sectional view of a liquid crystal display device of the invention.

FIG. 7 is a top plan view of a liquid crystal display device of the invention.

FIGS. 8A to 8D are top plan views of a liquid crystal display device of the invention.

FIGS. 9A to 9D are top plan views of a liquid crystal display device of the invention.

FIG. 10 is a cross-sectional view of a liquid crystal display device of the invention.

FIG. 11 is a top plan view of a liquid crystal display device of the invention.

FIG. 12 is a cross-sectional view of a liquid crystal display device of the invention.

FIG. 13 is a top plan view of a liquid crystal display device of the invention.

FIG. 14A is a top plan view of a liquid crystal display device of the invention, and FIG. 14B is a cross-sectional view thereof.

FIGS. 15A to 15D are cross-sectional views showing manufacturing steps of a liquid crystal display device of the invention.

FIGS. 16A to 16C are cross-sectional views showing manufacturing steps of a liquid crystal display device of the invention.

FIGS. 17A to 17C are cross-sectional views showing manufacturing steps of a liquid crystal display device of the invention.

FIG. 18 is a cross-sectional view showing a manufacturing step of a liquid crystal display device of the invention.

FIGS. 19A and 19B are circuit diagrams of a liquid crystal display device of the invention.

FIGS. 20A and 20B are circuit diagrams of a liquid crystal display device of the invention.

FIGS. 21A to 21H show examples of electronic devices each formed by using a liquid crystal display device of the invention.

FIG. 22 is a cross-sectional view of a liquid crystal display device of the invention.

FIGS. 23A and 23B are top plan views of a liquid crystal display device of the invention.

FIG. 24 is a cross-sectional view of a liquid crystal display device of the invention.

FIG. 25 is a cross-sectional view of a liquid crystal display device of the invention.

FIG. 26 is a cross-sectional view of a liquid crystal display device of the invention.

FIG. 27 is a top plan view of a liquid crystal display device of the invention.

FIG. 28 shows a liquid crystal display device of the invention.

FIGS. 29A to 29G are cross-sectional views showing transistors according to the invention.

FIG. 30 is a cross-sectional view showing a transistor according to the invention.

FIG. 31 is a cross-sectional view showing a transistor according to the invention.

FIG. 32 is a cross-sectional view showing a transistor according to the invention.

FIG. 33 is a cross-sectional view showing a transistor according to the invention.

FIGS. 34A to 34C show structures of a display device according to the invention.

FIGS. 35A and 35B show structures of a display device according to the invention.

FIG. 36 shows a structure of a display device according to the invention.

FIG. 37 shows one driving method of a display device according to the invention.

FIG. 38 shows one driving method of a display device according to the invention.

FIGS. 39A and 39B each show one driving method of a display device according to the invention.

FIG. 40 is a cross-sectional view of a liquid crystal display device according to the invention.

FIGS. 41A to 41D are cross-sectional views of a liquid crystal display device according to the invention.

FIG. 42 is a cross-sectional view of a liquid crystal display device according to the invention.

FIGS. 43A to 43C each show a structure of a liquid crystal display device according to the invention.

FIG. 44 is a cross-sectional view of a liquid crystal display device according to the invention.

FIGS. 45A and 45B are circuit diagrams of a pixel according to the invention.

FIG. 46 is a circuit diagram of a pixel according to the invention.

FIG. 47 is a circuit diagram of a pixel according to the invention.

FIGS. 48A to 48E each show one driving method of a liquid crystal display device according to the invention.

FIGS. 49A and 49B each show one driving method of a liquid crystal display device according to the invention.

FIGS. 50A to 50C each show one driving method of a liquid crystal display device according to the invention.

FIGS. 51A to 51C each show one driving method of a liquid crystal display device according to the invention.

FIGS. 52A to 52C each show one driving method of a liquid crystal display device according to the invention.

FIGS. 53A and 53B show a structure of a display device according to the invention.

FIG. 54 shows a structure of a display device according to the invention.

FIG. 55 shows a structure of a display device according to the invention.

FIG. 56 shows a structure of a display device according to the invention.

FIGS. 57A to 57C each show a structure of a display device according to the invention.

FIG. 58 shows an electronic device according to the invention.

FIG. 59 shows an electronic device according to the invention.

FIGS. 60A and 60B each show an electronic device according to the invention.

FIG. 61 shows an electronic device according to the invention.

FIGS. 62A to 62C each show an electronic device according to the invention.

FIG. 63 shows an electronic device according to the invention.

FIG. 64 shows an electronic device according to the invention.

FIG. 65 shows an electronic device according to the invention.

FIG. 66 shows an electronic device according to the invention.

FIGS. 67A and 67B show an electronic device according to the invention.

FIGS. 68A and 68B show an electronic device according to the invention.

FIGS. 69A to 69C each show an electronic device according to the invention.

FIGS. 70A and 70B each show an electronic device according to the invention.

FIG. 71 shows an electronic device according to the invention.

DETAILED DESCRIPTION OF THE INVENTION

Hereinafter, embodiment modes of the present invention will be described with reference to drawings. However, the present invention can be implemented in various modes, and it is easily understood by those skilled in the art that modes and details can be variously changed without departing from the scope and the spirit of the present invention. Therefore, the present invention is not construed as being limited to description of the embodiment modes. Note that in the drawings shown below, the same portions or portions having simi-

lar functions are denoted by the same reference numerals, and repeated description is omitted.

Embodiment Mode 1

This embodiment mode is described with reference to FIGS. 1 and 3 to 5.

FIG. 1 shows an example where a top-gate thin film transistor (TFT) is used as a switching element in a pixel portion. A conductive film 115 to be a first electrode in FFS (Fringe-Field Switching) drive is formed over an entire surface of one side of a substrate 101.

A light-transmitting conductive film is used as the conductive film 115. As such a light-transmitting conductive film, an indium tin oxide (ITO) film, an indium zinc oxide (IZO) film, an indium tin oxide containing silicon (also referred to as ITSO) film, a zinc oxide (ZnO) film, a cadmium tin oxide (CTO) film, a tin oxide (SnO) film, or the like may be used.

A base film 102 is formed over the conductive film 115, and a thin film transistor (TFT) 121 is formed over the base film 102. The TFT 121 includes a region 131a which is one of a source region and a drain region, a region 131b which is the other of the source region and the drain region, an active layer 103 including a channel formation region 132, a gate insulating film 104, and a gate electrode 105. Note that although the gate insulating film 104 in FIG. 1 is formed only above the channel formation region 132, it may be formed over portions other than above the channel formation region 132.

An interlayer insulating film 106 is formed over the TFT 121 and the base film 102. An electrode 107 (a source wiring) which is electrically connected to one of the source region and the drain region through a contact hole in the interlayer insulating film 106, and an electrode 108 which is electrically connected to the other of the source region and the drain region through a contact hole in the interlayer insulating film 106 are formed over the interlayer insulating film 106.

An interlayer insulating film 111 is formed over the interlayer insulating film 106, the electrodes 107 and 108, and an electrode 109. Further, pixel electrodes 113 and 114a to 114c which are electrically connected to the electrode 108 through a contact hole formed in the interlayer insulating film 111 are formed over the interlayer insulating film 111. Note that the pixel electrode 113 may be electrically connected to the electrode 107, not to the electrode 108. In addition, only one of the interlayer insulating films 106 and 111 may be formed.

As shown in FIG. 1, an electric field 125 is generated between the pixel electrodes 113 and 114 (114a to 114c) and the conductive film 115. As described below, liquid crystal molecules are driven by the electric field 125.

Further, as shown in FIG. 3, the conductive film 115 is electrically connected to the connection electrode 109 through a contact hole in the interlayer insulating film 106 and the base film 102, and the connection electrode 109 is electrically connected to a wiring 119. Note that the wiring 119 is formed of the same material and in the same step as the gate electrode 105. The connection electrode 109 is formed of the same material and in the same step as the electrodes 107 and 108. Thus, they can be formed without adding a manufacturing step, so that the number of photomasks can be reduced. Note that the same portions in FIGS. 1 and 3 are denoted by the same reference numerals.

Note that the wiring 119 may be arranged in parallel to the gate electrode 105. When the wiring 119 is arranged in parallel to the gate electrode 105, decrease in aperture ratio is reduced.

When the wiring 119 is connected to the conductive film 115 for each pixel, resistance of the conductive film 115 can be reduced. Further, waveform distortion can be reduced.

In addition, the connection electrode 109 may be extended across the pixels, without being connected to the wiring 119. In this case, the connection electrode 109 is preferably arranged in parallel to the source wiring 107.

FIG. 4 is a top plan view of FIGS. 1 and 3. FIG. 3 is a cross-sectional view along A-A' and B-B' of FIG. 4. FIG. 1 is a cross-sectional view along A-A' of FIG. 4. The pixel electrodes 113 and 114a to 114c, and the like are provided with grooves (also referred to as openings, slits, apertures, gaps, or spaces) 117.

As shown in FIG. 4, a plurality of source wirings 107 are provided in parallel to each other (extended in a vertical direction in the drawing) and apart from each other. A plurality of gate wirings 105 are extended in a direction generally perpendicular to the source wirings 107 (a horizontal direction in the drawing) and provided apart from each other. The wiring 119 is adjacent to the plurality of gate wirings 105 and extended in a direction parallel to the gate wirings 105, that is, a direction perpendicular to the source wirings 107 (the horizontal direction in the drawing). By such arrangement, an aperture ratio can be increased. A space with a generally rectangular shape, which is surrounded by the source wirings 107, the wiring 119, and the gate wiring 105, is provided with the pixel electrode 113 of a liquid crystal display device. The thin film transistor 121 for driving the pixel electrode 113 is provided at an upper left corner of the drawing. The plurality of pixel electrodes and thin film transistors are arranged in matrix.

Note that in this embodiment mode, the wiring 119 and the conductive film 115 are connected to each pixel through contact holes; however, the invention is not limited thereto.

Note that the wiring 119 is provided in FIG. 4; FIG. 27 shows an example where the gate wiring 105 is used instead of the wiring 119. A cross-sectional view of FIG. 27 is the same as FIG. 3, except that the wiring 119 is the same wiring as the gate wiring 105.

Note that each of the gate wiring 105, the wiring 119, and the source wiring 107 is preferably formed of one or more elements selected from aluminum (Al), tantalum (Ta), titanium (Ti), molybdenum (Mo), tungsten (W), neodymium (Nd), chromium (Cr), nickel (Ni), platinum (Pt), gold (Au), silver (Ag), copper (Cu), magnesium (Mg), scandium (Sc), cobalt (Co), zinc (Zn), niobium (Nb), silicon (Si), phosphorus (P), boron (B), arsenic (As), gallium (Ga), indium (In), tin (Sn), and oxygen (O); or a compound or an alloy material including one or more of the aforementioned elements (e.g., indium tin oxide (ITO), indium zinc oxide (IZO), indium tin oxide containing silicon (ITSO), zinc oxide (ZnO), tin oxide (SnO), cadmium tin oxide (CTO), aluminum neodymium (Al—Nd), magnesium silver (Mg—Ag), or molybdenum-niobium (Mo—Nb)); a substance in which these compounds are combined; or the like. Alternatively, each of the gate wiring 105, the wiring 119, and the source wiring 107 is preferably formed to contain a substance including a compound (silicide) of silicon and one or more of the aforementioned elements (e.g., aluminum silicon, molybdenum silicon, or nickel silicide); or a compound of nitrogen and one or more of the aforementioned elements (e.g., titanium nitride, tantalum nitride, or molybdenum nitride).

Note that silicon (Si) may contain an n-type impurity (such as phosphorus) or a p-type impurity (such as boron). When silicon contains the impurity, the conductivity is increased,

and a function similar to a general conductor can be realized. Thus, such silicon can be utilized easily as a wiring, an electrode, or the like.

In addition, silicon with various levels of crystallinity, such as single crystalline silicon, polycrystalline silicon, or micro-crystalline silicon can be used. Alternatively, silicon having no crystallinity, such as amorphous silicon can be used. By using single crystalline silicon or polycrystalline silicon, resistance of a wiring, an electrode, a conductive layer, a conductive film, a terminal, or the like can be reduced. By using amorphous silicon or microcrystalline silicon, a wiring or the like can be formed by a simple process.

Aluminum and silver have high conductivity, and thus can reduce a signal delay. Further, since aluminum and silver can be easily etched, they can be minutely processed.

Copper has high conductivity, and thus can reduce a signal delay. When copper is used, a stacked-layer structure is preferably employed to improve adhesion.

Molybdenum and titanium are preferable since even if molybdenum or titanium is in contact with an oxide semiconductor (e.g., ITO or IZO) or silicon, molybdenum or titanium does not cause defects. Further, molybdenum and titanium are preferable since they are easily etched and has high heat resistance.

Tungsten is preferable since it has an advantage such as high heat resistance.

Neodymium is also preferable since it has an advantage such as high heat resistance. In particular, an alloy of neodymium and aluminum is preferable since heat resistance is increased and aluminum hardly causes hillocks.

Silicon is preferable since it can be formed at the same time as a semiconductor layer included in a transistor and has high heat resistance.

Since ITO, IZO, ITSO, zinc oxide (ZnO), silicon (Si), tin oxide (SnO), and cadmium tin oxide (CTO) have light-transmitting properties, they can be used as a portion which transmits light. For example, they can be used for a pixel electrode or a common electrode.

IZO is preferable since it is easily etched and processed. In etching IZO, a residue is hardly left. Thus, when IZO is used for a pixel electrode, defects (such as short circuit or orientation disorder) of a liquid crystal element or a light-emitting element can be reduced.

A wiring, an electrode, a conductive layer, a conductive film, a terminal, or the like may have a single-layer structure or a multi-layer structure. By employing a single-layer structure, each manufacturing process of a wiring, an electrode, a conductive layer, a conductive film, a terminal, or the like can be simplified, the number of days for a process can be reduced, and cost can be reduced. Alternatively, by employing a multi-layer structure, a wiring, an electrode, and the like with high quality can be formed while an advantage of each material is utilized and a disadvantage thereof is reduced. For example, when a low-resistant material (e.g., aluminum) is included in a multi-layer structure, reduction in resistance of a wiring can be realized. Further, when a stacked-layer structure where a low heat-resistant material is interposed between high heat-resistant materials is employed, heat resistance of a wiring, an electrode, and the like can be increased, utilizing advantages of the low heat-resistance material. For example, it is preferable to employ a stacked-layer structure where a layer containing aluminum is interposed between layers containing molybdenum, titanium, neodymium, or the like.

When wirings, electrodes, or the like are in direct contact with each other, they adversely affect each other in some cases. For example, one wiring or one electrode is mixed into a material of another wiring or another electrode and changes

its properties, and thus, an intended function cannot be obtained in some cases. As another example, when a high-resistant portion is formed, a problem may occur so that it cannot be normally formed. In such cases, a reactive material is preferably interposed by or covered with a non-reactive material in a stacked-layer structure. For example, when ITO and aluminum are connected, titanium, molybdenum, or an alloy of neodymium is preferably interposed between ITO and aluminum. As another example, when silicon and aluminum are connected, titanium, molybdenum, or an alloy of neodymium is preferably interposed between silicon and aluminum.

Note that the term "wiring" indicates a portion including a conductor. A wiring may be provided linearly or may be short without being extended linearly. Therefore, an electrode is included in a wiring.

Note that the gate wiring **105** is preferably formed of a material with higher heat resistance than that of the source wiring **107**. This is because the gate wiring **105** is more likely to be exposed to a high temperature in manufacturing steps than the source wiring **107**.

In addition, the source wiring **107** is preferably formed of a material with lower resistance than that of the gate wiring **105**. This is because only signals with two values, which is an H-level signal and an L-level signal, are supplied to the gate wiring **105**, whereas an analog signal which contributes to display is supplied to the source wiring **107**. Accordingly, a material with low resistance is preferably used for the source wiring **107** in order that an accurate signal is supplied to the source wiring **107**.

Note that although the wiring **119** does not have to be provided, a potential of a common electrode in each pixel can be stabilized when the wiring **119** is provided. Note also that the wiring **119** is provided in parallel to the gate wiring in FIG. 4; however, the invention is not limited thereto. The wiring **119** may be provided in parallel to the source wiring **107**. At this time, the wiring **119** is preferably formed of the same material as the source wiring **107**.

Since an aperture ratio can be increased and layout can be efficiently performed, the wiring is preferably parallel to the gate wiring.

The substrate **101** is a glass substrate, a quartz substrate, a substrate formed of an insulator such as alumina, a plastic substrate with heat resistance high enough to withstand a processing temperature of subsequent steps, a single crystalline substrate (e.g., a single crystalline silicon substrate), an SOI substrate, or a metal plate. Alternatively, the substrate **101** may be formed of polycrystalline silicon.

When a display device operates as a transmissive display device, the substrate **101** is preferably has a light-transmitting property.

The conductive film **115** is formed of a conductive film with a light-transmitting property (e.g., an indium tin oxide (ITO) film, an indium zinc oxide (IZO) film, a zinc oxide (ZnO) film, a tin oxide (SnO) film, or a polycrystalline silicon film or an amorphous silicon film into which an impurity is introduced).

An insulating film is formed as the base film **102** over the conductive film **115**. The insulating film **102** is for preventing impurities from the substrate **101** from being diffused, and functions as the base film. The insulating film **102** is formed of an insulating material containing oxygen or nitrogen, such as silicon oxide (SiO_x), silicon nitride (SiN_x), silicon oxide containing nitrogen (SiO_xN_y: x>y), or silicon nitride containing oxygen (SiN_xO_y: x>y). Alternatively, the insulating film **102** may be a stacked-layer film in which a plurality of these films are stacked. Note that an insulating film having the

same function as the insulating film 102 may be provided between the substrate 101 and the conductive film 115.

For example, a stacked-layer film of a silicon nitride film and a silicon oxide film; or a single-layer film of a silicon oxide film may be used as the base film 102. It is useful to use a silicon oxide film which is thicker than the gate insulating film 104 as the base film 102 because capacitive coupling with the gate wiring 105 can be reduced. Accordingly, the base film 102 is preferably thicker than, more preferably three times thicker than, the gate insulating film 104.

The semiconductor film 103 is formed over the insulating film 102. The region 131a to be one of the source region and the drain region, and the region 131b to be the other of the source region and the drain region are formed in the semiconductor film 103. The regions 131a and 131b are n-type impurity regions, for example, but may be p-type impurity regions. As an impurity imparting n-type conductivity, phosphorus (P) or arsenic (As) is used, for example. As an impurity imparting p-type conductivity, boron (B) or gallium (Ga) is used, for example. The channel formation region 132 is formed between the regions 131a and 131b.

Further, low concentration impurity regions may be formed between the region 131a and the channel formation region 132, and the region 131b and the channel formation region 132.

As shown in FIG. 4, the conductive film 115 is formed over almost the entire surface of the pixel. Each rectangular region surrounded by the source wirings 107, the wiring 119, and the gate wiring 105, is provided with the thin film transistor 121. That is, the gate wiring 105 is formed as a first wiring, the source wiring 107 is formed as a second wiring, and the wiring 119 is formed as a third wiring. By provision of the thin film transistor 121, a region which is effective for display in the pixel can be formed more efficiently. In other words, an aperture ratio can be increased. Note that the semiconductor film 103 is a polycrystalline silicon film, for example, but may be another semiconductor film (e.g., an amorphous silicon film, a single crystalline silicon film, an organic semiconductor film, or a carbon nanotube) or a microcrystalline silicon film (also referred to as a semi-amorphous silicon film).

Here, a semi-amorphous semiconductor film typified by a semi-amorphous silicon film includes a semiconductor having an intermediate structure between an amorphous semiconductor film and a semiconductor film having a crystalline structure (including single crystal and polycrystalline). A semi-amorphous semiconductor film is a semiconductor film having a third state which is stable in free energy, is a crystalline substance with a short-range order and lattice distortion, and can be dispersed in a non-single crystalline semiconductor film with a grain size of 0.5 to 20 nm. Raman spectrum of a semi-amorphous semiconductor film shifts to a wave number side lower than 520 cm^{-1} , and the diffraction peaks of (111) and (220) which are thought to be derived from a silicon crystalline lattice are observed by X-ray diffraction. Further, a semi-amorphous semiconductor film contains hydrogen or halogen of at least 1 atomic % or more to terminate dangling bonds. In this specification, such a semiconductor film is referred to as a semi-amorphous semiconductor (SAS) film for convenience. When a rare gas element such as helium, argon, krypton, or neon is contained to further increase the lattice distortion, stability can be enhanced, and a favorable semi-amorphous semiconductor film can be obtained.

In addition, a SAS film can be obtained by glow discharge decomposition of a gas containing silicon. As a typical gas containing silicon, SiH_4 , or Si_2H_6 , SiH_2Cl_2 , SiHCl_3 , SiCl_4 , SiF_4 , or the like can be used. Further, when the gas containing

silicon is diluted with hydrogen or with a gas in which one or more of rare gas elements of helium, argon, krypton, and neon are added to hydrogen, the SAS film can be easily formed. The gas containing silicon is preferably diluted at a dilution ratio in the range of 2 to 1000 times. In addition, a carbide gas such as CH_4 or C_2H_6 ; a germanium gas such as GeH_4 or GeF_4 ; F_2 ; or the like may be mixed into the gas containing silicon to adjust the energy bandwidth to be from 1.5 to 2.4 eV or 0.9 to 1.1 eV.

A semiconductor layer may be provided below the gate wiring 105. Thus, capacitive coupling between the conductive film 115 and the gate wiring 105 can be reduced. Accordingly, the gate wiring 105 can be rapidly charged and discharged, and waveform distortion can be suppressed.

The gate insulating film 104 of the thin film transistor 121 is formed over the semiconductor film 103.

Note that the gate insulating film 104 is provided only near the channel region and not provided in other portions in some cases. Further, thickness or a stacked-layer structure of the gate insulating film 104 may differ depending on a position. For example, the gate insulating film 104 may be thicker or include more layers only near the channel and may be thinner or include fewer layers in other portions. This makes it easy to control the addition of an impurity to the source region and the drain region. Further, when the thickness or the number of layers of the gate insulating film 104 near the channel differs, the amount of impurity added to the semiconductor film are different depending on a position, so that an LDD region can be formed. When the LDD region is formed, leak current and generation of hot carriers can be suppressed, and reliability can be improved.

The gate insulating film 104 is not necessarily formed in a region in which the pixel electrode 113 is formed. In this case, a distance between the pixel electrode 113 and the conductive film 115 can be reduced, so that an electric field can be easily controlled.

The gate insulating film 104 is formed of, for example, an insulating material containing oxygen or nitrogen, such as silicon oxide (SiO_x), silicon nitride (SiN_x), silicon oxide containing nitrogen (SiO_xN_y : $x>y$), or silicon nitride containing oxygen (SiN_xO_y : $x>y$). Alternatively, the gate insulating film 104 may be a stacked-layer film in which a plurality of these films are stacked. The gate electrode 105 provided above the semiconductor film 103 is formed over the gate insulating film 104.

As shown in FIGS. 4 and 3, the gate electrode (the gate wiring) 105 is in the same wiring layer as the wiring 119.

The first interlayer insulating film 106 is formed over the gate insulating film 104 and the gate electrode 105. An inorganic material or an organic material can be used for the first interlayer insulating film 106. As the organic material, polyimide, acrylic, polyamide, polyimide amide, resist, siloxane, polysilazane, or the like can be used. As the inorganic material, an insulating material containing oxygen or nitrogen, such as silicon oxide (SiO_x), silicon nitride (SiN_x), silicon oxide containing nitrogen (SiO_xN_y : $x>y$), or silicon nitride containing oxygen (SiN_xO_y : $x>y$); or a stacked-layer film in which a plurality of these films are stacked can be used. Alternatively, a stacked-layer film in which the organic material and the inorganic material are combined may be used.

A contact hole located over the region 131a, a contact hole located over the region 131b, and a contact hole located over the wiring 119 are formed in the insulating film 102, the gate insulating film 104, and the first interlayer insulating film 106. The source wiring 107, the electrode 108, and the connection electrode 109 are formed over the first interlayer insulating film 106.

Note that when an inorganic material is used for the insulating film, intrusion of moisture and an impurity can be prevented. In particular, a layer containing nitrogen can efficiently block moisture and an impurity.

Note that when an organic material is used for the insulating film, a surface thereof can be planarized. Accordingly, the insulating film can have a good effect on a layer provided thereover. For example, the layer formed over the organic material can also be planarized, so that disturbance of orientation of liquid crystals can be prevented.

The source wiring **107** is located above the region **131a**, and is electrically connected to the region **131a** through the contact hole. Therefore, the electrode **108** is electrically connected to the region **131b** through the contact hole.

Note that the pixel electrode **113** and the impurity region **131b** may be directly connected to each other without a conductive film for connection interposed therebetween. In this case, a contact hole for connecting the pixel electrode **113** and the impurity region **131b** is needed to be deep; however, a conductive film for connection is not needed, and a region for the conductive film for connection can be used as an opening region for displaying an image. Thus, an aperture ratio can be increased, and reduction in power consumption can be realized.

The connection electrode **109** is located above the wiring **119**, and is electrically connected to the wiring **119** and the conductive film **115**. The conductive film **115** is electrically connected to the wiring **119** through the connection electrode **109** in this manner. Note that a plurality of connection electrodes **109** may be provided. Thus, a potential of the conductive film **115** is stabilized. Further, the number of times for forming a contact hole can be reduced by connecting the conductive film **115** and the wiring **119** through the connection electrode **109**, so that a process can be simplified.

Note that the connection electrode **109** is formed of the same material as the source wiring **107** at the same time; however, the invention is not limited thereto. The connection electrode **109** may be formed of the same material as the pixel electrode **113** at the same time.

The second interlayer insulating film **111** is formed over the source wiring **107**, the electrode **108**, the connection electrode **109**, and the first interlayer insulating film **106**. Note that a structure may be employed in which the second interlayer insulating film **111** is not formed (see FIG. **28**). An inorganic material or an organic material can be used for the second interlayer insulating film **111**. As the organic material, polyimide, acrylic, polyamide, polyimide amide, resist, siloxane, polysilazane, or the like can be used. As the inorganic material, an insulating material containing oxygen or nitrogen, such as silicon oxide (SiOx), silicon nitride (SiNx), silicon oxide containing nitrogen (SiOxNy: x>y), or silicon nitride containing oxygen (SiNxOy: x>y); or a stacked-layer film in which a plurality of these films are stacked can be used. Alternatively, a stacked-layer film in which the organic material and the inorganic material are combined may be used.

FIG. **28** is a cross-sectional view in the case where the second interlayer insulating film **111** is not formed. In FIG. **28**, the portions same as those in FIG. **3** are denoted by the same reference numerals. Since the electrode **108** is not formed, the pixel electrode **113** is directly connected to the island-shaped semiconductor film **103**. The source wiring **107**, the pixel electrodes **113** and **114**, and the connection electrode **109** are formed of the same material in the same step. In a structure shown in FIG. **28**, a distance between the pixel electrode **113** and the conductive film **115** can be reduced, and an electric field can be easily controlled.

The pixel electrodes **113**, **114a**, **114b**, and **114c**, and the like which are second electrodes in FFS drive are formed over the second interlayer insulating film **111**. Note that the pixel electrode **113** and the pixel electrodes **114** (**114a**, **114b**, **114c**, and the like) are separated in FIGS. **1** and **3**, which are cross-sectional views, for convenience; as is apparent from FIG. **4**, which is a top plan view, the pixel electrodes are formed in such a manner that grooves (also referred to as openings, slits, apertures, gaps, or spaces) **117** (**117a**, **117b**, **117c**, and the like) are formed in a conductive film formed of the same material in the same step. Accordingly, in the following description, the pixel electrodes **113** and **114** (**114a**, **114b**, **114c**, and the like) may be collectively referred to as the pixel electrode **113** in some cases.

The pixel electrode **113** functions as a pixel electrode to which voltage depending on each pixel is applied, and is formed of ITO (indium tin oxide), ZnO (zinc oxide), IZO formed by using a target in which ZnO of 2 to 20 wt % is mixed to indium oxide, tin oxide (SnO), or the like. Part of the pixel electrode **113** is located above the electrode **108** and is electrically connected to the electrode **108**. Thus, the pixel electrode **113** is electrically connected to the region **131b** of the thin film transistor **121** through the electrode **108**.

Note that when the connection electrode **109** is not provided, the pixel electrode **113** is directly connected to the region **131b** of the thin film transistor **121**.

As shown in FIGS. **3** and **4**, the pixel electrode **113** is generally rectangular and includes a plurality of grooves **117a**, **117b**, **117c**, and the like. Examples of the grooves **117a**, **117b**, **117c**, and the like often include grooves which are slit-shaped and in parallel to each other.

In an example in FIG. **4**, the grooves **117a**, **117b**, **117c**, and the like are directed obliquely to the source wiring **107**, and directions of the grooves in the upper half of the pixel in the drawing and the grooves in the lower half thereof are different from each other. By formation of the grooves **117a**, **117b**, **117c**, and the like, an electric field having a component parallel to the substrate between the conductive film **115** and the pixel electrode **113** is generated from each pixel electrode **114** to the conductive film **115**. Thus, orientation of liquid crystals described below can be controlled by controlling potentials of the pixel electrodes **113** and **114**.

In addition, as shown in FIG. **4**, the directions of the grooves **117** (**117a**, **117b**, **117c**, and the like) vary. Thus, a plurality of regions in which a direction toward which liquid crystal molecules move varies can be provided. In other words, a multi-domain structure can be employed. With a multi-domain structure, a display defect can be prevented when an image is seen from a particular direction. Accordingly, a viewing angle can be improved.

Note that a shape of the groove is not limited to those in this embodiment mode. A shape of the groove includes a space in which a conductor is not formed, for example, a space between comb-shaped portions of a comb-shaped electrode.

When the thickness of the pixel electrode **113** and the thickness of the conductive film **115** are compared, the conductive film **115** is preferably thicker than the pixel electrode **113**. More preferably, the conductive film **115** is 1.5 times or more as thick as the pixel electrode **113**. Accordingly, resistance can be reduced.

As shown in FIG. **5**, a first alignment film **112** and a liquid crystal **116** are stacked over the second interlayer insulating film **111** and the pixel electrode **113**. As the liquid crystal **116**, a ferroelectric liquid crystal (FLC), a bistable liquid crystal, a nematic liquid crystal, a smectic liquid crystal, a polymer dispersed liquid crystal, a liquid crystal to be homogeneously aligned, a liquid crystal to be homeotropically aligned, or the

like can be used. Alternatively, an element other than a liquid crystal, for example, an electrical image element may be used. An opposite substrate **120** is provided over the liquid crystal **116** with a second alignment film **123** and a color filter **122** interposed therebetween. The substrate **101** and the opposite substrate **120** are provided with polarizing plates **126** and **124**, respectively.

Note that a retardation plate, a $\lambda/4$ plate, or the like is often provided in addition to the polarizing plate.

Note that in the aforementioned structure, capacitance is formed by portions of the conductive film **115** and the pixel electrode **113**, in which grooves are not formed, and by each insulating film interposed between the conductive film **115** and the pixel electrode **113**. Storage capacitance is increased by the formation of the capacitance.

Next, an example of a manufacturing method of a semiconductor device and a liquid crystal display device in the invention is described. First, the conductive film **115** having a light-transmitting property (e.g., indium tin oxide (ITO), indium zinc oxide (IZO), zinc oxide (ZnO), tin oxide (SnO), or silicon (Si)) is formed over the entire surface of the substrate **101**.

As shown in FIG. 25, the interlayer insulating film **106** may be removed in an opening portion. Alternatively, the gate insulating film **104** and the base film **102** may be removed. That is, a semiconductor device in which the interlayer insulating film **106** is removed at an opening portion, a semiconductor device in which the insulating film **106** and the gate insulating film **104** are removed at an opening portion, or a semiconductor device in which the interlayer insulating film **106**, the gate insulating film **104**, and the base film **102** are removed at an opening portion can be formed. Accordingly, a distance d between the conductive film **115** and the pixel electrodes **114** (in FIG. 25, the pixel electrodes **114b**, **114c**, and **114d** among the pixel electrodes **114a** to **114f**) can be reduced; thus, an electric field can be easily controlled.

Next, the insulating film **102** is formed over each of the substrate **101** and the conductive film **115**. The insulating film **102** is preferably formed thicker than the gate insulating film **104** described below. Then, a semiconductor film (e.g., a polycrystalline silicon film) is formed over the insulating film **102** and is selectively removed by etching with the use of a resist. Thus, the island-shaped semiconductor film **103** is formed over the insulating film **102**.

As the semiconductor film, an amorphous silicon film or another non-crystalline silicon film may be used as well as the polycrystalline silicon film. Further, the invention is not limited to silicon, and a compound semiconductor such as ZnO, a-InGaZnO, SiGe, or GaAs may also be used.

Alternatively, a semiconductor substrate or an SOI (Silicon On Insulator) substrate may be used as the substrate **101** to form the island-shaped semiconductor film **103**.

Next, the gate insulating film **104** is formed over the semiconductor film **103** and the insulating film **102**. The gate insulating film **104** is a silicon oxide film containing nitrogen or a silicon oxide film, for example, and is formed by a plasma CVD method. Note that the gate insulating film **104** may be formed of a silicon nitride film or a stacked-layer film containing silicon nitride and silicon oxide. Next, a conductive film is formed over the gate insulating film **104** and is selectively removed by etching. Thus, the gate electrode **105** is formed over the gate insulating film **104** located over the semiconductor film **103**. Further, the gate wiring **105** and the wiring **119** are formed in this step.

Note that by provision of the wiring **119** as described above, a potential of the conductive film **115** in each pixel can be stabilized. Alternatively, the wiring **119** is not formed in

some cases. Further, the wiring **119** may be in another layer (e.g., the same layer as the source wiring **107**, the same layer as the conductive film **115**, or the same layer as the pixel electrode **113**), or may be separately provided in a plurality of layers. In addition, although the wiring **119** is extended in a direction perpendicular to the source wiring **107** in the drawing, it may be extended in the same direction as the source wiring **107**.

The conductive film forming the gate electrode **105** and the wiring **119** is preferably formed of one or a plurality of elements selected from aluminum (Al), tantalum (Ta), titanium (Ti), molybdenum (Mo), tungsten (W), neodymium (Nd), chromium (Cr), nickel (Ni), platinum (Pt), gold (Au), silver (Ag), copper (Cu), magnesium (Mg), scandium (Sc), cobalt (Co), zinc (Zn), niobium (Nb), silicon (Si), phosphorus (P), boron (B), arsenic (As), gallium (Ga), indium (In), tin (Sn), and oxygen (O); a compound or an alloy material containing one or a plurality of the aforementioned elements (e.g., indium tin oxide (ITO), indium zinc oxide (IZO), indium tin oxide containing silicon oxide (ITSO), zinc oxide (ZnO), tin oxide (SnO), cadmium tin oxide (CTO), aluminum-neodymium (Al—Nd), magnesium-silver (Mg—Ag), or molybdenum-niobium (Mo—Nb)); a substance in which these compounds are combined; or the like. Alternatively, the conductive film is preferably formed of a compound (silicide) of silicon and one or a plurality of the aforementioned elements (e.g., aluminum-silicon, molybdenum-silicon, or nickel-silicide), or a compound of nitrogen and one or a plurality of the aforementioned elements (e.g., titanium nitride, tantalum nitride, or molybdenum nitride).

Note that silicon (Si) may contain an n-type impurity (such as phosphorus) or a p-type impurity (such as boron). When silicon contains the impurity, the conductivity is increased, and a function similar to a general conductor can be realized. Thus, such silicon can be utilized easily as a wiring, an electrode, or the like.

In addition, silicon with various levels of crystallinity, such as single crystalline silicon, polycrystalline silicon, or microcrystalline silicon can be used. Alternatively, silicon having no crystallinity, such as amorphous silicon can be used. By using single crystalline silicon or polycrystalline silicon, resistance of a wiring, an electrode, a conductive layer, a conductive film, a terminal, or the like can be reduced. By using amorphous silicon or microcrystalline silicon, a wiring or the like can be formed by a simple process.

Aluminum and silver have high conductivity, and thus can reduce a signal delay. Further, since aluminum and silver can be easily etched, they can be minutely processed.

Copper has high conductivity, and thus can reduce a signal delay. When copper is used, a stacked-layer structure is preferably employed to improve adhesion.

Molybdenum and titanium are preferable since even if molybdenum or titanium is in contact with an oxide semiconductor (e.g., ITO or IZO) or silicon, molybdenum or titanium does not cause defects. Further, molybdenum and titanium are preferable since they are easily etched and has high heat resistance.

Tungsten is preferable since it has an advantage such as high heat resistance.

Neodymium is also preferable since it has an advantage such as high heat resistance. In particular, an alloy of neodymium and aluminum is preferable since heat resistance is increased and aluminum hardly causes hillocks.

Silicon is preferable since it can be formed at the same time as a semiconductor layer included in a transistor and has high heat resistance.

Since ITO, IZO, ITSO, zinc oxide (ZnO), silicon (Si), tin oxide (SnO), and cadmium tin oxide (CTO) have light-transmitting properties, they can be used as a portion which transmits light. For example, they can be used for a pixel electrode or a common electrode.

IZO is preferable since it is easily etched and processed. In etching IZO, a residue is hardly left. Thus, when IZO is used for a pixel electrode, defects (such as short circuit or orientation disorder) of a liquid crystal element or a light-emitting element can be reduced.

The conductive film forming the gate electrode **105** and the wiring **119** may have a single-layer structure or a multi-layer structure. By employing a single-layer structure, a manufacturing process of the conductive film forming the gate electrode **105** and the wiring **119** can be simplified, the number of days for a process can be reduced, and cost can be reduced. Alternatively, by employing a multi-layer structure, a wiring, an electrode, and the like with high quality can be formed while an advantage of each material is utilized and a disadvantage thereof is reduced. For example, when a low-resistant material (e.g., aluminum) is included in a multi-layer structure, reduction in resistance of a wiring can be realized. Further, when a stacked-layer structure where a low heat-resistant material is interposed between high heat-resistant materials is employed, heat resistance of a wiring, an electrode, and the like can be increased, utilizing advantages of the low heat-resistant material. For example, it is preferable to employ a stacked-layer structure where a layer containing aluminum is interposed between layers containing molybdenum, titanium, neodymium, or the like.

When wirings, electrodes, or the like are in direct contact with each other, they adversely affect each other in some cases. For example, one wiring or one electrode is mixed into a material of another wiring or another electrode and changes its properties, and thus, an intended function cannot be obtained in some cases. As another example, when a high-resistant portion is formed, a problem may occur so that it cannot be normally formed. In such cases, a reactive material is preferably interposed by or covered with a non-reactive material in a stacked-layer structure. For example, when ITO and aluminum are connected, titanium, molybdenum, or an alloy of neodymium is preferably interposed between ITO and aluminum. As another example, when silicon and aluminum are connected, titanium, molybdenum, or an alloy of neodymium is preferably interposed between silicon and aluminum.

Note that the term "wiring" indicates a portion including a conductor. A wiring may be provided linearly or may be short without being extended linearly. Therefore, an electrode is included in a wiring.

Next, an impurity is injected into the semiconductor film **103** by using the gate electrode **105** as a mask. Thus, the region **131a** which is one of the source region and the drain region, the region **131b** which is the other of the source region and the drain region, and the channel formation region **132** are formed in the semiconductor film **103**. Note that an n-type impurity element and a p-type impurity element may be separately injected, or both the n-type impurity element and the p-type impurity element may be injected into a particular region. In the latter case, the amount of one of the n-type impurity element and the p-type impurity element should be larger than the other. Note that in the step, a resist may be used for a mask.

At this time, an LDD region may be formed by changing the thickness or a stacked-layer structure of the gate insulating film **104**. In a portion in which the LDD region is to be formed, the gate insulating film **104** may be thickened or the

number of layers may be increased. Thus, the amount of impurity to be injected is reduced, and an LDD region can be easily formed.

Note that the impurity may be injected into the semiconductor film **103** before the gate electrode **105** is formed, for example, before or after the gate insulating film **104** is formed. In this case, a resist is used as a mask. Accordingly, capacitance can be formed between the electrode in the same layer as the gate and the semiconductor film into which the impurity is injected. The gate insulating film is provided between the electrode in the same layer as the gate and the semiconductor film into which the impurity is injected, so that capacitance with thin thickness and large capacity can be formed.

Next, the first interlayer insulating film **106** is formed, and further, a contact hole is formed. Then, a conductive film (e.g., a metal film) is formed over the first interlayer insulating film **106** and is selectively removed by etching with the use of a mask. Thus, the source wiring **107**, the electrode **108**, and the connection electrode **109** are formed.

Next, the second interlayer insulating film **111** is formed, and further, a contact hole is formed. Then, a conductive film having a light-transmitting property (e.g., indium tin oxide (ITO), indium zinc oxide (IZO), zinc oxide (ZnO), tin oxide (SnO), or silicon (Si)) is formed over the second interlayer insulating film **111**, and is selectively removed by etching with the use of a resist. Thus, the pixel electrode **113** is formed.

When the contact hole filled with part of the electrode **108** and the contact hole filled with part of the pixel electrode **113** are located at the same position, layout can be efficiently performed because the contact holes are located at one place. Thus, an aperture ratio of the pixel can be improved.

On the other hand, the contact hole filled with part of the electrode **108** and the contact hole filled with part of the pixel electrode **113** may be located at different positions. Thus, when portions of the electrode **108** and the pixel electrode **113**, which are located above the contact holes, are depressed, the depressed portions do not overlap with each other. Thus, the deeply depressed portion is not formed at the pixel electrode **113**, and generation of a defect of the resist can be suppressed. Thereafter, the resist is removed.

Next, the first alignment film **112** is formed, and the liquid crystal **116** is sealed between the first alignment film **112** and the opposite substrate **120** on which the color filter **122** and the second alignment film **123** are formed. Thereafter, sides of the opposite substrate **120** and the substrate **101**, which are not in contact with the liquid crystal **116**, are provided with the polarizing plates **126** and **124**, a retardation plate (not shown), an optical film (not shown) such as a $\lambda/4$ plate, an optical film such as a diffusing plate or a prism sheet, or the like. Further, a backlight or a front light is provided. As the backlight, a direct type backlight or a sidelight type backlight can be used. As a light source, a cold cathode tube or an LED (a light-emitting diode) can be used. As the LED, a white LED or a combination of LEDs of respective colors (e.g., white, red, blue, green, cyan, magenta, and/or yellow) may be used. By using the LED, color purity can be improved because the LED has a sharp peak of light wavelength. In the case of a sidelight type backlight, a light guide plate is provided to realize a uniform surface light source. The liquid crystal display device is formed in such a manner.

Note that a liquid crystal display device may only refer to a substrate, an opposite substrate, and a liquid crystal interposed therebetween. Alternatively, the liquid crystal display device may further include an optical film such as a polarizing plate or a retardation plate. Further alternatively, the liquid

crystal display device may also include a diffusing plate, a prism sheet, a light source (such as a cold cathode tube or an LED), a light-guide plate, and the like.

In this embodiment mode, a so-called top-gate thin film transistor in which a gate electrode is located above a channel region is described; however, the present invention is not particularly limited thereto. A so-called bottom-gate thin film transistor in which a gate electrode located below a channel region, or a transistor having a structure in which gate electrodes are arranged above and below a channel region may be formed.

In this embodiment mode, a so-called single-gate thin film transistor in which one gate electrode is formed is described; however, a so-called multi-gate thin film transistor in which two or more gate electrodes are formed may be formed.

A liquid crystal display device may be a transmissive liquid crystal display device or a reflective liquid crystal display device. For example, the conductive film 115 is formed of a light-transmitting film (e.g., an indium tin oxide (ITO) film, an indium zinc oxide (IZO) film, a zinc oxide (ZnO) film, or a polycrystalline silicon film or an amorphous silicon film into which an impurity is introduced), and the pixel electrode 113 is formed of a reflective conductive film, for example, a metal film. Thus, a reflective liquid crystal display device can be realized. In addition, the pixel electrode 113 is formed of a light-transmitting film, and part of the conductive film 115 is formed of a reflective conductive film, for example, a metal film, whereas the other part of the conductive film 115 is formed of a light-transmitting film; thus, a transfective liquid crystal display device can be realized.

In a reflective liquid crystal display device, when a reflective conductive film, for example, a metal film is used as the conductive film 115, the conductive film 115 can have a function as a reflecting plate. A reflective conductive film can be used as one or both of the pixel electrode 113 and the conductive film 115. Further, an insulating film (e.g., a silicon oxide film) may be provided between the substrate 101 and the conductive film 115, and a metal film as a reflecting film may be formed in the insulating film. A reflecting sheet (e.g., an aluminum film) as a reflecting film may be formed on an external surface of the substrate 101. Note that the contents described here can be similarly applied to embodiment modes described below.

According to this embodiment mode, a liquid crystal display device with a wide viewing angle and lower manufacturing cost than a conventional liquid crystal display device can be provided.

In this embodiment mode, since a conductive film is formed over an entire surface of a substrate, an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a semiconductor device with high reliability can be obtained.

In this embodiment mode, since a semiconductor device including a top-gate thin film transistor is formed, a potential of a back gate is stabilized; thus, a semiconductor device with high reliability can be obtained.

Embodiment Mode 2

In this embodiment mode, an example in which a bottom-gate TFT is formed as a switching element in a pixel portion is described with reference to FIG. 2.

A conductive film 202, a base film 203, a gate electrode 204, a gate insulating film 213, an island-shaped semiconductor film 206 to be an active layer, a region 208a which is one of a source region and a drain region, a region 208b which is the other of the source region and the drain region, an elec-

trode 207a which is one of a source electrode and a drain electrode, an electrode 207b which is the other of the source electrode and the drain electrode, and pixel electrodes 209 and 214 (214a, 214b, 214c, and the like) are formed over a substrate 201. A TFT 212 includes the gate electrode 204, the gate insulating film 213, the island-shaped semiconductor film 206, and the regions 208a and 208b.

A horizontal electric field 225 is generated between the pixel electrodes 214 and the conductive film 202. Liquid crystal molecules are driven by the horizontal electric field 225.

An electrode 205 formed of the same material and in the same step as the gate electrode 204 is formed over the base film 203. An electrode 211 formed of the same material and in the same step as the pixel electrode 209 is formed over an insulating film 210. The electrode 211 is electrically connected to the conductive film 202 and the electrode 205 through contact holes formed in the base film 203, the gate insulating film 213, and the insulating film 210.

As the substrate 201, a material similar to that of the substrate 101 may be used.

As the conductive film 202, a conductive film similar to the conductive film 115 described in Embodiment Mode 1 may be used.

The base film 203 may be formed of a material similar to that of the base film 102.

The gate electrode 204 and the electrode 205 may be formed of a material and in a step similar to those of the gate electrode 105. The gate insulating film 213 is formed of a material similar to that of the gate insulating film 104 or the interlayer insulating film 106 over an entire surface of the substrate 201.

In this embodiment mode, a so-called single-gate thin film transistor in which one gate electrode is formed is described; however, a so-called multi-gate thin film transistor in which two or more gate electrodes are formed may be formed.

The island-shaped semiconductor film 206, which is the active layer, is formed of a material similar to that of the island-shaped semiconductor film 103, and preferably, an amorphous semiconductor film or a microcrystalline semiconductor film (a semi-amorphous semiconductor film). In that case, after an intrinsic semiconductor film (the island-shaped semiconductor film 206) is formed, a semiconductor film containing an impurity imparting one conductivity type is formed. As the impurity imparting one conductivity type, phosphorus (P) or arsenic (As) may be used as an impurity imparting n-type conductivity, and boron (B) may be used as an impurity imparting p-type conductivity. A bottom-gate TFT in this embodiment mode employs a channel etch type; thus, after an island-shaped semiconductor film, a source electrode, and a drain electrode are formed, part of a channel formation region is needed to be etched.

Next, a conductive film is formed over the gate insulating film 213 and the island-shaped semiconductor film 206, and the electrodes 207a and 207b are formed by etching. Thereafter, by using the electrodes 207a and 207b as masks, part of the semiconductor film containing the impurity imparting one conductivity type is etched to form the regions 208a and 208b.

The insulating film 210 is formed over the island-shaped semiconductor film 206, the regions 208a and 208b, and the electrodes 207a and 207b. The insulating film 210 may be formed of a material and in a step similar to those of the interlayer insulating film 106 or the interlayer insulating film 111. Note that when an organic material is not used for the insulating film 210, a distance d between the pixel electrode 214 and the conductive film 202 can be reduced; thus, an electric field can be easily controlled.

The pixel electrodes **209** and **214** (**214a**, **214b**, **214c**, and the like) and the electrode **211** are formed over the insulating film **210**. The pixel electrodes **209** and **214** are formed in such a manner that grooves are formed in a conductive film, similar to the pixel electrodes **113** and **114**.

The electrode **211** is electrically connected to the electrode **205** through a contact hole formed in the gate insulating film **213** and the insulating film **210**, and is also electrically connected to the conductive film **202** through a contact hole formed in the base film **203**, the gate insulating film **213**, and the insulating film **210**.

An alignment film **215** is formed over the pixel electrodes **209** and **214**, and the electrode **211**. The alignment film **215** may be formed of a material similar to that of the alignment film **112**.

A color filter **222** and an alignment film **223** are formed over an opposite substrate **221**. The opposite substrate **221**, the color filter **222**, and the alignment film **223** may be formed of a material similar to that of the opposite substrate **120**, the color filter **122**, and the alignment film **123**, respectively.

The alignment film **223** over the opposite substrate **221** and the alignment film **215** over the substrate **201** face each other, and a liquid crystal **216** is injected into a space.

Thereafter, sides of the opposite substrate **221** and the substrate **201**, which are not in contact with the liquid crystal **216**, are provided with polarizing plates **224** and **217**, a retardation plate (not shown), an optical film (not shown) such as a $\lambda/4$ plate, an optical film such as a diffusing plate or a prism sheet, or the like. Further, a backlight or a front light is provided. As the backlight, a direct type backlight or a side-light type backlight can be used. As a light source, a cold cathode tube or an LED (a light-emitting diode) can be used. As the LED, a white LED or a combination of LEDs of respective colors (e.g., white, red, blue, green, cyan, magenta, and/or yellow) may be used. By using the LED, color purity can be improved because the LED has a sharp peak of light wavelength. In the case of a sidelight type backlight, a light guide plate is provided to realize a uniform surface light source. The liquid crystal display device is formed in such a manner.

FIG. **26** shows an example where an active layer of the TFT **212** is formed of a crystalline semiconductor film. In FIG. **26**, the portions same as those in FIG. **2** are denoted by the same reference numerals. In FIG. **26**, the TFT **212** includes an island-shaped crystalline semiconductor film **253** as an active layer. The island-shaped crystalline semiconductor film **253** includes a channel formation region **256**, a region **258a** which is one of a source region and a drain region, and a region **258b** which is the other of the source region and the drain region.

Instead of the electrode **211** in FIG. **2**, an electrode **251** formed of the same material and in the same step as the electrode **207a** which is one of the source electrode and the drain electrode and the electrode **207b** which is the other of the source electrode and the drain electrode is used.

Note that since this embodiment mode is similar to Embodiment Mode 1, except that the TFT **121** in Embodiment Mode 1 is replaced with the bottom-gate TFT **212** in this embodiment mode, materials and manufacturing steps of the other structures can refer to those described in Embodiment Mode 1.

According to this embodiment mode, a liquid crystal display device with a wide viewing angle and lower manufacturing cost than a conventional liquid crystal display device can be provided.

In the invention, since a conductive film is formed over an entire surface of a substrate, an impurity from the substrate

can be prevented from being mixed into an active layer. Thus, a semiconductor device with high reliability can be obtained.

Embodiment Mode 3

In this embodiment mode, FIG. **6** shows an example where the electrode **108** in Embodiment Mode 1 is not formed and the pixel electrode **113** is formed to be directly connected to the region **131b**. The reference numerals in Embodiment Mode 1 are used for reference numerals in FIG. **6**. Materials and manufacturing steps of the other structures can refer to those described in Embodiment Mode 1. This embodiment mode has an advantage of improvement in aperture ratio because the electrode **108** is not formed.

A bottom-gate TFT described in Embodiment Mode 2 may be used when needed.

According to this embodiment mode, a liquid crystal display device with a wide viewing angle and lower manufacturing cost than a conventional liquid crystal display device can be provided.

In the invention, since a conductive film is formed over an entire surface of a substrate, an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a semiconductor device with high reliability can be obtained.

In the invention, when a semiconductor device including a top-gate thin film transistor is formed, a potential of a back gate is stabilized; thus, a semiconductor device with high reliability can be obtained.

Embodiment Mode 4

This embodiment mode is described with reference to FIGS. **10** to **13**. The reference numerals in Embodiment Mode 1 are used for reference numerals in FIGS. **10** to **13**. Materials and manufacturing steps of the other structures may refer to those described in Embodiment Mode 1.

A bottom-gate TFT described in Embodiment Mode 2 may be used when needed.

Further, a structure where a pixel electrode is directly connected to an active layer, which is described in Embodiment Mode 3, may be used when needed.

In FIG. **10**, an electrode **141** formed of a material and in a step similar to those of the pixel electrode **113** is used instead of the connection electrode **109** in FIG. **6**. The wiring **119** and the conductive film **115** are electrically connected through the electrode **141**.

FIG. **11** is a top plan view of FIG. **10**. In FIG. **11**, the portions same as those in FIGS. **4** and **10** are denoted by the same reference numerals. FIG. **10** is a cross-sectional view of C-C' and D-D' in FIG. **11**.

In FIG. **12**, the electrode **141** formed of a material and in a step similar to those of the pixel electrode **113**; and an electrode **142** formed of a material and in a step similar to those of the electrodes **107** and **108** are used instead of the connection electrode **109** in FIG. **6**. The wiring **119** and the conductive film **115** are electrically connected through the electrodes **141** and **142**.

FIG. **13** is a top plan view of FIG. **12**. In FIG. **13**, the portions same as those in FIGS. **4** and **12** are denoted by the same reference numerals. FIG. **12** is a cross-sectional view of C-C' and D-D' in FIG. **13**.

According to this embodiment mode, a liquid crystal display device with a wide viewing angle and lower manufacturing cost than a conventional liquid crystal display device can be provided.

In the invention, since a conductive film is formed over an entire surface of a substrate, an impurity from the substrate

can be prevented from being mixed into an active layer. Thus, a semiconductor device with high reliability can be obtained.

In the invention, when a semiconductor device including a top-gate thin film transistor is formed, a potential of a back gate is stabilized; thus, a semiconductor device with high reliability can be obtained.

Embodiment Mode 5

In this embodiment mode, FIGS. 7, 8A to 8D, and 9A to 9D show examples of pixel electrodes with various shapes. The reference numerals in Embodiment Mode 1 are used for reference numerals in FIGS. 7, 8A to 8D, and 9A to 9D. Materials and manufacturing steps of the other structures may refer to those described in Embodiment Mode 1.

A bottom-gate TFT described in Embodiment Mode 2 may be used when needed.

Further, a structure where a pixel electrode is directly connected to an active layer, which is described in Embodiment Mode 3, may be used when needed.

Moreover, a connection structure of the conductive film 115 and the wiring 119, which is described in Embodiment Mode 4, may be used when needed.

FIG. 7 shows the pixel electrode 113 with a comb shape. A cross-sectional view of A-A' and B-B' is same as FIG. 3. FIGS. 8A to 8D and 9A to 9D only show the pixel electrode 113 and the conductive film 115 so that each drawing is understandable.

In FIG. 8A, a plurality of slit-shaped openings are formed in the pixel electrode 113. The slit-shaped openings are oblique to the source wiring. The slit-shaped openings in the upper half of the pixel electrode 113 and the slit-shaped openings in the lower half thereof have different angles with respect to the center line of the pixel electrode 113. The slit-shaped openings in the upper half of the pixel electrode 113 and the slit-shaped openings in the lower half thereof may be line-symmetrical with respect to the central line.

In FIG. 8B, the pixel electrode 113 has a shape in which a plurality of electrodes each having a shape along a circumference of a circle, radius of which is different from each other, are arranged in a concentric pattern and are connected to each other. Each space between the electrodes functions as an opening.

In FIG. 8C, the pixel electrode 113 is arranged so that two comb-shaped electrodes are arranged to face opposite directions to each other and comb-shaped portions are alternately arranged. Each space between comb-shaped portions functions as an opening.

In FIG. 8D, the pixel electrode 113 is comb-shaped. Each space between comb-shaped portions functions as an opening.

In FIG. 9A, the pixel electrode 113 is formed in stripes in an oblique direction. Each space between stripe portions functions as an opening.

In FIG. 9B, a plurality of rectangular opening portions are formed in the pixel electrode 113.

In FIG. 9C, an opening portion with a shape in which two sides of an elongated rectangular, which face each other, are wave-shaped, is formed in the pixel electrode 113.

In FIG. 9D, an opening portion with an elongated rectangular shape is formed in the pixel electrode 113.

According to the invention, a liquid crystal display device with a wide viewing angle and lower manufacturing cost than a conventional liquid crystal display device can be provided.

In the invention, since a conductive film is formed over an entire surface of a substrate, an impurity from the substrate

can be prevented from being mixed into an active layer. Thus, a semiconductor device with high reliability can be obtained.

In the invention, when a semiconductor device including a top-gate thin film transistor is formed, a potential of a back gate is stabilized; thus, a semiconductor device with high reliability can be obtained.

Embodiment Mode 6

In this embodiment mode, examples where a color filter is provided at a place different from that in Embodiment Mode 1 are described with reference to FIGS. 22, 23A, 23B, and 24.

FIG. 22 is a cross-sectional view for describing a structure of a pixel portion in an FFS mode liquid crystal display device according to this embodiment mode. The pixel portion in the liquid crystal display device according to this embodiment mode has a structure similar to that of the liquid crystal display device in Embodiment Mode 1, except that a color filter is not provided on the opposite substrate 120 side and color filters 241 (a red color filter 241R, a blue color filter 241B, and a green color filter 241G) are provided instead of the interlayer insulating film 106.

Accordingly, the contents described in other embodiment modes except Embodiment Mode 1 can also be applied to this embodiment mode. Hereinafter, the portions similar to those in Embodiment Mode 1 are denoted by the same reference numerals, and description thereof is omitted.

Note that an insulating film formed of an inorganic material may be provided between the color filter 241 and the gate electrode 105. The inorganic material is formed of an insulating material containing oxygen or nitrogen, such as silicon oxide, silicon nitride, silicon oxide containing nitrogen, or silicon nitride containing oxygen. It is preferable to use a material containing a large amount of nitrogen in order to prevent penetration of an impurity. Further, a planarization film may be formed over the color filter 241.

Note that colors of the color filters 241 may be colors other than red, blue, and green, and may be more than three colors, for example, four colors or six colors. For example, yellow, cyan, magenta, or white may be added. Further, a black matrix may be provided as well as a color filter. The black matrix may be formed using a resin material, a metal film, or carbon black.

By providing the color filters 241 over the substrate 101 in such a manner, it is not necessary to perform precise alignment with the opposite substrate 120; thus, a liquid crystal display device can be easily formed, cost is reduced, and manufacturing yield is improved.

A method for manufacturing the liquid crystal display device according to this embodiment mode is similar to the method for manufacturing the liquid crystal display device in Embodiment Mode 1, except that a step of forming the color filters 241 (241R, 241G, and 241B) is added instead of the step of forming the interlayer insulating film 106.

The color filters 241R, 241G, and 241B are formed by repeating the following steps three times: a step of forming a color filter layer, a step of forming a resist over the color filter layer, and a step of selectively dry-etching the color filter layer with use of the resist as a mask.

Alternatively, the color filters may be formed by using a photosensitive material, pigment, or the like without using a resist. Note that a space is generated between the color filter layers, and the interlayer insulating film 111 is embedded in this space. Alternatively, an inorganic material or an organic material may be further stacked. Further alternatively, a black matrix or the like may be stacked. The color filters 241R,

241G, and 241B, or the black matrix can also be formed by using a droplet discharging method (e.g., an ink-jet method).

Thus, the number of manufacturing steps of the liquid crystal display device can be reduced. Since the color filters are provided on the substrate 101 side, decrease in aperture ratio can be suppressed even when misalignment with the opposite substrate 120 is caused, as compared with the case where the color filters are provided on the opposite substrate 120. That is, a margin for misalignment of the opposite substrate 120 increases.

FIG. 23A is a plan view of the liquid crystal display device shown in FIG. 22. As shown in FIG. 23A, in the liquid crystal display device of this embodiment mode, a source line driver circuit 152 and a gate line driver circuit 154 which are peripheral driver circuits are provided around a pixel portion 150.

The red color filter 241R may be provided over each of the source line driver circuit 152 and the gate line driver circuit 154. Provision of the color filter 241R prevents light deterioration of an active layer of each thin film transistor included in the source line driver circuit 152 and the gate line driver circuit 154 and realizes planarization.

FIG. 23B is an enlarged view of a part (three rows×three columns) of the pixel portion 150 in FIG. 23A. In the pixel portion 150, the red color filter 241R, the blue color filter 241B, and the green color filter 241G are alternately arranged in stripes. Further, the red color filter 241R is provided over a thin film transistor included in each pixel.

Since a source wiring (not shown) and a gate wiring (not shown) are arranged to overlap with the space between the color filters, light leakage is suppressed.

Since the color filter 241 functions as a black matrix in this manner, a step of forming a black matrix, which is conventionally required, can be omitted.

As described above, according to this embodiment mode, advantageous effects similar to other embodiment modes can be obtained. Further, since the color filters 241R, 241G, and 241B are provided instead of the interlayer insulating film 106, the number of manufacturing steps of the liquid crystal display device can be reduced. Moreover, reduction in aperture ratio can be suppressed even when misalignment with the opposite substrate 120 is caused, as compared with the case where the color filter is provided on the opposite substrate 120. That is, a margin for misalignment of the opposite substrate 120 is increased.

In addition, a black matrix may be provided in addition to a color filter.

Note that in the FFS mode liquid crystal display devices shown in other embodiment modes, the color filters 241 (241R, 241G, and 241B) may be provided instead of the interlayer insulating film 106 or instead of the second interlayer insulating film 111 (see FIG. 24), similar to this embodiment mode. In this case also, advantageous effects similar to those of this embodiment mode can be obtained.

Embodiment Mode 7

In this embodiment mode, a structure and a manufacturing method of a transistor are described.

FIGS. 29A to 29G show a structure and a manufacturing method of a transistor. FIG. 29A shows a structure example of a transistor. FIGS. 29B to 29G show an example of a manufacturing method of the transistor.

Note that the structure and the manufacturing method of a transistor are not limited to those shown in FIGS. 29A to 29G and various structures and manufacturing methods can be employed.

First, a structure example of a transistor is described with reference to FIG. 29A. FIG. 29A is a cross-sectional view of a plurality of transistors each having a different structure. Here, in FIG. 29A, the plurality of transistors each having a different structure are juxtaposed, which is for describing structures of the transistors. Therefore, the transistors are not needed to be actually juxtaposed as shown in FIG. 29A and can be separately formed as needed.

Next, characteristics of each layer forming the transistor are described.

A substrate 7011 can be a glass substrate using barium borosilicate glass, aluminoborosilicate glass, or the like, a quartz substrate, a ceramic substrate, a metal substrate containing stainless steel, or the like. In addition, a substrate formed of plastics typified by polyethylene terephthalate (PET), polyethylene naphthalate (PEN), or polyethersulfone (PES), or a substrate formed of a flexible synthetic resin such as acrylic can also be used. By using a flexible substrate, a semiconductor device capable of being bent can be formed. A flexible substrate has no strict limitations on an area or a shape of the substrate. Therefore, for example, when a substrate having a rectangular shape, each side of which is 1 meter or more, is used as the substrate 7011, productivity can be significantly improved. Such an advantage is highly favorable as compared with the case where a circular silicon substrate is used.

An insulating film 7012 functions as a base film and is provided to prevent alkali metal such as Na or alkaline earth metal from the substrate 7011 from adversely affecting characteristics of a semiconductor element. The insulating film 7012 can have a single-layer structure or a stacked-layer structure of an insulating film containing oxygen or nitrogen, such as silicon oxide (SiO_x), silicon nitride (SiN_x), silicon oxynitride (SiO_xN_y) ($x>y$), or silicon nitride oxide (SiN_xO_y) ($x>y$). For example, when the insulating film 7012 is provided to have a two-layer structure, it is preferable that a silicon nitride oxide film be used as a first insulating film and a silicon oxynitride film be used as a second insulating film. As another example, when the insulating film 7012 is provided to have a three-layer structure, it is preferable that a silicon oxynitride film be used as a first insulating film, a silicon nitride oxide film be used as a second insulating film, and a silicon oxynitride film be used as a third insulating film.

Semiconductor layers 7013, 7014, and 7015 can be formed using an amorphous semiconductor, a microcrystalline semiconductor, or a semi-amorphous semiconductor (SAS). Alternatively, a polycrystalline semiconductor layer may be used. SAS is a semiconductor having an intermediate structure between amorphous and crystalline (including single crystal and polycrystalline) structures and having a third state which is stable in free energy. Moreover, SAS includes a crystalline region with a short-range order and lattice distortion. A crystalline region of 0.5 to 20 nm can be observed at least in part of a film. When silicon is contained as a main component, Raman spectrum shifts to a wave number side lower than 520 cm⁻¹. The diffraction peaks of (111) and (220), which are thought to be derived from a silicon crystalline lattice, are observed by X-ray diffraction. SAS contains hydrogen or halogen of at least 1 atomic % or more to compensate dangling bonds. SAS is formed by glow discharge decomposition (plasma CVD) of a material gas. As the material gas, SiH₄, Si₂H₆, SiH₂Cl₂, SiHCl₃, SiCl₄, SiF₄, or the like can be used. Further, GeF₄ may be mixed. Alternatively, the material gas may be diluted with H₂, or H₂ and one or more kinds of rare gas elements selected from He, Ar, Kr, and Ne. A dilution ratio is in the range of 2 to 1000 times. Pressure is in the range of approximately 0.1 to 133 Pa, and a power supply frequency

is 1 to 120 MHz, preferably 13 to 60 MHz. A substrate heating temperature may be 300° C. or lower. A concentration of impurities in atmospheric components such as oxygen, nitrogen, and carbon is preferably $1 \times 10^{20} \text{ cm}^{-3}$ or less as impurity elements in the film. In particular, an oxygen concentration is $5 \times 10^{19} \text{ cm}^{-3}$ or less, preferably $1 \times 10^{19} \text{ cm}^{-3}$ or less. Here, an amorphous semiconductor layer is formed using a material containing silicon (Si) as its main component (e.g., $\text{Si}_x\text{Ge}_{1-x}$) by a sputtering method, an LPCVD method, a plasma CVD method, or the like. Then, the amorphous semiconductor layer is crystallized by a crystallization method such as a laser crystallization method, a thermal crystallization method using RTA or an annealing furnace, or a thermal crystallization method using a metal element which promotes crystallization.

An insulating film **7016** can have a single-layer structure or a stacked-layer structure of an insulating film containing oxygen or nitrogen, such as silicon oxide (SiOx), silicon nitride (SiNx), silicon oxynitride (SiOxNy) ($x > y$), or silicon nitride oxide (SiNxOy) ($x > y$).

A gate electrode **7017** can have a single-layer structure of a conductive film or a stacked-layer structure of two or three conductive films. As a material for the gate electrode **7017**, a conductive film can be used. For example, a single film of an element such as tantalum (Ta), titanium (Ti), molybdenum (Mo), tungsten (W), chromium (Cr), silicon (Si), or the like; a nitride film containing the aforementioned element (typically, a tantalum nitride film, a tungsten nitride film, or a titanium nitride film); an alloy film in which the aforementioned elements are combined (typically, a Mo—W alloy or a Mo—Ta alloy); a silicide film containing the aforementioned element (typically, a tungsten silicide film or a titanium silicide film); and the like can be used. Note that the aforementioned single film, nitride film, alloy film, silicide film, and the like can have a single-layer structure or a stacked-layer structure.

An insulating film **7018** can have a single-layer structure or a stacked-layer structure of an insulating film containing oxygen or nitrogen, such as silicon oxide (SiOx), silicon nitride (SiNx), silicon oxynitride (SiOxNy) ($x > y$), or silicon nitride oxide (SiNxOy) ($x > y$); or a film containing carbon, such as a DLC (Diamond-Like Carbon), by a sputtering method, a plasma CVD method, or the like.

An insulating film **7019** can have a single-layer structure or a stacked-layer structure of a siloxane resin; an insulating film containing oxygen or nitrogen, such as silicon oxide (SiOx), silicon nitride (SiNx), silicon oxynitride (SiOxNy) ($x > y$), or silicon nitride oxide (SiNxOy) ($x > y$); a film containing carbon, such as a DLC (Diamond-Like Carbon); or an organic material such as epoxy, polyimide, polyamide, polyvinyl phenol, benzocyclobutene, or acrylic. Note that a siloxane resin corresponds to a resin having Si—O—Si bonds. Siloxane includes a skeleton structure of a bond of silicon (Si) and oxygen (O). As a substituent, an organic group containing at least hydrogen (such as an alkyl group or aromatic hydrocarbon) is used. Alternatively, a fluoro group, or a fluoro group and an organic group containing at least hydrogen can be used as a substituent. Note that the insulating film **7019** can be provided to cover the gate electrode **7017** directly without provision of the insulating film **7018**.

As a conductive film **7023**, a single film of an element such as Al, Ni, C, W, Mo, Ti, Pt, Cu, Ta, Au, Mn, or the like, a nitride film containing the aforementioned element, an alloy film in which the aforementioned elements are combined, a silicide film containing the aforementioned element, or the like can be used. For example, as an alloy containing a plurality of the aforementioned elements, an Al alloy containing

C and Ti, an Al alloy containing Ni, an Al alloy containing C and Ni, an Al alloy containing C and Mn, or the like can be used. When the conductive film has a stacked-layer structure, a structure can be such that Al is interposed between Mo, Ti, or the like; thus, resistance of Al to heat and chemical reaction can be improved.

Next, characteristics of each structure are described with reference to the cross-sectional view of the plurality of transistors each having a different structure in FIG. **29A**.

A transistor **7001** is a single drain transistor. Since it can be formed by a simple method, it is advantageous in low manufacturing cost and high yield. Note that a tapered angle is 45° or more and less than 95°, and preferably, 60° or more and less than 95°. The tapered angle may be less than 45°. Here, the semiconductor layers **7013** and **7015** have different concentrations of impurities, and the semiconductor layer **7013** is used as a channel region and the semiconductor layers **7015** are used as a source region and a drain region. By controlling the concentration of impurities in this manner, resistivity of the semiconductor layer can be controlled. Further, an electrical connection state of the semiconductor layer and the conductive film **7023** can be closer to ohmic contact. Note that as a method of separately forming the semiconductor layers each having different amount of impurities, a method where impurities are doped in the semiconductor layer using the gate electrode **7017** as a mask can be used.

In a transistor **7002**, the gate electrode **7017** is tapered at an angle of at least certain degrees. Since it can be formed by a simple method, it is advantageous in low manufacturing cost and high yield. Here, the semiconductor layers **7013**, **7014**, and **7015** have different concentrations of impurities. The semiconductor layer **7013** is used as a channel region, the semiconductor layers **7014** as lightly doped drain (LDD) regions, and the semiconductor layers **7015** as a source region and a drain region. By controlling the amount of impurities in this manner, resistivity of the semiconductor layer can be controlled. Further, an electrical connection state of the semiconductor layer and the conductive film **7023** can be closer to ohmic contact. Moreover, since the transistor includes the LDD regions, high electric field is hardly applied inside the transistor, so that deterioration of the element due to hot carriers can be suppressed. Note that as a method of separately forming the semiconductor layers having different amount of impurities, a method where impurities are doped in the semiconductor layer using the gate electrode **7017** as a mask can be used. In the transistor **7002**, since the gate electrode **7017** is tapered at an angle of at least certain degrees, gradient of the concentration of impurities doped in the semiconductor layer through the gate electrode **7017** can be provided, and the LDD region can be easily formed. Note that the tapered angle is 45° or more and less than 95°, and preferably, 60° or more and less than 95°. Alternatively, the tapered angle can be less than 45°.

A transistor **7003** has a structure where the gate electrode **7017** is formed of at least two layers and a lower gate electrode is longer than an upper gate electrode. In this specification, a shape of the lower and upper gate electrodes is called a hat shape. When the gate electrode **7017** has a hat shape, an LDD region can be formed without addition of a photomask. Note that a structure where the LDD region overlaps with the gate electrode **7017**, like the transistor **7003**, is particularly called a GOLD (Gate Overlapped LDD) structure. As a method of forming the gate electrode **7017** with a hat shape, the following method may be used.

First, when the gate electrode **7017** is etched, the lower and upper gate electrodes are etched by dry etching so that side surfaces thereof are inclined (tapered). Then, an inclination of

the upper gate electrode is processed to be almost perpendicular by anisotropic etching. Thus, the gate electrode a cross section of which is a hat shape is formed. After that, impurity elements are doped twice, so that the semiconductor layer **7013** used as the channel region, the semiconductor layers **7014** used as the LDD regions, and the semiconductor layers **7015** used as a source electrode and a drain electrode are formed.

Note that part of the LDD region, which overlaps with the gate electrode **7017**, is referred to as an Lov region, and part of the LDD region, which does not overlap with the gate electrode **7017**, is referred to as an Loff region. The Loff region is highly effective in suppressing an off-current value, whereas it is not very effective in preventing deterioration in an on-current value due to hot carriers by relieving an electric field in the vicinity of the drain. On the other hand, the Lov region is highly effective in preventing deterioration in the on-current value by relieving the electric field in the vicinity of the drain, whereas it is not very effective in suppressing the off-current value. Thus, it is preferable to form a transistor having a structure appropriate for characteristics of each of the various circuits. For example, when a semiconductor device is used for a display device, a transistor having an Loff region is preferably used as a pixel transistor in order to suppress the off-current value. On the other hand, as a transistor in a peripheral circuit, a transistor having an Lov region is preferably used in order to prevent deterioration in the on-current value by relieving the electric field in the vicinity of the drain.

A transistor **7004** includes a sidewall **7021** in contact with the side surface of the gate electrode **7017**. When the transistor includes the sidewall **7021**, a region overlapping with the sidewall **7021** can be made to be an LDD region.

In a transistor **7005**, an LDD (Loff) region is formed by doping in the semiconductor layer with the use of a mask **7022**. Thus, the LDD region can surely be formed, and an off-current value of the transistor can be reduced.

In a transistor **7006**, an LDD (Lov) region is formed by doping in the semiconductor layer with the use of a mask. Thus, the LDD region can surely be formed, and deterioration in an on-current value can be prevented by relieving the electric field in the vicinity of the drain of the transistor.

Next, an example of a method for manufacturing a transistor is described with reference to FIGS. **29B** to **29G**.

Note that a structure and a manufacturing method of a transistor are not limited to those in FIGS. **29A** to **29G**, and various structures and manufacturing methods can be used.

In this embodiment mode, surfaces of the substrate **7011**, the insulating film **7012**, the semiconductor layers **7013**, **7014**, and **7015**, the insulating film **7016**, the insulating film **7018**, or the insulating film **7019** are oxidized or nitrided by plasma treatment, so that the semiconductor layer or the insulating film can be oxidized or nitrided. By oxidizing or nitriding the semiconductor layer or the insulating film by plasma treatment in such a manner, a surface of the semiconductor layer or the insulating film is modified, and the insulating film can be formed to be denser than an insulating film formed by a CVD method or a sputtering method. Thus, a defect such as a pinhole can be suppressed, and characteristics and the like of a semiconductor device can be improved. Note that an insulating film **7024** formed by plasma treatment is referred to as a plasma-treated insulating film.

Silicon oxide (SiOx) or silicon nitride (SiNx) can be used for the sidewall **7021**. As a method of forming the sidewall **7021** on the side surface of the gate electrode **7017**, a method where a silicon oxide (SiOx) film or a silicon nitride (SiNx) film is formed after the gate electrode **7017** is formed, and

then, the silicon oxide (SiOx) film or the silicon nitride (SiNx) film is etched by anisotropic etching can be used, for example. Thus, the silicon oxide (SiOx) film or the silicon nitride (SiNx) film remains only on the side surface of the gate electrode **7017**, so that the sidewall **7021** can be formed on the side surface of the gate electrode **7017**.

Note that a conductive film may be provided under the insulating film **7012**. This conductive film functions as a common electrode in some cases.

FIG. **33** shows cross-sectional structures of a bottom-gate transistor and a capacitor.

A first insulating film (an insulating film **7092**) is formed over an entire surface of a substrate **7091**. Note that the structure is not limited thereto, and the first insulating film (the insulating film **7092**) is not formed in some cases. The first insulating film can prevent impurities from the substrate from adversely affecting a semiconductor layer and changing properties of a transistor. That is, the first insulating film functions as a base film. Thus, a transistor with high reliability can be formed. As the first insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

A first conductive layer (a conductive layer **7093** and a conductive layer **7094**) is formed over the first insulating film. The conductive layer **7093** includes a portion functioning as a gate electrode of a transistor **7108**. The conductive layer **7094** includes a portion functioning as a first electrode of a capacitor **7109**. As the first conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba, Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

A second insulating film (an insulating film **7104**) is formed to cover at least the first conductive layer. The second insulating film functions as a gate insulating film. As the second insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

Note that as a portion of the second insulating film, which is in contact with the semiconductor layer, a silicon oxide film is preferably used. This is because the trap level at the interface between the semiconductor layer and the second insulating film is lowered.

When the second insulating film is in contact with Mo, a silicon oxide film is preferably used as a portion of the second insulating film in contact with Mo. This is because the silicon oxide film does not oxidize Mo.

A semiconductor layer is formed in part of a portion over the second insulating film, which overlaps with the first conductive layer, by a photolithography method, an ink-jet method, a printing method, or the like. Part of the semiconductor layer extends to a portion over the second insulating film, which does not overlap with the first conductive layer. The semiconductor layer includes a channel formation region (a channel formation region **7100**), an LDD region (LDD regions **7098** and **7099**), and an impurity region (impurity regions **7095**, **7096**, and **7097**). The channel formation region **7100** functions as a channel formation region of the transistor **7108**. The LDD regions **7098** and **7099** function as LDD regions of the transistor **7108**. Note that the LDD regions **7098** and **7099** are not always necessarily formed. The impurity region **7095** includes a portion functioning as one of a source electrode and a drain electrode of the transistor **7108**. The impurity region **7096** includes a portion functioning as the other of the source electrode and the drain electrode of the transistor **7108**. The impurity region **7097** includes a portion functioning as a second electrode of the capacitor **7109**.

A third insulating film (an insulating film **7101**) is formed over the entire surface. A contact hole is selectively formed in part of the third insulating film. The insulating film **7101** functions as an interlayer film. As the third insulating film, an inorganic material (e.g., silicon oxide, silicon nitride, or silicon oxynitride), an organic compound material having a low dielectric constant (e.g., a photosensitive or nonphotosensitive organic resin material), or the like can be used. Alternatively, a material containing siloxane may be used. Note that siloxane is a material in which a skeleton structure is formed by a bond of silicon (Si) and oxygen (O). As a substitute, an organic group containing at least hydrogen (such as an alkyl group or aromatic hydrocarbon) is used. Alternatively, a fluoro group, or a fluoro group and an organic group containing at least hydrogen may be used as a substituent.

A second conductive layer (a conductive layer **7102** and a conductive layer **7103**) is formed over the third insulating film. The conductive layer **7102** is connected to the other of the source electrode and the drain electrode of the transistor **7108** through the contact hole formed in the third insulating film. Thus, the conductive layer **7102** includes a portion functioning as the other of the source electrode and the drain electrode of the transistor **7108**. When the conductive layer **7103** is electrically connected to the conductive layer **7094**, the conductive layer **7103** includes a portion functioning as the first electrode of the capacitor **7109**. Alternatively, when the conductive layer **7103** is electrically connected to the impurity region **7097** which is a conductive layer, the conductive layer **7103** includes a portion functioning as the second electrode of the capacitor **7109**. Further alternatively, when the conductive layer **7103** is not connected to the conductive layer **7094** and the impurity region **7097**, a capacitor other than the capacitor **7109** is formed. In this capacitor, the conductive layer **7103**, the impurity region **7097**, and the insulating film **7101** are used as a first electrode, a second electrode, and an insulating film, respectively. Note that as the second conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba, Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

In steps after forming the second conductive layer, various insulating films or various conductive films may be formed.

Note that a conductive film may be provided under the insulating film **7092**. This conductive film functions as a common electrode in some cases.

Next, structures of a transistor and a capacitor are described when an amorphous silicon (a-Si:H) film, a microcrystalline silicon film, or the like is used as a semiconductor layer of the transistor.

FIG. **30** shows cross-sectional structures of a top-gate transistor and a capacitor.

A first insulating film (an insulating film **7032**) is formed over an entire surface of a substrate **7031**. The first insulating film can prevent impurities from the substrate from adversely affecting a semiconductor layer and changing properties of a transistor. That is, the first insulating film functions as a base film. Thus, a transistor with high reliability can be formed. As the first insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

Note that the first insulating film is not always necessarily formed. When the first insulating film is not formed, reduction in the number of steps and manufacturing cost can be realized. Further, since the structure can be simplified, the yield can be improved.

A first conductive layer (a conductive layer **7033**, a conductive layer **7034**, and a conductive layer **7035**) is formed

over the first insulating film. The conductive layer **7033** includes a portion functioning as one of a source electrode and a drain electrode of a transistor **7048**. The conductive layer **7034** includes a portion functioning as the other of the source electrode and the drain electrode of the transistor **7048**. The conductive layer **7035** includes a portion functioning as a first electrode of a capacitor **7049**. As the first conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba, Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

A first semiconductor layer (a semiconductor layer **7036** and a semiconductor layer **7037**) is formed above the conductive layers **7033** and **7034**. The semiconductor layer **7036** includes a portion functioning as one of the source electrode and the drain electrode. The semiconductor layer **7037** includes a portion functioning as the other of the source electrode and the drain electrode. As the first semiconductor layer, silicon containing phosphorus or the like can be used.

A second semiconductor layer (a semiconductor layer **7038**) is formed over the first insulating film and between the conductive layer **7033** and the conductive layer **7034**. Part of the semiconductor layer **7038** extends over the conductive layers **7033** and **7034**. The semiconductor layer **7038** includes a portion functioning as a channel region of the transistor **7048**. As the second semiconductor layer, a semiconductor layer having no crystallinity such as amorphous silicon (a-Si:H), a semiconductor layer such as a microcrystalline semiconductor (μ -Si:H), or the like can be used.

A second insulating film (an insulating film **7039** and an insulating film **7040**) is formed to cover at least the semiconductor layer **7038** and the conductive layer **7035**. The second insulating film functions as a gate insulating film. As the second insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

Note that as a portion of the second insulating film, which is in contact with the second semiconductor layer, a silicon oxide film is preferably used. This is because the trap level at the interface between the second semiconductor layer and the second insulating film is lowered.

Note that when the second insulating film is in contact with Mo, a silicon oxide film is preferably used as a portion of the second insulating film in contact with Mo. This is because the silicon oxide film does not oxidize Mo.

A second conductive layer (a conductive layer **7041** and a conductive layer **7042**) is formed over the second insulating film. The conductive layer **7041** includes a portion functioning as a gate electrode of the transistor **7048**. The conductive layer **7042** functions as a second electrode of the capacitor **7049** or a wiring. As the second conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba, Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

In steps after forming the second conductive layer, various insulating films or various conductive films may be formed.

Note that a conductive film may be provided under the insulating film **7032**. This conductive film functions as a common electrode in some cases.

FIG. **31** shows cross-sectional structures of an inversely staggered (bottom gate) transistor and a capacitor. In particular, the transistor shown in FIG. **31** has a channel etch structure.

A first insulating film (an insulating film **7052**) is formed over an entire surface of a substrate **7051**. The first insulating film can prevent impurities from the substrate from adversely

affecting a semiconductor layer and changing properties of a transistor. That is, the first insulating film functions as a base film. Thus, a transistor with high reliability can be formed. As the first insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

Note that the first insulating film is not always necessarily formed. When the first insulating film is not formed, reduction in the number of steps and manufacturing cost can be realized. Further, since the structure can be simplified, the yield can be improved.

A first conductive layer (a conductive layer **7053** and a conductive layer **7054**) is formed over the first insulating film. The conductive layer **7053** includes a portion functioning as a gate electrode of a transistor **7068**. The conductive layer **7054** includes a portion functioning as a first electrode of a capacitor **7069**. As the first conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba, Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

A second insulating film (an insulating film **7055**) is formed to cover at least the first conductive layer. The second insulating film functions as a gate insulating film. As the second insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

Note that as a portion of the second insulating film, which is in contact with the semiconductor layer, a silicon oxide film is preferably used. This is because the trap level at the interface between the semiconductor layer and the second insulating film is lowered.

When the second insulating film is in contact with Mo, a silicon oxide film is preferably used as a portion of the second insulating film in contact with Mo. This is because the silicon oxide film does not oxidize Mo.

A first semiconductor layer (a semiconductor layer **7056**) is formed in part of a portion over the second insulating film, which overlaps with the first conductive layer, by a photolithography method, an ink-jet method, a printing method, or the like. Part of the semiconductor layer **7056** extends to a portion over the second insulating film, which does not overlap with the first conductive layer. The semiconductor layer **7056** includes a portion functioning as a channel region of the transistor **7068**. As the semiconductor layer **7056**, a semiconductor layer having no crystallinity such as amorphous silicon (a-Si:H), a semiconductor layer such as a microcrystalline semiconductor (μ -Si:H), or the like can be used.

A second semiconductor layer (a semiconductor layer **7057** and a semiconductor layer **7058**) is formed over part of the first semiconductor layer. The semiconductor layer **7057** includes a portion functioning as one of a source electrode and a drain electrode. The semiconductor layer **7058** includes a portion functioning as the other of the source electrode and the drain electrode. As the second semiconductor layer, silicon containing phosphorus or the like can be used.

A second conductive layer (a conductive layer **7059**, a conductive layer **7060**, and a conductive layer **7061**) is formed over the second semiconductor layer and the second insulating film. The conductive layer **7059** includes a portion functioning as one of a source electrode and a drain electrode of the transistor **7068**. The conductive layer **7060** includes a portion functioning as the other of the source electrode and the drain electrode of the transistor **7068**. The conductive layer **7061** includes a portion functioning as a second electrode of the capacitor **7069**. As the second conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba,

Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

In steps after forming the second conductive layer, various insulating films or various conductive films may be formed.

Here, an example of a step of forming a channel etch type transistor is described. The first semiconductor layer and the second semiconductor layer can be formed using the same mask. Specifically, the first semiconductor layer and the second semiconductor layer are sequentially formed. At this time, the first semiconductor layer and the second semiconductor layer are formed using the same mask.

Another example of a step of forming a channel etch type transistor is described. Without using an additional mask, a channel region of a transistor can be formed. Specifically, after the second conductive layer is formed, part of the second semiconductor layer is removed using the second conductive layer as a mask. Alternatively, part of the second semiconductor layer is removed by using the same mask as the second conductive layer. The first semiconductor layer below the removed second semiconductor layer functions as a channel region of the transistor.

Note that a conductive film may be provided under the insulating film **7052**. This conductive film functions as a common electrode in some cases.

FIG. 32 shows cross-sectional structures of an inversely staggered (bottom gate) transistor and a capacitor. In particular, the transistor shown in FIG. 32 has a channel protection (channel stop) structure.

A first insulating film (an insulating film **7072**) is formed over an entire surface of a substrate **7071**. The first insulating film can prevent impurities from the substrate from adversely affecting a semiconductor layer and changing properties of a transistor. That is, the first insulating film functions as a base film. Thus, a transistor with high reliability can be formed. As the first insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

Note that the first insulating film is not always necessarily formed. When the first insulating film is not formed, reduction in the number of steps and manufacturing cost can be realized. Further, since the structure can be simplified, the yield can be improved.

A first conductive layer (a conductive layer **7073** and a conductive layer **7074**) is formed over the first insulating film. The conductive layer **7073** includes a portion functioning as a gate electrode of a transistor **7088**. The conductive layer **7074** includes a portion functioning as a first electrode of a capacitor **7089**. As the first conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba, Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

A second insulating film (an insulating film **7075**) is formed to cover at least the first conductive layer. The second insulating film functions as a gate insulating film. As the second insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

Note that as a portion of the second insulating film, which is in contact with the semiconductor layer, a silicon oxide film is preferably used. This is because the trap level at the interface between the semiconductor layer and the second insulating film is lowered.

When the second insulating film is in contact with Mo, a silicon oxide film is preferably used as a portion of the second

insulating film in contact with Mo. This is because the silicon oxide film does not oxidize Mo.

A first semiconductor layer (a semiconductor layer 7076) is formed in part of a portion over the second insulating film, which overlaps with the first conductive layer, by a photolithography method, an ink-jet method, a printing method, or the like. Part of the semiconductor layer 7076 extends to a portion over the second insulating film, which does not overlap with the first conductive layer. The semiconductor layer 7076 includes a portion functioning as a channel region of the transistor 7088. As the semiconductor layer 7076, a semiconductor layer having no crystallinity such as amorphous silicon (a-Si:H), a semiconductor layer such as a microcrystalline semiconductor (μ -Si:H), or the like can be used.

A third insulating film (an insulating film 7082) is formed over part of the first semiconductor layer. The insulating film 7082 has a function to prevent the channel region of the transistor 7088 from being removed by etching. That is, the insulating film 7082 functions as a channel protection film (a channel stop film). As the third insulating film, a single layer or a stacked layer of a silicon oxide film, a silicon nitride film, a silicon oxynitride film (SiOxNy), or the like can be used.

A second semiconductor layer (a semiconductor layer 7077 and a semiconductor layer 7078) is formed over part of the first semiconductor layer and part of the third insulating film. The semiconductor layer 7077 includes a portion functioning as one of a source electrode and a drain electrode. The semiconductor layer 7078 includes a portion functioning as the other of the source electrode and the drain electrode. As the second semiconductor layer, silicon containing phosphorus or the like can be used.

A second conductive layer (a conductive layer 7079, a conductive layer 7080, and a conductive layer 7081) is formed over the second semiconductor layer. The conductive layer 7079 includes a portion functioning as one of the source electrode and the drain electrode of the transistor 7088. The conductive layer 7080 includes a portion functioning as the other of the source electrode and the drain electrode of the transistor 7088. The conductive layer 7081 includes a portion functioning as a second electrode of the capacitor 7089. As the second conductive layer, Ti, Mo, Ta, Cr, W, Al, Nd, Cu, Ag, Au, Pt, Nb, Si, Zn, Fe, Ba, Ge, or the like, or an alloy of these elements can be used. Further, a stacked layer of these elements (including the alloy thereof) can be used.

In steps after forming the second conductive layer, various insulating films or various conductive films may be formed.

Note that a conductive film may be provided under the insulating film 7072. This conductive film functions as a common electrode in some cases.

Next, an example where a semiconductor substrate is used as a substrate for a transistor. Since a transistor formed using a semiconductor substrate has high mobility, the size of the transistor can be decreased. Accordingly, the number of transistors per unit area can be increased (the degree of integration can be improved), and the size of the substrate can be decreased as the degree of integration is increased in the case of the same circuit structure. Thus, manufacturing cost can be reduced. Further, since the circuit scale can be increased as the degree of integration is increased in the case of the same substrate size, more advanced function can be provided without increase in manufacturing cost. Moreover, reduction in variations in characteristics can improve manufacturing yield. Reduction in operating voltage can reduce power consumption. High mobility can realize high-speed operation.

When a circuit which is formed by integrating transistors formed using a semiconductor substrate is mounted on a device in the form of an IC chip or the like, the circuit can

provide the device with various functions. For example, a peripheral driver circuit (e.g., a data driver (a source driver), a scan driver (a gate driver), a timing controller, an image processing circuit, an interface circuit, a power supply circuit, or an oscillation circuit) of a display device is formed by integrating transistors formed using a semiconductor substrate, so that a small peripheral circuit which can operate with low power consumption and at high speed can be formed at low cost in high yield. Note that a circuit which is formed by integrating transistors formed using a semiconductor substrate may have a unipolar transistor. Thus, a manufacturing process can be simplified, so that manufacturing cost can be reduced.

A circuit which is formed by integrating transistors formed using a semiconductor substrate may also be used for a display panel, for example. More specifically, the circuit can be used for a reflective liquid crystal panel such as a liquid crystal on silicon (LCOS) device, a digital micromirror device (DMD) in which micromirrors are integrated, an EL panel, and the like. When such a display panel is formed using a semiconductor substrate, a small display panel which can operate with low power consumption and at high speed can be formed at low cost in high yield. Note that the display panel may be formed over an element having a function other than a function to drive the display panel, such as a large-scale integration (LSI).

Note that a structure of a transistor is not limited to the structure shown in each drawing. For example, a transistor may have an inversely staggered structure, a FinFET structure, or the like. It is preferable to have a FinFET structure since a short channel effect due to miniaturization of transistor size can be suppressed.

The above is the description of the structures and manufacturing methods of transistors. Here, a wiring, an electrode, a conductive layer, a conductive film, a terminal, a via, a plug, and the like are preferably formed of one or more elements selected from aluminum (Al), tantalum (Ta), titanium (Ti), molybdenum (Mo), tungsten (W), neodymium (Nd), chromium (Cr), nickel (Ni), platinum (Pt), gold (Au), silver (Ag), copper (Cu), magnesium (Mg), scandium (Sc), cobalt (Co), zinc (Zn), niobium (Nb), silicon (Si), phosphorus (P), boron (B), arsenic (As), gallium (Ga), indium (In), tin (Sn), and oxygen (O); or a compound or an alloy material including one or more of the aforementioned elements (e.g., indium tin oxide (ITO), indium zinc oxide (IZO), indium tin oxide containing silicon (ITSO), zinc oxide (ZnO), tin oxide (SnO), cadmium tin oxide (CTO), aluminum neodymium (Al—Nd), magnesium silver (Mg—Ag), or molybdenum-niobium (Mo—Nb)); a substance in which these compounds are combined; or the like. Alternatively, they are preferably formed to contain a substance including a compound (silicide) of silicon and one or more of the aforementioned elements (e.g., aluminum silicon, molybdenum silicon, or nickel silicide); or a compound of nitrogen and one or more of the aforementioned elements (e.g., titanium nitride, tantalum nitride, or molybdenum nitride).

Note that silicon (Si) may contain an n-type impurity (such as phosphorus) or a p-type impurity (such as boron). When silicon contains the impurity, the conductivity is increased, and a function similar to a general conductor can be realized. Thus, such silicon can be utilized easily as a wiring, an electrode, or the like.

In addition, silicon with various levels of crystallinity, such as single crystalline silicon, polycrystalline silicon, or microcrystalline silicon can be used. Alternatively, silicon having no crystallinity, such as amorphous silicon can be used. By using single crystalline silicon or polycrystalline silicon,

resistance of a wiring, an electrode, a conductive layer, a conductive film, a terminal, or the like can be reduced. By using amorphous silicon or microcrystalline silicon, a wiring or the like can be formed by a simple process.

Aluminum and silver have high conductivity, and thus can reduce a signal delay. Further, since aluminum and silver can be easily etched, they can be minutely processed.

Copper has high conductivity, and thus can reduce a signal delay. When copper is used, a stacked-layer structure is preferably employed to improve adhesion.

Molybdenum and titanium are preferable since even if molybdenum or titanium is in contact with an oxide semiconductor (e.g., ITO or IZO) or silicon, molybdenum or titanium does not cause defects. Further, molybdenum and titanium are preferable since they are easily etched and has high heat resistance.

Tungsten is preferable since it has an advantage such as high heat resistance.

Neodymium is also preferable since it has an advantage such as high heat resistance. In particular, an alloy of neodymium and aluminum is preferable since heat resistance is increased and aluminum hardly causes hillocks.

Silicon is preferable since it can be formed at the same time as a semiconductor layer included in a transistor and has high heat resistance.

Since ITO, IZO, ITSO, zinc oxide (ZnO), silicon (Si), tin oxide (SnO), and cadmium tin oxide (CTO) have light-transmitting properties, they can be used as a portion which transmits light. For example, they can be used for a pixel electrode or a common electrode.

IZO is preferable since it is easily etched and processed. In etching IZO, a residue is hardly left. Thus, when IZO is used for a pixel electrode, defects (such as short circuit or orientation disorder) of a liquid crystal element or a light-emitting element can be reduced.

A wiring, an electrode, a conductive layer, a conductive film, a terminal, a via, a plug, or the like may have a single-layer structure or a multi-layer structure. By employing a single-layer structure, each manufacturing process of a wiring, an electrode, a conductive layer, a conductive film, a terminal, or the like can be simplified, the number of steps for a process can be reduced, and cost can be reduced. Alternatively, by employing a multi-layer structure, a wiring, an electrode, and the like with high quality can be formed while an advantage of each material is utilized and a disadvantage thereof is reduced. For example, when a low-resistant material (e.g., aluminum) is included in a multi-layer structure, reduction in resistance of a wiring can be realized. As another example, when a stacked-layer structure where a low heat-resistant material is interposed between high heat-resistant materials is employed, heat resistance of a wiring, an electrode, and the like can be increased, utilizing advantages of the low heat-resistance material. For example, it is preferable to employ a stacked-layer structure where a layer containing aluminum is interposed between layers containing molybdenum, titanium, neodymium, or the like.

When wirings, electrodes, or the like are in direct contact with each other, they adversely affect each other in some cases. For example, one wiring or one electrode is mixed into a material of another wiring or another electrode and changes its properties, and thus, an intended function cannot be obtained in some cases. As another example, when a high-resistant portion is formed, a problem may occur so that it cannot be normally formed. In such cases, a reactive material is preferably interposed by or covered with a non-reactive material in a stacked-layer structure. For example, when ITO and aluminum are connected, titanium, molybdenum, or an

alloy of neodymium is preferably interposed between ITO and aluminum. As another example, when silicon and aluminum are connected, titanium, molybdenum, or an alloy of neodymium is preferably interposed between silicon and aluminum.

The term "wiring" indicates a portion including a conductor. A wiring may be a linear shape or may be short without a linear shape. Therefore, an electrode is included in a wiring.

Note that a carbon nanotube may be used for a wiring, an electrode, a conductive layer, a conductive film, a terminal, a via, a plug, or the like. Since a carbon nanotube has a light-transmitting property, it can be used for a portion which transmits light. For example, a carbon nanotube can be used for a pixel electrode or a common electrode.

Although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

This embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

Embodiment Mode 8

In this embodiment mode, a structure of a display device is described.

A structure of a display device is described with reference to FIG. 34A. FIG. 34A is a top plan view of the display device. A pixel portion 8201, a scan line input terminal 8203, and a signal line input terminal 8204 are formed over a substrate 8200. Scan lines extending in a row direction from the scan line input terminal 8203 are formed over the substrate 8200, and signal lines extending in a column direction from the signal line input terminal 8204 are formed over the substrate 8200. Pixels 8202 are arranged in matrix at each intersection of the scan lines and the signal lines in the pixel portion 8201.

The above is the description of the case where a signal is input from an external driver circuit; however, the invention is not limited thereto, and an IC chip can be mounted on a display device.

For example, as shown in FIG. 35A, an IC chip 8211 can be mounted on the substrate 8200 by a COG (Chip On Glass) method. In this case, the IC chip 8211 can be examined before being mounted on the substrate 8200, so that improvement in yield and reliability of the display device can be realized. Note that portions common to those in FIG. 34A are denoted by common reference numerals, and description thereof is omitted.

As another example, as shown in FIG. 35B, the IC chip 8211 can be mounted on an FPC (Flexible Printed Circuit) 8210 by a TAB (Tape Automated Bonding) method. In this case, the IC chip 8211 can be examined before being mounted on the FPC 8210, so that improvement in yield and reliability

of the display device can be realized. Note that portions common to those in FIG. 34A are denoted by common reference numerals, and description thereof is omitted.

Not only the IC chip can be mounted on the substrate **8200**, but also a driver circuit can be formed over the substrate **8200**.

For example, as shown in FIG. 34B, a scan line driver circuit **8205** can be formed over the substrate **8200**. In this case, the cost can be reduced by reduction in the number of components. Further, reliability can be improved by reduction in the number of connection points between components. Since the driving frequency of the scan line driver circuit **8205** is low, the scan line driver circuit **8205** can be easily formed using amorphous silicon or microcrystalline silicon as a semiconductor layer of a transistor. Note that an IC chip for outputting a signal to the signal line may be mounted on the substrate **8200** by a COG method. Alternatively, an FPC on which an IC chip for outputting a signal to the signal line is mounted by a TAB method may be provided on the substrate **8200**. In addition, an IC chip for controlling the scan line driver circuit **8205** may be mounted on the substrate **8200** by a COG method. Alternatively, an FPC on which an IC chip for controlling the scan line driver circuit **8205** is mounted by a TAB method may be provided on the substrate **8200**. Note that portions common to those in FIG. 34A are denoted by common reference numerals, and description thereof is omitted.

As another example, as shown in FIG. 34C, the scan line driver circuit **8205** and a signal line driver circuit **8206** can be formed over the substrate **8200**. Thus, the cost can be reduced by reduction in the number of components. Further, reliability can be improved by reduction in the number of connection points between components. Note that an IC chip for controlling the scan line driver circuit **8205** may be mounted on the substrate **8200** by a COG method. Alternatively, an FPC on which an IC chip for controlling the scan line driver circuit **8205** is mounted by a TAB method may be provided on the substrate **8200**. In addition, an IC chip for controlling the signal line driver circuit **8206** may be mounted on the substrate **8200** by a COG method. Alternatively, an FPC on which an IC chip for controlling the signal line driver circuit **8206** is mounted by a TAB method may be provided on the substrate **8200**. Note that portions common to those in FIG. 34A are denoted by common reference numerals, and description thereof is omitted.

Although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

This embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

In this embodiment mode, an operation of a display device is described.

FIG. 36 shows a structure example of a display device.

A display device **8400** includes a pixel portion **8401**, a signal line driver circuit **8403**, and a scan line driver circuit **8404**. In the pixel portion **8401**, a plurality of signal lines **S1** to **Sn** extend from the signal line driver circuit **8403** in a column direction. In the pixel portion **8401**, a plurality of scan lines **G1** to **Gm** extend from the scan line driver circuit **8404** in a row direction. Pixels **8402** are arranged in matrix at each intersection of the plurality of signal lines **S1** to **Sn** and the plurality of scan lines **G1** to **Gm**.

The signal line driver circuit **8403** has a function to output a signal to each of the signal lines **S1** to **Sn**. This signal may be referred to as a video signal. The scan line driver circuit **8404** has a function to output a signal to each of the scan lines **G1** to **Gm**. This signal may be referred to as a scan signal.

The pixel **8402** may include at least a switching element connected to the signal line. On/off of the switching element is controlled by a potential of a scan line (a scan signal). When the switching element is turned on, the pixel **8402** is selected. On the other hand, when the switching element is turned off, the pixel **8402** is not selected.

When the pixel **8402** is selected (a selection state), a video signal is input to the pixel **8402** from the signal line. A state (e.g., luminance, transmittance, or voltage of a storage capacitor) of the pixel **8402** is changed in accordance with the video signal input.

When the pixel **8402** is not selected (a non-selection state), the video signal is not input to the pixel **8402**. Note that the pixel **8402** holds a potential corresponding to the video signal which is input when selected; thus, the pixel **8402** maintains the state (e.g., luminance, transmittance, or voltage of a storage capacitor) in accordance with the video signal.

A structure of the display device is not limited to that shown in FIG. 36. For example, an additional wiring (such as a scan line, a signal line, a power supply line, a capacitor line, or a common line) may be added in accordance with the structure of the pixel **8402**. As another example, a circuit having various functions may be added.

FIG. 37 shows an example of a timing chart for describing an operation of a display device.

The timing chart of FIG. 37 shows one frame period corresponding to a period when an image of one screen is displayed. On one frame period is not particularly limited, but one frame period is preferably $\frac{1}{60}$ second or less so that a viewer does not perceive a flicker.

The timing chart of FIG. 37 shows timing for selecting the scan line **G1** in the first row, the scan line **Gi** (one of the scan lines **G1** to **Gm**) in the *i*-th row, the scan line **Gi+1** in the (*i*+1)-th row, and the scan line **Gm** in the *m*-th row.

At the same time as the scan line is selected, the pixel **8402** connected to the scan line is also selected. For example, when the scan line **Gi** in the *i*-th row is selected, the pixel **8402** connected to the scan line **Gi** in the *i*-th row is also selected.

The scan lines **G1** to **Gm** are sequentially selected (also referred to as scanned) from the scan line **G1** in the first row to the scan line **Gm** in the *m*-th row. For example, while the scan line **Gi** in the *i*-th row is selected, the scan lines (**G1** to **Gi-1** and **Gi+1** to **Gm**) other than the scan line **Gi** in the *i*-th row are not selected. Then, during the next period, the scan line **Gi+1** in the (*i*+1)-th row is selected. The period during which one scan line is selected is referred to as one gate selection period.

Therefore, when a scan line in a certain row is selected, a plurality of pixels **8402** connected to the scan line receive a video signal from each of the signal lines **S1** to **Sn**. For example, when the scan line **Gi** in the *i*-th row is selected, the plurality of pixels **8402** connected to the scan line **Gi** in the *i*-th row receive a given video signal from each of the signal lines **S1** to **Sn**. Thus, each of the plurality of pixels **8402** can be controlled individually by the scan signal and the video signal.

Next, the case where one gate selection period is divided into a plurality of subgate selection periods is described.

FIG. **38** is a timing chart in the case where one gate selection period is divided into two subgate selection periods (a first subgate selection period and a second subgate selection period).

Note that one gate selection period may be divided into three or more subgate selection periods.

The timing chart of FIG. **38** shows one frame period corresponding to a period when an image of one screen is displayed. One frame period is not particularly limited, but one frame period is preferably $\frac{1}{60}$ second or less so that a viewer does not perceive a flicker.

Note that one frame is divided into two subframes (a first subframe and a second subframe).

The timing chart of FIG. **38** shows timing for selecting the scan line **Gi** in the *i*-th row, the scan line **Gi+1** in the (*i*+1)th row, the scan line **Gj** (one of the scan lines **Gi+1** to **Gm**) in the *j*-th row, and the scan line **Gj+1** in the (*j*+1)th row.

At the same time as the scan line is selected, the pixel **8402** connected to the scan line is also selected. For example, when the scan line **Gi** in the *i*-th row, the pixel **8402** connected to the scan line **Gi** in the *i*-th row is also selected.

The scan lines **G1** to **Gm** are sequentially scanned in each subgate selection period. For example, in a certain one gate selection period, the scan line **Gi** in the *i*-th row is selected in the first subgate selection period, and the scan line **Gj** in the *j*-th row is selected in the second subgate selection period. Thus, in one gate selection period, an operation can be performed as if the scan signals of two rows are selected. At this time, different video signals are input to the signal lines **S1** to **Sn** in the first subgate selection period and the second subgate selection period. Accordingly, a plurality of pixels **8402** connected to the scan line **Gi** in the *i*-th row can receive a different video signal from a plurality of pixels **8402** connected to the scan line **Gj** in the *j*-th row.

Next, a driving method for displaying images with high quality is described.

FIGS. **39A** and **39B** are views for describing high frequency driving.

FIG. **39A** shows the case where an interpolation image is displayed between two input images. A period **8410** is a cycle of an input image signal. An image **8411**, an image **8412**, an image **8413**, and an image **8414** are a first input image, a first interpolation image, a second input image, and a second interpolation image, respectively. Here, the input image corresponds to an image based on a signal input from outside of a display device. Further, the interpolation image corresponds to an image which is displayed at a timing different from that of the input image so as to interpolate an image.

The image **8412** is an image formed based on image signals of the images **8411** and **8413**. Specifically, movement of an object is estimated by difference between a position of the object included in the image **8411** and a position of the object included in the image **8413**, and the image can be made in which the position of the object included in the image **8412** is at an intermediate state between the image **8411** and the image **8413**. This process is referred to as motion compensa-

tion. Since the image **8412** is formed by motion compensation, the object at the intermediate ($\frac{1}{2}$) position, which cannot be displayed only by the input image, can be displayed, and the movement of the object can be smoothed to be displayed.

Alternatively, the image **8412** can be formed by an average value of the image signals of the images **8411** and **8413**. Thus, the load to a circuit due to formation of the interpolation image can be reduced, so that power consumption can be reduced.

Alternatively, the image **8412** can be formed from the image **8411**. Specifically, the image **8412** can be formed by increasing or decreasing brightness of the image **8411** entirely or partially. More specifically, the image with the entire brightness higher or lower can be made by converting gamma characteristics of the image **8411**.

Note that the image **8412** may be a black image. Thus, the quality of a moving image in a hold-type display device can be improved.

FIG. **39B** shows the case where two interpolation images are displayed between two input images. The period **8410** is a cycle of an input image signal. An image **8421**, an image **8422**, an image **8423**, and an image **8424** are a first input image, a first interpolation image, a second interpolation image, and a second input image, respectively.

Each of the image **8422** and the image **8423** can be formed based on image signals of the images **8421** and **8424**. Specifically, the images **8422** and **8423** can be formed by motion compensation using difference between a position of an object included in the image **8421** and a position of the object included in the image **8424**. Since the images **8422** and **8423** are formed by motion compensation, the object at the intermediate ($\frac{1}{3}$ and $\frac{2}{3}$) positions, which cannot be displayed only by the input image, can be displayed, movement of the object can be smoothed to be displayed. In addition, the images **8422** and **8423** can be formed by an average value of the image signals of the images **8421** and **8424**. Thus, the load to a circuit due to formation of the interpolation image can be reduced, so that power consumption can be reduced.

Alternatively, the images **8422** and **8423** can be formed from the images **8421** and **8424**. Specifically, the images **8422** and **8423** can be formed by increasing or decreasing brightness of the image **8421** entirely or partially. More specifically, the image with the entire brightness higher or lower can be made by converting the gamma characteristics of the image **8411**.

Note that the images **8422** and **8423** may be black images. Thus, the quality of a moving image in a hold-type display device can be improved.

Although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

This embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents

described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

Embodiment Mode 10

In this embodiment mode, a peripheral portion of a liquid crystal panel is described.

FIG. 40 shows an example of a liquid crystal display device including a so-called edge-light type backlight unit **5201** and a liquid crystal panel **5207**. An edge-light type corresponds to a type in which a light source is provided at an end of a backlight unit and fluorescence of the light source is emitted from the entire light-emitting surface. The edge-light type backlight unit is thin and can save power.

The backlight unit **5201** includes a diffusion plate **5202**, a light guide plate **5203**, a reflection plate **5204**, a lamp reflector **5205**, and a light source **5206**.

The light source **5206** has a function to emit light as necessary. As the light source **5206**, a cold cathode fluorescent lamp, a hot cathode fluorescent lamp, a light-emitting diode, an inorganic EL element, an organic EL element, or the like can be used, for example.

FIGS. 41A to 41D each show a detailed structure of the edge-light type backlight unit. Note that description of a diffusion plate, a light guide plate, a reflection plate, and the like is omitted.

A backlight unit **5111** shown in FIG. 41A has a structure in which a cold cathode fluorescent lamp **5113** is used as a light source. A lamp reflector **5112** is provided to efficiently reflect light from the cold cathode fluorescent lamp **5113**. Such a structure is often used for a large display device because luminance from the cold cathode fluorescent lamp is high.

A backlight unit **5221** shown in FIG. 41B has a structure in which light-emitting diodes (LEDs) **5223** are used as light sources. For example, the light-emitting diodes (LEDs) **5223** which emit white light are provided at a predetermined interval. Further, a lamp reflector **5222** is provided to efficiently reflect light from the light-emitting diodes (LEDs) **5223**.

A backlight unit **5231** shown in FIG. 41C has a structure in which light-emitting diodes (LEDs) **5233**, light-emitting diodes (LEDs) **5234**, and light-emitting diodes (LEDs) **5235** of each color of RGB are used as light sources. The light-emitting diodes (LEDs) **5233**, **5234**, and **5235** of each color of RGB are provided at a predetermined interval. By using the light-emitting diodes (LEDs) **5233**, **5234**, and **5235** of each color of RGB, color reproducibility can be improved. In addition, a lamp reflector **5232** is provided to efficiently reflect light from the light-emitting diodes.

A backlight unit **5241** shown in FIG. 41D has a structure in which light-emitting diodes (LEDs) **5243**, light-emitting diodes (LEDs) **5244**, and light-emitting diodes (LEDs) **5245** of each color of RGB are used as light sources. For example, among the light-emitting diodes (LEDs) **5243**, **5244**, and **5245** of each color of RGB, the light-emitting diodes of a color with low emission intensity (e.g., green) are provided more than other light-emitting diodes. By using the light-emitting diodes (LEDs) **5243**, **5244**, and **5245** of each color of RGB, color reproducibility can be improved. In addition, a lamp reflector **5242** is provided to efficiently reflect light from the light-emitting diodes.

FIG. 44 shows an example of a liquid crystal display device including a so-called direct-type backlight unit and a liquid crystal panel. A direct type corresponds to a type in which a light source is provided directly under a light-emitting surface and fluorescence of the light source is emitted from the entire light-emitting surface. The direct-type backlight unit can efficiently utilize the amount of emitted light.

A backlight unit **5290** includes a diffusion plate **5291**, a light-shielding plate **5292**, a lamp reflector **5293**, and a light source **5294**.

The light source **5294** has a function to emit light as necessary. As the light source **5294**, a cold cathode fluorescent lamp, a hot cathode fluorescent lamp, a light-emitting diode, an inorganic EL element, an organic EL element, or the like can be used, for example.

FIG. 42 shows an example of a structure of a polarizing plate (also referred to as a polarizing film).

A polarizing film **5250** includes a protective film **5251**, a substrate film **5252**, a PVA polarizing film **5253**, a substrate film **5254**, an adhesive layer **5255**, and a mold release film **5256**.

When the PVA polarizing film **5253** is interposed between films (the substrate films **5252** and **5254**) to be base materials, reliability can be improved. Note that the PVA polarizing film **5253** may be interposed by triacetyl cellulose (TAC) films with high light-transmitting properties and high durability. The substrate films and the TAC films each function as a protective film of a polarizer included in the PVA polarizing film **5253**.

The adhesive layer **5255** which is to be attached to a glass substrate of the liquid crystal panel is attached to one of the substrate films (the substrate film **5254**). Note that the adhesive layer **5255** is formed by applying an adhesive to one of the substrate films (the substrate film **5254**). The adhesive layer **5255** is provided with the mold release film **5256** (a separate film).

The other of the substrates films (the substrate film **5252**) is provided with the protective film **5251**.

A hard coating scattering layer (an anti-glare layer) may be provided on a surface of the polarizing film **5250**. Since the surface of the hard coating scattering layer has minute unevenness formed by AG treatment and has an anti-glare function which scatters external light, reflection of external light in the liquid crystal panel and surface reflection can be prevented.

A treatment in which a plurality of optical thin film layers having different refractive indexes are layered (also referred to as anti-reflection treatment or AR treatment) may be performed on the surface of the polarizing film **5250**. The plurality of layered optical thin film layers having different refractive indexes can reduce reflectivity on the surface by an interference effect of light.

FIGS. 43A to 43C show examples of a system block of a liquid crystal display device.

In a pixel portion **5265**, signal lines **5269** which are extended from a signal line driver circuit **5263** are provided. In the pixel portion **5265**, scan lines **5260** which are extended from a scan line driver circuit **5264** are also provided. Further, a plurality of pixels are arranged in matrix at intersections of the signal lines **5269** and the scan lines **5260**. Note that each of the plurality of pixels includes a switching element. Therefore, voltage for controlling inclination of liquid crystal molecules can be separately input to each of the plurality of pixels. A structure in which a switching element is provided at each intersection in this manner is referred to as an active matrix type. Note that the invention is not limited to such an active matrix type, and a structure of a passive matrix type may be used. In a passive matrix type, a switching element is not included in each pixel, so that a process is simple.

A driver circuit portion **5268** includes a control circuit **5262**, the signal line driver circuit **5263**, and the scan line driver circuit **5264**. An image signal **5261** is input to the control circuit **5262**. The control circuit **5262** controls the signal line driver circuit **5263** and the scan line driver circuit

5264 in accordance with the image signal **5261**. Accordingly, the control circuit **5262** inputs a control signal to each of the signal line driver circuit **5263** and the scan line driver circuit **5264**. Then, in accordance with the control signal, the signal line driver circuit **5263** inputs a video signal to each of the signal lines **5269** and the scan line driver circuit **5264** inputs a scan signal to each of the scan lines **5260**. Then, the switching element included in the pixel is selected in accordance with the scan signal, and the video signal is input to a pixel electrode of the pixel.

In addition, the control circuit **5262** also controls a power supply **5267** in accordance with the image signal **5261**. The power supply **5267** includes a means to supply power to a lighting unit **5266**. As the lighting unit **5266**, an edge-light type backlight unit or a direct-type backlight unit can be used. Note that a front light may be used as the lighting unit **5266**. A front light corresponds to a plate-like lighting unit including a luminous body and a light conducting body, which is attached to the front surface side of a pixel portion and illuminates the whole area. Such a lighting unit can uniformly illuminate the pixel portion at low power consumption.

As shown in FIG. 43B, the scan line driver circuit **5264** includes a shift register **5271**, a level shifter **5272**, and a circuit functioning as a buffer **5273**. A signal such as a gate start pulse (GSP) or a gate clock signal (GCK) is input to the shift register **5271**.

As shown in FIG. 43C, the signal line driver circuit **5263** includes a shift register **5281**, a first latch **5282**, a second latch **5283**, a level shifter **5284**, and a circuit functioning as a buffer **5285**. The circuit functioning as the buffer **5285** corresponds to a circuit which has a function to amplify a weak signal and includes an operational amplifier or the like. A signal such as a start pulse (SSP) is input to the shift register **5281**, and data (DATA) such as a video signal is input to the first latch **5282**. A latch (LAT) signal can be temporally held in the second latch **5283** and is simultaneously input to the pixel portion **5265**. This is referred to as line sequential driving. Therefore, when a pixel in which not line sequential driving but dot sequential driving is performed is employed, the second latch can be omitted.

In this embodiment mode, various types of liquid crystal panels can be used. For example, a structure in which a liquid crystal layer is sealed between two substrates can be used for the liquid crystal panel. A transistor, a capacitor, a pixel electrode, an alignment film, or the like is formed over one substrate. A polarizing plate, a retardation plate, or a prism sheet may be provided on the surface opposite to a top surface of one substrate. A color filter, a black matrix, an opposite electrode, an alignment film, or the like is provided on the other substrate. A polarizing plate or a retardation plate may be provided on the surface opposite to a top surface of the other substrate. Note that the color filter and the black matrix may be formed over the top surface of one substrate. In addition, three-dimensional display can be performed by providing a slit (a grid) on the top surface or the surface opposite to the top surface of one substrate.

Each of the polarizing plate, the retardation plate, and the prism sheet can be provided between the two substrates. Alternatively, each of the polarizing plate, the retardation plate, and the prism sheet can be integrated with one of the two substrates.

Although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents)

described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

This embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

Embodiment Mode 11

In this embodiment mode, a structure and an operation of a pixel which can be applied to a liquid crystal display device are described.

In this embodiment mode, as an operation mode of a liquid crystal element, a TN (Twisted Nematic) mode, an IPS (In-Plane-Switching) mode, an FFS (Fringe Field Switching) mode, an MVA (Multi-domain Vertical Alignment) mode, a PVA (Patterned Vertical Alignment) mode, an ASM (Axially Symmetric aligned Microcell) mode, an OCB (Optical Compensated Birefringence) mode, an FLC (Ferroelectric Liquid Crystal) mode, an AFLC (AntiFerroelectric Liquid Crystal) mode, or the like can be used.

FIG. 45A shows an example of a pixel structure which can be applied to the liquid crystal display device.

A pixel **5600** includes a transistor **5601**, a liquid crystal element **5602**, and a capacitor **5603**. A gate of the transistor **5601** is connected to a wiring **5605**. A first terminal of the transistor **5601** is connected to a wiring **5604**. A second terminal of the transistor **5601** is connected to a first electrode of the liquid crystal element **5602** and a first electrode of the capacitor **5603**. A second electrode of the liquid crystal element **5602** corresponds to an opposite electrode **5607**. A second electrode of the capacitor **5603** is connected to a wiring **5606**.

The wiring **5604** functions as a signal line. The wiring **5605** functions as a scan line. The wiring **5606** functions as a capacitor line. The transistor **5601** functions as a switch. The capacitor **5603** functions as a storage capacitor.

It is only necessary that the transistor **5601** function as a switch, and the transistor **5601** may be a p-channel transistor or an n-channel transistor.

FIG. 45B shows an example of a pixel structure which can be applied to the liquid crystal display device. In particular, FIG. 45B shows an example of a pixel structure which can be applied to a liquid crystal display device suitable for a lateral electric field mode (including an IPS mode and an FFS mode).

A pixel **5610** includes a transistor **5611**, a liquid crystal element **5612**, and a capacitor **5613**. A gate of the transistor **5611** is connected to a wiring **5615**. A first terminal of the transistor **5611** is connected to a wiring **5614**. A second terminal of the transistor **5611** is connected to a first electrode of the liquid crystal element **5612** and a first electrode of the capacitor **5613**. A second electrode of the liquid crystal element **5612** is connected to a wiring **5616**. A second electrode of the capacitor **5613** is connected to the wiring **5616**.

The wiring **5614** functions as a signal line. The wiring **5615** functions as a scan line. The wiring **5616** functions as a capacitor line. The transistor **5611** functions as a switch. The capacitor **5613** functions as a storage capacitor.

It is only necessary that the transistor **5611** function as a switch, and the transistor **5611** may be a p-channel transistor or an n-channel transistor.

FIG. **46** shows an example of a pixel structure which can be applied to the liquid crystal display device. In particular, FIG. **46** shows an example of a pixel structure in which an aperture ratio of a pixel can be increased by reducing the number of wirings.

FIG. **46** shows two pixels (a pixel **5620** and a pixel **5630**) which are provided in the same column direction. For example, when the pixel **5620** is provided in the N-th row, the pixel **5630** is provided in the (N+1)th row.

A pixel **5620** includes a transistor **5621**, a liquid crystal element **5622**, and a capacitor **5623**. A gate of the transistor **5621** is connected to a wiring **5625**. A first terminal of the transistor **5621** is connected to a wiring **5624**. A second terminal of the transistor **5621** is connected to a first electrode of the liquid crystal element **5622** and a first electrode of the capacitor **5623**. A second electrode of the liquid crystal element **5622** corresponds to an opposite electrode **5627**. A second electrode of the capacitor **5623** is connected to a wiring which is the same as that connected to a gate of a transistor in the previous row.

A pixel **5630** includes a transistor **5631**, a liquid crystal element **5632**, and a capacitor **5633**. A gate of the transistor **5631** is connected to a wiring **5635**. A first terminal of the transistor **5631** is connected to the wiring **5624**. A second terminal of the transistor **5631** is connected to a first electrode of the liquid crystal element **5632** and a first electrode of the capacitor **5633**. A second electrode of the liquid crystal element **5632** corresponds to an opposite electrode **5637**. A second electrode of the capacitor **5633** is connected to a wiring which is the same as that connected to the gate of the transistor in the previous row (i.e., the wiring **5625**).

The wiring **5624** functions as a signal line. The wiring **5625** functions as a scan line of the N-th row, and also as a capacitor line of the (N+1)th row. The transistor **5621** functions as a switch. The capacitor **5623** functions as a storage capacitor.

The wiring **5635** functions as a scan line of the (N+1)th row, and also as a capacitor line of the (N+2)th row. The transistor **5631** functions as a switch. The capacitor **5633** functions as a storage capacitor.

It is only necessary that each of the transistor **5621** and the transistor **5631** function as a switch, and each of the transistor **5621** and the transistor **5631** may be a p-channel transistor or an n-channel transistor.

FIG. **47** shows an example of a pixel structure which can be applied to the liquid crystal display device. In particular, FIG. **47** shows an example of a pixel structure in which a viewing angle can be improved by using a subpixel.

A pixel **5659** includes a subpixel **5640** and a subpixel **5650**. Although the case where the pixel **5659** includes two subpixels is described below, the pixel **5659** may include three or more subpixels.

The subpixel **5640** includes a transistor **5641**, a liquid crystal element **5642**, and a capacitor **5643**. A gate of the transistor **5641** is connected to a wiring **5645**. A first terminal of the transistor **5641** is connected to a wiring **5644**. A second terminal of the transistor **5641** is connected to a first electrode of the liquid crystal element **5642** and a first electrode of the capacitor **5643**. A second electrode of the liquid crystal ele-

ment **5642** corresponds to an opposite electrode **5647**. A second electrode of the capacitor **5643** is connected to a wiring **5646**.

The subpixel **5650** includes a transistor **5651**, a liquid crystal element **5652**, and a capacitor **5653**. A gate of the transistor **5651** is connected to a wiring **5655**. A first terminal of the transistor **5651** is connected to the wiring **5644**. A second terminal of the transistor **5651** is connected to a first electrode of the liquid crystal element **5652** and a first electrode of the capacitor **5653**. A second electrode of the liquid crystal element **5652** corresponds to an opposite electrode **5657**. A second electrode of the capacitor **5653** is connected to the wiring **5646**.

The wiring **5644** functions as a signal line. The wiring **5645** functions as a scan line. The wiring **5655** functions as a scan line. The wiring **5646** functions as a capacitor line. The transistor **5641** functions as a switch. The transistor **5651** functions as a switch. The capacitor **5643** functions as a storage capacitor. The capacitor **5653** functions as a storage capacitor.

It is only necessary that the transistor **5641** function as a switch, and the transistor **5641** may be a p-channel transistor or an n-channel transistor. It is only necessary that the transistor **5651** function as a switch, and the transistor **5651** may be a p-channel transistor or an n-channel transistor.

A video signal input to the subpixel **5640** may be a value different from that of a video signal input to the subpixel **5650**. In this case, the viewing angle can be widened because alignment of liquid crystal molecules of the liquid crystal element **5642** can be different from alignment of liquid crystal molecules of the liquid crystal element **5652**.

Note that although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

Note that this embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

Embodiment Mode 12

In this embodiment mode, a method for driving a display device is described. In particular, a method for driving a liquid crystal display device is described.

A liquid crystal display panel which can be used for a liquid crystal display device described in this embodiment mode has a structure in which a liquid crystal material is interposed between two substrates. Each of the two substrates is provided with an electrode for controlling an electric field applied to the liquid crystal material. A liquid crystal material corresponds to a material optical and electrical properties of which are changed by an electric field externally applied.

61

Accordingly, a liquid crystal panel corresponds to a device in which desired optical and electrical properties can be obtained by controlling voltage applied to the liquid crystal material with use of the electrode included in each of the two substrates. In addition, a plurality of electrodes are arranged in a planar manner so that each of the electrodes corresponds to a pixel, and voltages applied to the pixels are individually controlled; therefore, a liquid crystal display panel which can display a high-definition image can be obtained.

Here, response time of the liquid crystal material due to change in an electric field depends on a space (a cell gap) between the two substrates and a type or the like of the liquid crystal material, and is generally several milliseconds to several ten milliseconds. When the amount of change in the electric field is small, the response time of the liquid crystal material is further lengthened. This characteristic causes defects in image display, such as an after image, a phenomenon in which traces can be seen, and decrease in contrast when the liquid crystal panel displays a moving image. In particular, when a half tone is changed into another half tone (when change in the electric field is small), a degree of the above-described defects become noticeable.

On the other hand, as a particular problem of a liquid crystal panel using an active matrix method, fluctuation in writing voltage due to constant charge driving is given. Constant charge driving in this embodiment mode is described below.

A pixel circuit using an active matrix method includes a switch which controls writing and a capacitor which holds a charge. A method for driving the pixel circuit using the active matrix method corresponds to a method in which predetermined voltage is written in a pixel circuit with a switch in an on state, and immediately after that, the switch is turned off and a charge in the pixel circuit is held (a hold state). At the time of the hold state, exchange of the charge between inside and outside of the pixel circuit is not performed (a constant charge). In general, a period when the switch is in an off state is approximately several hundreds (the number of scan lines) of times longer than a period when the switch is in an on state. Accordingly, it is likely that the switch of the pixel circuit is almost always in an off state. As described above, constant charge driving in this embodiment mode corresponds to a driving method in which a pixel circuit is in a hold state in almost all periods when a liquid crystal panel is driven.

Next, electrical properties of the liquid crystal material are described. A dielectric constant as well as optical properties of the liquid crystal material are changed when an electric field externally applied is changed. That is, when it is considered that each pixel of the liquid crystal panel is a capacitor (a liquid crystal element) interposed between two electrodes, the capacitor corresponds to a capacitor, capacitance of which is changed in accordance with applied voltage. This phenomenon is called dynamic capacitance.

When a capacitor, the capacitance of which is changed in accordance with applied voltage in this manner, is driven by the constant charge driving, the following problem occurs. When capacitance of a liquid crystal element is changed in a hold state in which a charge is not moved, applied voltage is also changed. This can be understood from the fact that the amount of charges is constant in a relational expression of (the amount of charges)=(capacitance) \times (applied voltage).

For the above-described reasons, voltage at the time of a hold state is changed from voltage at the time of writing because constant charge driving is performed in a liquid crystal panel using an active matrix method. Accordingly, change in transmittance of the liquid crystal element is different from change in transmittance of a liquid crystal element in a driv-

62

ing method which does not take a hold state. FIGS. 51A to 51C show this state. FIG. 51A shows an example of controlling voltage written in a pixel circuit when time is represented by a horizontal axis and an absolute value of the voltage is represented by a vertical axis. FIG. 51B shows an example of controlling voltage written in the pixel circuit when time is represented by a horizontal axis and the voltage is represented by a vertical axis. FIG. 51C shows change in transmittance of the liquid crystal element over time in the case where the voltage shown in FIG. 51A or 51B is written in the pixel circuit when time is represented by a horizontal axis and transmittance of the liquid crystal element is represented by a vertical axis. In each of FIGS. 51A to 51C, a period F indicates a period for rewriting the voltage, and time for rewriting the voltage is denoted by t_1 , t_2 , t_3 , t_4 , and the like.

Here, writing voltage corresponding to image data input to the liquid crystal display device corresponds to $|V_1|$ in rewriting at the time of 0 and corresponds to $|V_2|$ in rewriting at the time of t_1 , t_2 , t_3 , t_4 , and the like (see FIG. 51A).

Note that polarity of the writing voltage corresponding to image data input to the liquid crystal display device may be switched periodically (inversion driving; see FIG. 51B). Since direct voltage can be prevented from being applied to a liquid crystal as much as possible by using this method, burn-in or the like caused by deterioration of the liquid crystal element can be prevented. Note that a period of switching the polarity (an inversion period) may be the same as a period of rewriting voltage. In this case, generation of a flicker caused by inversion driving can be reduced because the inversion period is short. Further, the inversion period may be a period which is integral times the period of rewriting voltage. In this case, power consumption can be reduced because the inversion period is long and frequency of writing voltage can be decreased by changing the polarity.

FIG. 51C shows change in transmittance of the liquid crystal element over time when voltage as shown in FIG. 51A or 51B is applied to the liquid crystal element. Here, the voltage $|V_1|$ is applied to the liquid crystal element, and transmittance of the liquid crystal element after enough time passes corresponds to TR_1 . Similarly, the voltage $|V_2|$ is applied to the liquid crystal element, and transmittance of the liquid crystal element after enough time passes corresponds to TR_2 . When the voltage applied to the liquid crystal element is changed from $|V_1|$ to $|V_2|$ at the time of t_1 , transmittance of the liquid crystal element does not immediately become TR_2 but slowly changes as shown by a dashed line 5461. For example, when the period of rewriting voltage is the same as a frame period (16.7 milliseconds) of an image signal of 60 Hz, time for several frames is necessary until transmittance is changed to TR_2 .

Note that smooth change in transmittance over time as shown in the dashed line 5461 corresponds to change in transmittance over time when the voltage $|V_2|$ is accurately applied to the liquid crystal element. In an actual liquid crystal panel, for example, in a liquid crystal panel using an active matrix method, transmittance of the liquid crystal element does not change over time as shown by the dashed line 5461 but gradually changes over time as shown by a solid line 5462. This is because voltage at the time of a hold state is changed from voltage at the time of writing due to constant charge driving, and it is impossible to reach intended voltage only by one writing. Accordingly, the response time of transmittance of the liquid crystal element becomes further longer than original response time (the dashed line 5461) in appearance, so that defects when an image is displayed, such as an after image, a phenomenon in which traces can be seen, or decrease in contrast noticeably occur.

By using overdriving, it is possible to solve a phenomenon in which the response time in appearance becomes further longer because of shortage of writing by dynamic capacitance and constant charge driving as well as length of the original response time of the liquid crystal element. FIGS. 52A to 52C show this state. FIG. 52A shows an example of controlling voltage written in a pixel circuit when time is represented by a horizontal axis and an absolute value of the voltage is represented by a vertical axis. FIG. 52B shows an example of controlling voltage written in the pixel circuit when time is represented by a horizontal axis and the voltage is represented by a vertical axis. FIG. 52C shows change in transmittance of the liquid crystal element over time in the case where the voltage shown in FIG. 52A or 52B is written in the pixel circuit when time is represented by a horizontal axis and transmittance of the liquid crystal element is represented by a vertical axis. In each of FIGS. 52A to 52C, a period F indicates a period for rewriting the voltage, and time for rewriting the voltage is denoted by t_1 , t_2 , t_3 , t_4 , and the like.

Here, writing voltage corresponding to image data input to the liquid crystal display device corresponds to $|V_1|$ in rewriting at the time of 0, corresponds to $|V_3|$ in rewriting at the time of t_1 , and corresponds to $|V_2|$ in rewriting at the time of t_2 , t_3 , t_4 , and the like (see FIG. 52A).

Note that polarity of the writing voltage corresponding to image data input to the liquid crystal display device may be switched periodically (inversion driving: see FIG. 52B). Since direct voltage can be prevented from being applied to a liquid crystal as much as possible by using this method, burn-in or the like caused by deterioration of the liquid crystal element can be prevented. Note that a period of switching the polarity (an inversion period) may be the same as a period of rewriting voltage. In this case, generation of a flicker caused by inversion driving can be reduced because the inversion period is short. Further, the inversion period may be a period which is integral times the period of rewriting voltage. In this case, power consumption can be reduced because the inversion period is long and frequency of writing voltage can be decreased by changing the polarity.

FIG. 52C shows change in transmittance of the liquid crystal element over time when voltage as shown in FIG. 52A or 52B is applied to the liquid crystal element. Here, the voltage $|V_1|$ is applied to the liquid crystal element and transmittance of the liquid crystal element after enough time passes corresponds to TR_1 . Similarly, the voltage $|V_2|$ is applied to the liquid crystal element and transmittance of the liquid crystal element after enough time passes corresponds to TR_2 . Similarly, the voltage $|V_3|$ is applied to the liquid crystal element and transmittance of the liquid crystal element after enough time passes corresponds to TR_3 . When the voltage applied to the liquid crystal element is changed from $|V_1|$ to $|V_3|$ at the time of t_1 , transmittance of the liquid crystal element is tried to be changed to TR_3 for several frames as shown by a dashed line 5471. However, application of the voltage $|V_3|$ is terminated at the time of t_2 , and the voltage $|V_2|$ is applied after the time of t_2 . Therefore, transmittance of the liquid crystal element does not become as shown by the dashed line 5471 but becomes as shown by a solid line 5472. It is preferable that a value of the voltage $|V_3|$ be set so that transmittance is approximately TR_2 at the time of t_2 . Here, the voltage $|V_3|$ is also referred to as overdriving voltage.

That is, the response time of the liquid crystal element can be controlled to some extent by changing $|V_3|$, which is the overdriving voltage. This is because the response time of the liquid crystal element is changed by the strength of an electric field. Specifically, the response time of the liquid crystal element becomes shorter as the electric field is stronger, and

the response time of the liquid crystal element becomes longer as the electric field is weaker.

It is preferable that $|V_3|$, which is the overdriving voltage, be changed in accordance with the amount of change in the voltage, that is, the voltage $|V_1|$ and the voltage $|V_2|$ which provide intended transmittance TR_1 and TR_2 . This is because appropriate response time can be always obtained by changing $|V_3|$, which is the overdriving voltage, in accordance with change in the response time of the liquid crystal element even when the response time of the liquid crystal element is changed by the amount of change in the voltage.

It is preferable that $|V_3|$, which is the overdriving voltage, be changed depending on a mode of the liquid crystal element, such as a TN mode, a VA mode, an IPS mode, or an OCB mode. This is because appropriate response time can be always obtained by changing $|V_3|$, which is the overdriving voltage, in accordance with change in the response time of the liquid crystal element even when the response time of the liquid crystal element is changed depending on the mode of the liquid crystal element.

Note that the voltage rewriting period F may be the same as a frame period of an input signal. In this case, a liquid crystal display device with low manufacturing cost can be obtained since a peripheral driver circuit of the liquid crystal display device can be simplified.

Note that the voltage rewriting period F may be shorter than the frame period of the input signal. For example, the voltage rewriting period F may be one half the frame period of the input signal, or one third or less the frame period of the input signal. It is effective to combine this method with a measure against deterioration in quality of a moving image caused by hold driving of the liquid crystal display device, such as black data insertion driving, backlight blinking, backlight scanning, or intermediate image insertion driving by motion compensation. That is, since required response time of the liquid crystal element is short in the measure against deterioration in quality of a moving image caused by hold driving of the liquid crystal display device, the response time of the liquid crystal element can be relatively shortened easily by using the overdriving method described in this embodiment mode. Although the response time of the liquid crystal element can be shortened by a cell gap, a liquid crystal material, a mode of the liquid crystal element, or the like, it is technically difficult to shorten the response time of the liquid crystal element. Therefore, it is very important to use a method for shortening the response time of the liquid crystal element by a driving method, such as overdriving.

Note also that the voltage rewriting period F may be longer than the frame period of the input signal. For example, the voltage rewriting period F may be twice the frame period of the input signal, or three times or more the frame period of the input signal. It is effective to combine this method with a means (a circuit) which determines whether voltage is not rewritten for a long period or not. That is, when the voltage is not rewritten for a long period, an operation of the circuit can be stopped during a period where no voltage is rewritten without performing a rewriting operation of the voltage. Thus, a liquid crystal display device with low power consumption can be obtained.

Next, a specific method for changing the overdriving voltage $|V_3|$ in accordance with the voltage $|V_1|$ and the voltage $|V_2|$, which provide intended transmittance TR_1 and TR_2 , is described.

Since an overdriving circuit corresponds to a circuit for appropriately controlling the overdriving voltage $|V_3|$ in accordance with the voltage $|V_1|$ and the voltage $|V_2|$, which provide intended transmittance TR_1 and TR_2 , signals input to

the overdriving circuit are a signal related to the voltage $|V_1|$, which provides intended transmittance TR_1 , and a signal related to the voltage $|V_2|$, which provides intended transmittance TR_2 ; and a signal output from the overdriving circuit is a signal related to the overdriving voltage $|V_3|$. Here, each of these signals may have an analog voltage value such as the voltage ($|V_1|$, $|V_2|$, or $|V_3|$) applied to the liquid crystal element or may be a digital signal for supplying the voltage applied to the liquid crystal element. Here, the signal related to the overdriving circuit is described as a digital signal.

First, a general structure of the overdriving circuit is described with reference to FIG. 48A. Here, input image signals **5401a** and **5401b** are used as signals for controlling the overdriving voltage. As a result of processing these signals, an output image signal **5404** is to be output as a signal which provides the overdriving voltage.

Since the voltage $|V_3|$ and the voltage $|V_2|$ which provide intended transmittance TR_3 and TR_2 , are image signals in adjacent frames, it is preferable that the input image signals **5401a** and **5401b** be also image signals in adjacent frames. In order to obtain such signals, the input image signal **5401a** is input to a delay circuit **5402** in FIG. 48A, and a signal which is consequently output can be used as the input image signal **5401b**. An example of the delay circuit **5402** includes a memory. That is, the input image signal **5401a** is stored in the memory in order to delay the input image signal **5401a** for one frame, and at the same time, a signal stored in the previous frame is extracted from the memory as the input image signal **5401b**, and the input image signals **5401a** and **5401b** are simultaneously input to a correction circuit **5403**. Thus, the image signals in adjacent frames can be handled. By inputting the image signals in adjacent frames to the correction circuit **5403**, the output image signal **5404** can be obtained. Note that when a memory is used as the delay circuit **5402**, a memory having capacity for storing an image signal for one frame in order to delay the input image signal **5401a** for one frame (i.e., a frame memory) can be obtained. Thus, the memory can have a function as a delay circuit without causing excess and deficiency of memory capacity.

Next, the delay circuit **5402** formed mainly for reducing memory capacity is described. Since memory capacity can be reduced by using such a circuit as the delay circuit **5402**, manufacturing cost can be reduced.

Specifically, a delay circuit as shown in FIG. 48B can be used as the delay circuit **5402** having such characteristics. The delay circuit shown in FIG. 48B includes an encoder **5405**, a memory **5406**, and a decoder **5407**.

Operations of the delay circuit **5402** shown in FIG. 48B are as follows. First, compression processing is performed by the encoder **5405** before the input image signal **5401a** is stored in the memory **5406**. Thus, the size of data to be stored in the memory **5406** can be reduced. Accordingly, memory capacity can be reduced, and manufacturing cost can be reduced. Then, a compressed image signal is transferred to the decoder **5407** and extension processing is performed here. Thus, the signal which has been compressed by the encoder **5405** can be restored. Here, compression and extension processing which is performed by the encoder **5405** and the decoder **5407** may be reversible processing. Accordingly, since the image signal does not deteriorate even after compression and extension processing is performed, memory capacity can be reduced without causing deterioration of quality of an image, which is finally displayed on a device. Alternatively, compression and extension processing which is performed by the encoder **5405** and the decoder **5407** may be non-reversible processing.

Accordingly, since the size of data of the compressed image signal can be made extremely small, memory capacity can be significantly reduced.

As a method for reducing memory capacity, various methods can be used as well as the above-described method. For example, a method in which color information included in an image signal is reduced (e.g., tone reduction from 260 thousand colors to 65 thousand colors is performed) or the amount of data is reduced (resolution is reduced) without performing image compression by an encoder can be used.

Next, specific examples of the correction circuit **5403** are described with reference to FIGS. 48C to 44E. The correction circuit **5403** corresponds to a circuit for outputting an output image signal of a certain value from two input image signals. Here, when a relation between the two input image signals and the output image signal is non-linear and it is difficult to calculate the relation by simple operation, a look up table (LUT) may be used as the correction circuit **5403**. Since the relation between the two input image signals and the output image signal is calculated in advance by measurement in a LUT, the output image signal corresponding to the two input image signals can be calculated only by seeing the LUT (see FIG. 48C). By using a LUT **5408** as the correction circuit **5403**, the correction circuit **5403** can be realized without complicated circuit design or the like.

Since the LUT is one of memories, it is preferable to reduce memory capacity as much as possible in order to reduce manufacturing cost. As an example of the correction circuit **5403** for realizing reduction in memory capacity, a circuit shown in FIG. 48D can be considered. The correction circuit **5403** shown in FIG. 48D includes a LUT **5409** and an adder **5410**. Difference data between the input image signal **5401a** and the output image signal **5404** to be output is stored in the LUT **5409**. That is, corresponding difference data from the input image signal **5401a** and the input image signal **5401b** is extracted from the LUT **5409**, and the extracted difference data and the input image signal **5401a** are added by the adder **5410**, so that the output image signal **5404** can be obtained. Note that when data stored in the LUT **5409** is difference data, memory capacity of the LUT can be reduced. This is because the size of difference data is smaller than that of the output image signal **5404** as it is, so that memory capacity necessary for the LUT **5409** can be reduced.

In addition, when the output image signal can be calculated by simple operation such as four arithmetic operations of the two input image signals, the correction circuit **5403** can be realized by combination of simple circuits such as an adder, a subtractor, and a multiplier. Accordingly, it is not necessary to use the LUT, and manufacturing cost can be significantly reduced. As such a circuit, a circuit shown in FIG. 48E can be considered. The correction circuit **5403** shown in FIG. 48E includes a subtractor **5411**, a multiplier **5412**, and an adder **5413**. First, difference between the input image signal **5401a** and the input image signal **5401b** is calculated by the subtractor **5411**. After that, a differential value is multiplied by an appropriate coefficient by using the multiplier **5412**. Then, the differential value multiplied by the appropriate coefficient is added to the input image signal **5401a** by the adder **5413**; thus, the output image signal **5404** can be obtained. By using such a circuit, it is not necessary to use the LUT. Therefore, manufacturing cost can be significantly reduced.

By using the correction circuit **5403** shown in FIG. 48E under a certain condition, inappropriate output of the output image signal **5404** can be prevented. The condition is that the output image signal **5404** applying the overdriving voltage and a differential value between the input image signals **5401a** and **5401b** have linearity. The slope of this linearity is

a coefficient to be multiplied by the multiplier **5412**. That is, it is preferable that the correction circuit **5403** in FIG. **48E** be used for a liquid crystal element having such properties. As a liquid crystal element having such properties, an IPS mode liquid crystal element in which response time has little gray-scale dependency is considered. For example, when the correction circuit **5403** shown in FIG. **48E** is used for an IPS mode liquid crystal element in this manner, manufacturing cost can be significantly reduced and an overdriving circuit which can prevent output of the inappropriate output image signal **5404** can be obtained.

Note that operations which are similar to those of the circuit shown in FIGS. **48A** to **48E** may be realized by software processing. As the memory used for the delay circuit, another memory included in the liquid crystal display device, a memory included in a device which transfers an image displayed on the liquid crystal display device (e.g., a video card or the like included in a personal computer or a device similar to the personal computer), or the like can be used. Accordingly, not only can manufacturing cost be reduced, intensity of overdriving, availability, or the like can be selected in accordance with user's preference.

Next, driving which controls a potential of a common line is described with reference to FIGS. **49A** and **49B**. FIG. **49A** shows a plurality of pixel circuits in which one common line is provided with respect to one scan line in a display device using a display element which has capacitive properties, such as a liquid crystal element. Each of the pixel circuits shown in FIG. **49A** includes a transistor **5421**, an auxiliary capacitor **5422**, a display element **5423**, a video signal line **5424**, a scan line **5425**, and a common line **5426**.

A gate electrode of the transistor **5421** is electrically connected to the scan line **5425**. One of a source electrode and a drain electrode of the transistor **5421** is electrically connected to the video signal line **5424**. The other of the source electrode and the drain electrode of the transistor **5421** is electrically connected to one electrode of the auxiliary capacitor **5422** and one electrode of the display element **5423**. The other electrode of the auxiliary capacitor **5422** is electrically connected to the common line **5426**.

First, in each pixel selected by the scan line **5425**, voltage corresponding to a video signal is applied to the display element **5423** and the auxiliary capacitor **5422** through the video signal line **5424** since the transistor **5421** is turned on. At this time, when the video signal is a signal which makes all of pixels connected to the common line **5426** display a minimum gray scale or a maximum gray scale, it is not necessary that the video signal be written in each of the pixels through the video signal line **5424**. Voltage applied to the display element **5423** can be changed by changing a potential of the common line **5426** instead of writing the video signal through the video signal line **5424**.

Next, FIG. **49B** shows a plurality of pixel circuits in which two common lines are provided with respect to one scan line in a display device using a display element which has capacitive properties, such as a liquid crystal element. Each of the pixel circuits shown in FIG. **49B** includes a transistor **5431**, an auxiliary capacitor **5432**, a display element **5433**, a video signal line **5434**, a scan line **5435**, a first common line **5436**, and a second common line **5437**.

A gate electrode of the transistor **5431** is electrically connected to the scan line **5435**. One of a source electrode and a drain electrode of the transistor **5431** is electrically connected to the video signal line **5434**. The other of the source electrode and the drain electrode of the transistor **5431** is electrically connected to one electrode of the auxiliary capacitor **5432** and one electrode of the display element **5433**. The other

electrode of the auxiliary capacitor **5432** is electrically connected to the first common line **5436**. Further, in a pixel which is adjacent to the pixel, the other electrode of the auxiliary capacitor **5432** is electrically connected to the second common line **5437**.

In the pixel circuits shown in FIG. **49B**, the number of pixels which are electrically connected to one common line is small. Accordingly, by changing a potential of the first common line **5436** or the second common line **5437** instead of writing a video signal through the video signal line **5434**, frequency of changing voltage applied to the display element **5433** is significantly increased. In addition, source inversion driving or dot inversion driving can be performed. By performing source inversion driving or dot inversion driving, reliability of the element can be improved and a flicker can be suppressed.

Next, a scanning backlight is described with reference to FIGS. **50A** to **50C**. FIG. **50A** shows a scanning backlight in which cold cathode fluorescent lamps are arranged. The scanning backlight shown in FIG. **50A** includes a diffusion plate **5441** and N pieces of cold cathode fluorescent lamps **5442-1** to **5442-N**. The N pieces of the cold cathode fluorescent lamps **5442-1** to **5442-N** are arranged on the back side of the diffusion plate **5441**, so that the N pieces of the cold cathode fluorescent lamps **5442-1** to **5442-N** can be scanned while luminance thereof is changed.

Change in luminance of each cold cathode fluorescent lamp in scanning is described with reference to FIG. **50C**. First, luminance of the cold cathode fluorescent lamp **5442-1** is changed for a certain period. After that, luminance of the cold cathode fluorescent lamp **5442-2** which is provided adjacent to the cold cathode fluorescent lamp **5442-1** is changed for the same period. In this manner, luminance is changed sequentially from the cold cathode fluorescent lamps **5442-1** to **5442-N**. Note that although luminance which is changed for a certain period is set to be lower than original luminance in FIG. **50C**, it may be higher than original luminance. In addition, although scanning is performed from the cold cathode fluorescent lamps **5442-1** to **5442-N**, scanning may be performed from the cold cathode fluorescent lamps **5442-N** to **5442-1**, which is in a reversed order.

By performing driving as in FIG. **50C**, average luminance of the backlight can be decreased. Therefore, power consumption of the backlight, which mainly takes up power consumption of the liquid crystal display device, can be reduced.

Note that an LED may be used as a light source of the scanning backlight. FIG. **50B** shows the scanning backlight in that case. The scanning backlight in FIG. **50B** includes a diffusion plate **5451** and light sources **5452-1** to **5452-N**, in each of which LEDs are arranged. When the LED is used as the light source of the scanning backlight, it is advantageous in that the backlight can be thin and lightweight and that a color reproduction area can be widened. Further, since the LEDs which are arranged in each of the light sources **5452-1** to **5452-N** can be similarly scanned, a dot scanning backlight can also be obtained. By using the dot scanning backlight, image quality of a moving image can be further improved.

When the LED is used as the light source of the backlight, driving can be performed by changing luminance as shown in FIG. **50C** as well.

Although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents)

described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

This embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

Embodiment Mode 13

In this embodiment mode, an example of a display device is described. In particular, the case where a display device is optically treated is described.

A rear projection display device **7400** in FIGS. **53A** and **53B** is provided with a projector unit **7406**, a mirror **7407**, and a screen **7401**. The rear projection display device **7400** may also be provided with a speaker **7402** and operation switches **7404**. The projector unit **7406** is provided at a lower portion of a housing **7405** of the rear projection display device **7400**, and projects incident light for projecting an image based on a video signal to the mirror **7407**. The rear projection display device **7400** displays an image projected from a rear surface of the screen **7401**.

FIG. **54** shows a front projection display device **7410**. The front projection display device **7410** is provided with the projector unit **7406** and a projection optical system **7411**. The projection optical system **7411** projects an image to a screen or the like provided at the front.

Hereinafter, a structure of the projector unit **7406** which is applied to the rear projection display device **7400** in FIGS. **53A** and **53B** and the front projection display device **7410** in FIG. **54** is described.

FIG. **55** shows a structure example of the projector unit **7406**. The projector unit **7406** is provided with a light source unit **7421** and a modulation unit **7424**. The light source unit **7421** is provided with a light source optical system **7423** including lenses and a light source lamp **7422**. The light source lamp **7422** is stored in a housing so that stray light is not scattered. As the light source lamp **7422**, a high-pressure mercury lamp or a xenon lamp, for example, which can emit a large amount of light is used. The light source optical system **7423** is provided with an optical lens, a film having a function to polarize light, a film for adjusting phase difference, an IR film, or the like as appropriate. The light source unit **7421** is provided so that incident light is incident on the modulation unit **7424**. The modulation unit **7424** is provided with a plurality of display panels **7428**, a color filter, a retardation plate **7427**, a dichroic mirror **7425**, a total reflection mirror **7426**, a prism **7429**, and a projection optical system **7430**. Light emitted from the light source unit **7421** is split into a plurality of optical paths by the dichroic mirror **7425**.

Each optical path is provided with the display panel **7428** and a color filter which transmits light with a predetermined wavelength or wavelength range. The transmissive display panel **7428** modulates transmitted light based on a video signal. Light of each color transmitted through the display panel **7428** is incident on the prism **7429**, and an image is

displayed on the screen through the projection optical system **7430**. Note that a Fresnel lens may be provided between the mirror and the screen. Projected light which is projected by the projector unit **7406** and reflected by the mirror is converted into generally parallel light by the Fresnel lens to be projected on the screen. Displacement between a chief ray and an optical axis of the parallel light is preferably $\pm 10^\circ$ or less, and more preferably, $\pm 5^\circ$ or less.

The projector unit **7406** shown in FIG. **56** is provided with reflective display panels **7447**, **7448**, and **7449**.

The projector unit **7406** in FIG. **56** is provided with the light source unit **7421** and a modulation unit **7440**. The light source unit **7421** may have a structure similar to FIG. **55**. Light from the light source unit **7421** is split into a plurality of optical paths by dichroic mirrors **7441** and **7442** and a total reflection mirror **7443** to be incident on polarization beam splitters **7444**, **7445**, and **7446**. The polarization beam splitters **7444**, **7445**, and **7446** are provided corresponding to the reflective display panels **7447**, **7448**, and **7449** which correspond to respective colors. The reflective display panels **7447**, **7448**, and **7449** modulate reflected light based on a video signal. Light of each color, which are reflected by the reflective display panels **7447**, **7448**, and **7449**, is incident on the prism **7450** to be composed, and projected through a projection optical system **7451**.

Among light emitted from the light source unit **7421**, only light in a wavelength region of red is transmitted through the dichroic mirror **7441** and light in wavelength regions of green and blue is reflected by the dichroic mirror **7441**. Further, only the light in the wavelength region of green is reflected by the dichroic mirror **7442**. The light in the wavelength region of red, which is transmitted through the dichroic mirror **7441**, is reflected by the total reflection mirror **7443** and incident on the polarization beam splitter **7444**. The light in the wavelength region of blue is incident on the polarization beam splitter **7445**. The light in the wavelength region of green is incident on the polarization beam splitter **7446**. The polarization beam splitters **7444**, **7445**, and **7446** have a function to split incident light into P-polarized light and S-polarized light and a function to transmit only P-polarized light. The reflective display panels **7447**, **7448**, and **7449** polarize incident light based on a video signal.

Only the S-polarized light corresponding to each color is incident on the reflective display panels **7447**, **7448**, and **7449** corresponding to each color. Note that the reflective display panels **7447**, **7448**, and **7449** may be liquid crystal panels. In this case, the liquid crystal panel operates in an electrically controlled birefringence (ECB) mode. Liquid crystal molecules are vertically aligned at an angle to a substrate. Accordingly, in the reflective display panels **7447**, **7448**, and **7449**, when a pixel is turned off, display molecules are aligned not to change a polarization state of incident light so as to reflect the incident light. When the pixel is turned on, alignment of the display molecules is changed, and the polarization state of the incident light is changed.

The projector unit **7406** in FIG. **56** can be applied to the rear projection display device **7400** in FIGS. **53A** and **53B** and the front projection display device **7410** in FIG. **54**.

FIGS. **57A** to **57C** each show a single-panel type projector unit. The projector unit **7406** shown in FIG. **57A** is provided with the light source unit **7421**, a display panel **7467**, a projection optical system **7471**, and a retardation plate **7464**. The projection optical system **7471** includes one or a plurality of lenses. The display panel **7467** may be provided with a color filter.

FIG. **57B** shows a structure of the projector unit **7406** operating in a field sequential mode. A field sequential mode

corresponds to a mode in which color display is performed by light of respective colors such as red, green, and blue sequentially incident on a display panel with a time lag, without a color filter. A high-definition image can be displayed particularly by combination with a display panel with high-speed response to change in input signal. The projector unit **7406** in FIG. **57B** is provided with a rotating color filter plate **7465** including a plurality of color filters with red, green, blue, or the like between the light source unit **7421** and a display panel **7468**.

FIG. **57C** shows a structure of the projector unit **7406** with a color separation method using a micro lens, as a color display method. This method corresponds to a method in which color display is realized by providing a micro lens array **7466** on the side of a display panel **7469**, on which light is incident, and light of each color is emitted from each direction. The projector unit **7406** employing this method has little loss of light due to a color filter, so that light from the light source unit **7421** can be efficiently utilized. The projector unit **7406** in FIG. **57C** is provided with dichroic mirrors **7461**, **7462**, and **7463** so that light of each color is emitted to the display panel **7469** from each direction.

Although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

This embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

Embodiment Mode 14

In this embodiment mode, examples of electronic devices are described.

FIG. **58** shows a display panel module combining a display panel **9601** and a circuit board **9605**. The display panel **9601** includes a pixel portion **9602**, a scan line driver circuit **9603**, and a signal line driver circuit **9604**. The circuit board **9605** is provided with a control circuit **9606**, a signal dividing circuit **9607**, and the like, for example. The display panel **9601** and the circuit board **9605** are connected to each other by a connection wiring **9608**. An FPC or the like can be used as the connection wiring.

FIG. **59** is a block diagram showing a main structure of a television receiver. A tuner **9611** receives a video signal and an audio signal. The video signals are processed by an video signal amplifier circuit **9612**; a video signal processing circuit **9613** which converts a signal output from the video signal amplifier circuit **9612** into a color signal corresponding to each color of red, green, and blue; and a control circuit **9622** which converts the video signal into the input specification of a driver circuit. The control circuit **9622** outputs a signal to each of a scan line driver circuit **9624** and a signal line driver

circuit **9614**. The scan line driver circuit **9624** and the signal line driver circuit **9614** drive a display panel **9621**. When performing digital drive, a structure may be employed in which a signal dividing circuit **9623** is provided on the signal line side so that an input digital signal is divided into m signals (m is a positive integer) to be supplied.

Among the signals received by the tuner **9611**, an audio signal is transmitted to an audio signal amplifier circuit **9615**, and an output thereof is supplied to a speaker **9617** through an audio signal processing circuit **9616**. A control circuit **9618** receives control information on receiving station (receiving frequency) and volume from an input portion **9619** and transmits signals to the tuner **9611** or the audio signal processing circuit **9616**.

FIG. **60A** shows a television receiver incorporated with a display panel module, which is different from FIG. **59**. In FIG. **60A**, a display screen **9632** incorporated in a housing **9631** is formed using the display panel module. Note that speakers **9633**, input means (an operation key **9634**, a connection terminal **9635**, a sensor **9636** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9637**), and the like may be provided as appropriate.

FIG. **60B** shows a television receiver in which only a display can be carried wirelessly. The television receiver is provided with a display portion **9643**, a speaker portion **9647**, input means (an operation key **9646**, a connection terminal **9648**, a sensor **9649** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9641**), and the like as appropriate. A battery and a signal receiver are incorporated in a housing **9642**. The battery drives the display portion **9643**, the speaker portion **9647**, the sensor **9649**, and the microphone **9641**. The battery can be repeatedly charged by a charger **9640**. The charger **9640** can transmit and receive a video signal and transmit the video signal to the signal receiver of the display. The device in FIG. **60B** is controlled by the operation key **9646**. Alternatively, the device in FIG. **60B** can transmit a signal to the charger **9640** by operating the operation key **9646**. That is, the device may be an image and audio interactive communication device. Further alternatively, by operating the operation key **9646**, the device in FIG. **60B** may transmit a signal to the charger **9640** and another electronic device is made to receive a signal which can be transmitted from the charger **9640**; thus, the device in FIG. **60B** can control communication of another electronic device. That is, the device may be a general-purpose remote control device. Note that the contents (or part thereof) described in each drawing of this embodiment mode can be applied to the display portion **9643**.

Next, a structure example of a mobile phone is described with reference to FIG. **61**.

A display panel **9662** is detachably incorporated in a housing **9650**. The shape and size of the housing **9650** can be changed as appropriate in accordance with the size of the display panel **9662**. The housing **9650** which fixes the display panel **9662** is fitted in a printed wiring board **9651** to be assembled as a module.

The display panel **9662** is connected to the printed wiring board **9651** through an FPC **9663**. The printed wiring board **9651** is provided with a speaker **9652**, a microphone **9653**, a transmitting/receiving circuit **9654**, a signal processing circuit **9655** including a CPU, a controller, and the like, and a sensor **9661** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray). Such a module, an operation key **9656**, a battery **9657**, and an antenna **9660** are combined and stored in a housing **9659**. A pixel portion of the display panel **9662** is provided to be seen from an opening window formed in the housing **9659**.

In the display panel **9662**, the pixel portion and part of peripheral driver circuits (a driver circuit having a low operation frequency among a plurality of driver circuits) may be formed over the same substrate by using transistors, and another part of the peripheral driver circuits (a driver circuit having a high operation frequency among the plurality of driver circuits) may be formed over an IC chip. Then, the IC chip may be mounted on the display panel **9662** by COG (Chip On Glass). Alternatively, the IC chip may be connected to a glass substrate by using TAB (Tape Automated Bonding) or a printed wiring board. With such a structure, power consumption of a display device can be reduced and operation time of the mobile phone per charge can be extended. Further, reduction in cost of the mobile phone can be realized.

The mobile phone in FIG. **61** has various functions such as, but not limited to, a function to display various kinds of information (e.g., a still image, a moving image, and a text image); a function to display a calendar, a date, the time, and the like on a display portion; a function to operate or edit the information displaying on the display portion; a function to control processing by various kinds of software (programs); a function of wireless communication; a function to communicate with another mobile phone, a fixed phone, or an audio communication device by using the wireless communication function; a function to connect with various computer networks by using the wireless communication function; a function to transmit or receive various kinds of data by using the wireless communication function; a function to operate a vibrator in accordance with incoming call, reception of data, or an alarm; and a function to generate a sound in accordance with incoming call, reception of data, or an alarm.

FIG. **62A** shows a display, which includes a housing **9671**, a support base **9672**, a display portion **9673**, a speaker **9677**, an LED lamp **9679**, input means (a connection terminal **9674**, a sensor **9675** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), a microphone **9676**, and an operation key **9678**), and the like. The display in FIG. **62A** can have various functions such as, but not limited to, a function to display various kinds of information (e.g., a still image, a moving image, and a text image) on the display portion.

FIG. **62B** shows a camera, which includes a main body **9691**, a display portion **9692**, a shutter button **9696**, a speaker **9700**, an LED lamp **9701**, input means (an image receiving portion **9693**, operation keys **9694**, an external connection port **9695**, a connection terminal **9697**, a sensor **9698** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a

tance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9699**), and the like. The camera in FIG. **62B** can have various functions such as, but not limited to, a function to photograph a still image and a moving image; a function to automatically adjust the photographed image (the still image or the moving image); a function to store the photographed image in a recording medium (provided externally or incorporated in the camera); and a function to display the photographed image on the display portion.

FIG. **62C** shows a computer, which includes a main body **9711**, a housing **9712**, a display portion **9713**, a speaker **9720**, an LED lamp **9721**, a reader/writer **9722**, input means (a keyboard **9714**, an external connection port **9715**, a pointing device **9716**, a connection terminal **9717**, a sensor **9718** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9719**), and the like. The computer in FIG. **62C** can have various functions such as, but not limited to, a function to display various kinds of information (e.g., a still image, a moving image, and a text image) on the display portion; a function to control processing by various kinds of software (programs); a communication function such as wireless communication or wire communication; a function to connect with various computer networks by using the communication function; and a function to transmit or receive various kinds of data by using the communication function.

FIG. **69A** shows a mobile computer, which includes a main body **9791**, a display portion **9792**, a switch **9793**, a speaker **9799**, an LED lamp **9800**, input means (operation keys **9794**, an infrared port **9795**, a connection terminal **9796**, a sensor **9797** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9798**), and the like. The mobile computer in FIG. **69A** can have various functions such as, but not limited to, a function to display various kinds of information (e.g., a still image, a moving image, and a text image) on the display portion; a touch panel function provided on the display portion; a function to display a calendar, a date, the time, and the like on the display portion; a function to control processing by various kinds of software (programs); a function of wireless communication; a function to connect with various computer networks by using the wireless communication function; and a function to transmit or receive various kinds of data by using the wireless communication function.

FIG. **69B** shows a portable image reproducing device having a recording medium (e.g., a DVD reproducing device), which includes a main body **9811**, a housing **9812**, a display portion A **9813**, a display portion B **9814**, a speaker portion **9817**, an LED lamp **9821**, input means (a recording medium reading portion **9815** (a recording medium thereof is a DVD or the like), operation keys **9816**, a connection terminal **9818**, a sensor **9819** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a

flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9820**), and the like. The display portion **A 9813** can mainly display image information, and the display portion **B 9814** can mainly display text information.

FIG. **69C** shows a goggle-type display, which includes a main body **9831**, a display portion **9832**, an earphone **9833**, a support portion **9834**, an LED lamp **9839**, a speaker **9838**, input means (a connection terminal **9835**, a sensor **9836** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9837**), and the like. The goggle-type display in FIG. **69C** can have various functions such as, but not limited to, a function to display an externally obtained image (e.g., a still image, a moving image, and a text image) on the display portion.

FIG. **70A** shows a portable game machine, which includes a housing **9851**, a display portion **9852**, a speaker portion **9853**, a recording medium insert portion **9855**, an LED lamp **9859**, input means (an operation key **9854**, a connection terminal **9856**, a sensor **9857** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9858**), and the like. The portable game machine in FIG. **70A** can have various functions such as, but not limited to, a function to read a program or data stored in the recording medium to display on the display portion; and a function to share information by wireless communication with another portable game machine.

FIG. **70B** shows a digital camera having a television reception function, which includes a housing **9861**, a display portion **9862**, a speaker **9864**, a shutter button **9865**, an LED lamp **9871**, input means (an operation key **9863**, an image receiving portion **9866**, an antenna **9867**, a connection terminal **9868**, a sensor **9869** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9870**), and the like. The digital camera having a television reception function in FIG. **70B** can have various functions such as, but not limited to, a function to photograph a still image and a moving image; a function to automatically adjust the photographed image; a function to obtain various kinds of information from the antenna; a function to store the photographed image or the information obtained from the antenna; and a function to display the photographed image or the information obtained from the antenna on the display portion.

FIG. **71** shows a portable game machine, which includes a housing **9881**, a first display portion **9882**, a second display portion **9883**, a speaker portion **9884**, a recording medium insert portion **9886**, an LED lamp **9890**, input means (an operation key **9885**, a connection terminal **9887**, a sensor **9888** (having a function to measure power, displacement, position, speed, acceleration, angular velocity, the number of rotations, distance, light, liquid, magnetism, temperature, a chemical substance, sound, time, hardness, an electric field, current, voltage, electric power, radiation, a flow rate, humidity, gradient, oscillation, smell, or infrared ray), and a microphone **9889**), and the like. The portable game machine in FIG.

71 can have various functions such as, but not limited to, a function to read a program or data stored in the recording medium to display on the display portion; and a function to share information by wireless communication with another portable game machine.

As shown in FIGS. **62A** to **62C**, **69A** to **69C**, **70A**, **70B**, and **71**, each electronic device includes a display portion for displaying some kind of information.

Next, application examples of a semiconductor device are described.

FIG. **63** shows an example where a semiconductor device is incorporated in a constructed object. FIG. **63** shows a housing **9730**, a display portion **9731**, a remote control device **9732** which is an operation portion, a speaker portion **9733**, and the like. The semiconductor device is incorporated in the constructed object as a wall-hanging type and can be provided without requiring a large space.

FIG. **64** shows another example where a semiconductor device is incorporated in a constructed object. A display panel **9741** is incorporated with a prefabricated bath **9742**, and a person who takes a bath can view the display panel **9741**. The display panel **9741** has a function to display information by an operation by a person who takes a bath; and a function to be used as an advertisement or an entertainment means.

Note that the semiconductor device can be provided not only to a side wall of the prefabricated bath **9742** as shown in FIG. **64**, but also to various places. For example, the semiconductor device can be incorporated with part of a mirror, a bathtub itself, or the like. At this time, a shape of the display panel **9741** may be changed in accordance with a shape of the mirror or the bathtub.

FIG. **65** shows another example where a semiconductor device is incorporated in a constructed object. A display panel **9752** is bent and attached to a curved surface of a column-shaped object **9751**. Here, a utility pole is described as the column-shaped object **9751**.

The display panel **9752** in FIG. **65** is provided at a position higher than a human viewpoint. When the same images are displayed on the display panels **9752** provided in constructed objects which stand together in large numbers outdoors, such as utility poles, advertisement can be performed to a plurality of unspecified viewers. Since it is easy for the display panel **9752** to display the same images and instantly switch images by external control, highly efficient information display and advertisement effect can be obtained. When provided with self-luminous display elements, the display panel **9752** can be effectively used as a highly visible display medium even at night. When the display panel **9752** is provided in the utility pole, a power supply means for the display panel **9752** can be easily obtained. In an emergency such as disaster, the display panel **9752** can also be used as a means to transmit correct information to victims rapidly.

An example of the display panel **9752** includes a display panel in which a switching element such as an organic transistor is provided over a film-shaped substrate and a display element is driven so as to display an image.

Note that in this embodiment mode, a wall, a column-shaped object, and a prefabricated bath are shown as examples of a constructed object; however, this embodiment mode is not limited thereto, and various constructed objects can be provided with a semiconductor device.

Next, examples where a semiconductor device is incorporated with a moving object are described.

FIG. **66** shows an example where a semiconductor device is incorporated with a car. A display panel **9761** is incorporated with a car body **9762**, and can display an operation of the

car body or information input from inside or outside the car body on demand. Note that a navigation function may be provided.

The semiconductor device can be provided not only to the car body **9762** as shown in FIG. **66**, but also to various places. For example, the semiconductor device can be incorporated with a glass window, a door, a steering wheel, a gear shift, a seat, a rear-view mirror, and the like. At this time, a shape of the display panel **9761** may be changed in accordance with a shape of an object provided with the semiconductor device.

FIGS. **67A** and **67B** show examples where a semiconductor device is incorporated with a train car.

FIG. **67A** shows an example where a display panel **9772** is provided in glass of a door **9771** in a train car, which has an advantage compared with a conventional advertisement using paper in that labor cost for changing an advertisement is not necessary. Since the display panel **9772** can instantly switch images displaying on a display portion by an external signal, images on the display panel can be switched in every time period when types of passengers on the train are changed, for example; thus, more effective advertisement effect can be obtained.

FIG. **67B** shows an example where the display panels **9772** are provided to a glass window **9773** and a ceiling **9774** as well as the glass of the door **9771** in the train car. In this manner, the semiconductor device can be easily provided to a place where a semiconductor device has been difficult to be provided conventionally; thus, effective advertisement effect can be obtained. Further, the semiconductor device can instantly switch images displayed on a display portion by an external signal; thus, cost and time for changing an advertisement can be reduced, and more flexible advertisement management and information transmission can be realized.

The semiconductor device can be provided not only to the door **9771**, the glass window **9773**, and the ceiling **9774** as shown in FIG. **67**, but also to various places. For example, the semiconductor device can be incorporated with a strap, a seat, a handrail, a floor, and the like. At this time, a shape of the display panel **9772** may be changed in accordance with a shape of an object provided with the semiconductor device.

FIGS. **68A** and **68B** show an example where a semiconductor device is incorporated with a passenger airplane.

FIG. **68A** shows a shape of a display panel **9782** attached to a ceiling **9781** above a seat of the passenger airplane when the display panel **9782** is used. The display panel **9782** is incorporated with the ceiling **9781** using a hinge portion **9783**, and a passenger can view the display panel **9782** by stretching of the hinge portion **9783**. The display panel **9782** has a function to display information by an operation by the passenger and a function to be used as an advertisement or an entertainment means. As shown in FIG. **68B**, the hinge portion is bent and the display panel is stored in the ceiling **9781** of the airplane, so that safety in taking-off and landing can be assured. Note that a display element in the display panel is lit in an emergency, so that the display panel can also be used as an information transmission means and an evacuation light.

The semiconductor device can be provided not only to the ceiling **9781** as shown in FIGS. **68A** and **68B**, but also to various places. For example, the semiconductor device can be incorporated with a seat, a table attached to a seat, an armrest, a window, and the like. A large display panel which a plurality of people can view may be provided at a wall of an airframe. At this time, a shape of the display panel **9782** may be changed in accordance with a shape of an object provided with the semiconductor device.

Note that in this embodiment mode, bodies of a train car, a car, and an airplane are shown as a moving object; however,

the invention is not limited thereto, and a semiconductor device can be provided to various objects such as a motorcycle, an four-wheel drive car (including a car, a bus, and the like), a train (including a monorail, a railroad car, and the like), and a vessel. Since the semiconductor device can instantly switch images displayed on a display panel in a moving object by an external signal, the moving object provided with the semiconductor device can be used as an advertisement display board for a plurality of unspecified customers, an information display board in disaster, and the like.

Although this embodiment mode is described with reference to various drawings, the contents (or part of the contents) described in each drawing can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in another drawing. Further, much more drawings can be formed by combining each part with another part in the above-described drawings.

Similarly, the contents (or part of the contents) described in each drawing in this embodiment mode can be freely applied to, combined with, or replaced with the contents (or part of the contents) described in a drawing in another embodiment mode. Further, much more drawings can be formed by combining each part in each drawing in this embodiment mode with part of another embodiment mode.

This embodiment mode shows examples of embodying, slightly transforming, partially modifying, improving, describing in detailed, or applying the contents (or part of the contents) described in other embodiment modes, an example of related part thereof, or the like. Therefore, the contents described in other embodiment modes can be freely applied to, combined with, or replaced with this embodiment mode.

Embodiment 1

In this embodiment, an example where a liquid crystal display device is actually manufactured using the structure in Embodiment Mode 1 is described with reference to FIGS. **14A**, **14B**, **15A** to **15D**, **16A** to **16C**, **17A** to **17C**, and **18**. Note that this embodiment can be completed by using, as a basic structure, each part of the structures in Embodiment Modes 2 to 6 as well as the structure in Embodiment Mode 1.

It is needless to say that a bottom-gate TFT described in Embodiment Mode 2, a structure described in Embodiment Mode 3, in which a pixel electrode is directly connected to an island-shaped semiconductor film, a connection structure of electrodes described in Embodiment Mode 4, a shape of a pixel electrode described in Embodiment Mode 5, a color filter described in Embodiment Mode 6, or the like can be combined with this embodiment when needed.

FIG. **14A** is a top plan view of a liquid crystal display device in this embodiment, and FIG. **14B** is a cross-sectional view thereof. This embodiment is an example of a manufacturing method of a liquid crystal display device which has the structure shown in Embodiment Mode 1. Accordingly, the degree of freedom of a space between a common electrode (corresponding to the conductive film **115** in FIG. **1**) and a pixel electrode (corresponding to the pixel electrodes **113** and **114** in FIG. **1**) is increased. Since optimal values for an arrangement interval and the width of an opening of a pixel electrode are changed depending on a distance between the pixel electrode and the common electrode, the size, the width, and the interval of the opening can be freely set. Further, a gradient of an electric field applied between the electrodes can be controlled, and an electric field parallel to a substrate can be easily increased, for example. That is, in a display device using a liquid crystal, since liquid crystal molecules aligned in parallel to a substrate (so-called homogeneous

alignment) can be controlled in a direction parallel to the substrate, a viewing angle is widened by applying an optimal electric field.

First, as shown in FIG. 15A, a conductive film **801** having a light-transmitting property is formed over a substrate **800**. The substrate **800** is a glass substrate, a quartz substrate, a substrate formed of an insulator such as alumina, a plastic substrate with heat resistance high enough to withstand a processing temperature of subsequent steps, a silicon substrate, or a metal plate. Alternatively, the substrate **800** may be a substrate in which an insulating film such as a silicon oxide film or a silicon nitride film is formed on a surface of metal such as stainless steel, a semiconductor substrate, or the like. Note that when a plastic substrate is used as the substrate **800**, it is preferable to use a plastic substrate having a relatively high glass transition point, such as PC (polycarbonate), PES (polyethersulfone), PET (polyethylene terephthalate), or PEN (polyethylene naphthalate).

The conductive film **801** is, for example, an indium tin oxide (ITO) film, an indium tin oxide film containing a Si element, or an film using a material (in this specification, also referred to as indium zinc oxide (IZO)) formed using a target in which zinc oxide (ZnO) of 2 to 20 wt % is mixed with indium oxide.

Next, an insulating film **802** is formed as a base film over the conductive film **801** and the substrate **800**. The insulating film **802** is, for example, a film in which a silicon oxide film is stacked on a silicon nitride film; however, it may be another insulator (e.g., a silicon oxide film containing nitrogen or a silicon nitride film containing oxygen).

Here, by performing nitriding with high-density plasma on a surface of the insulating film **802** formed of the silicon oxide film, the silicon oxide film containing nitrogen, or the like, a silicon nitride film may be formed on the surface of the insulating film **802**.

For example, high-density plasma is generated by using a microwave of 2.45 GHz, and has an electron density of 1×10^{11} to $1 \times 10^{13}/\text{cm}^3$, an electron temperature of 2 eV or less, and an ion energy of 5 eV or less. Such high-density plasma has low kinetic energy of active species, and can form a film with less plasma damage and fewer defects compared with conventional plasma treatment. A distance from an antenna generating a microwave to the insulating film **802** is set to 20 to 80 mm, and preferably 20 to 60 mm.

The surface of the insulating film **802** can be nitrided by performing the high-density plasma treatment in a nitrogen atmosphere, such as an atmosphere including nitrogen and rare gas, an atmosphere including nitrogen, hydrogen, and rare gas, or an atmosphere including ammonia and rare gas.

Since a silicon nitride film can suppress impurity diffusion from the substrate **800** and can be formed to be extremely thin by the high-density plasma treatment, influence of stress on a semiconductor film to be formed thereover can be reduced.

Then, as shown in FIG. 15B, a crystalline semiconductor film (e.g., a polycrystalline silicon film) is formed as a semiconductor film **803** over the insulating film **802**. Examples of a method of forming the crystalline semiconductor film include a method of directly forming the crystalline semiconductor film over the insulating film **802**, and a method of forming an amorphous semiconductor film over the insulating film **802** and then crystallizing the amorphous semiconductor film.

As a method for crystallizing the amorphous semiconductor film, a method of laser light irradiation, a method of thermal crystallization using an element which promotes crystallization of a semiconductor film (e.g., a metal element such as nickel), or a method of laser light irradiation after

thermal crystallization using an element which promotes crystallization of the semiconductor film can be used. It is needless to say that a method of thermal crystallization of the amorphous semiconductor film without using the above-described element can also be used; however, it is limited to the case of a substrate which can withstand high temperature, such as a quartz substrate or a silicon wafer.

When laser irradiation is used, a continuous wave laser beam (a CW laser beam) or a pulsed laser beam (a pulse laser beam) can be used. As a laser beam which can be used here, a laser emitted from one or more of the following can be used: a gas laser such as an Ar laser, a Kr laser, or an excimer laser; a laser of which a medium is single crystalline YAG; YVO_4 , forsterite (Mg_2SiO_4), YAlO_3 , or GdVO_4 , or polycrystalline (ceramic) YAG, Y_2O_3 , YVO_4 , YAlO_3 , or GdVO_4 , added with one or more of Nd, Yb, Cr, Ti, Ho, Er, Tm, and Ta as a dopant; a glass laser; a ruby laser; an alexandrite laser; a Ti:sapphire laser; a copper vapor laser; or a gold vapor laser. Crystals with a large grain size can be obtained by irradiation with a fundamental wave of such a laser beam or second to fourth harmonics of the fundamental wave. For example, the second harmonic (532 nm) or the third harmonic (355 nm) of an Nd:YVO4 laser (fundamental wave of 1064 nm) can be used. In this case, a power density of the laser is needed to be approximately 0.01 to 100 MW/cm² (preferably, 0.1 to 10 MW/cm²). Irradiation is performed with a scanning rate of approximately 10 to 2000 cm/sec.

Note that a laser of which a medium is single crystalline YAG, YVO_4 , forsterite (Mg_2SiO_4), YAlO_3 , or GdVO_4 , or polycrystalline (ceramic) YAG, Y_2O_3 , YVO_4 , YAlO_3 , or GdVO_4 added with one or more of Nd, Yb, Cr, Ti, Ho, Er, Tm, and Ta as a dopant; an Ar ion laser; or a Ti:sapphire laser can be continuously oscillated, and pulse oscillation thereof can be performed at a repetition rate of 10 MHz or more by performing Q-switch operation, mode locking, or the like. When a laser beam is oscillated at a repetition rate of 10 MHz or more, a semiconductor film is irradiated with the next pulse while the semiconductor film is melted by the laser and solidified. Accordingly, unlike the case of using a pulsed laser with a low repetition rate, a solid-liquid interface can be continuously moved in the semiconductor film; thus, crystal grains which continuously grow in a scanning direction can be obtained.

When ceramic (polycrystal) is used as a medium, the medium can be formed to have a desired shape for a short time and at low cost. When a single crystalline is used, a columnar medium with several mm in diameter and several tens of mm in length is used. When the ceramic is used, a medium larger than the case of using the single crystalline can be formed.

A concentration of a dopant such as Nd or Yb in a medium, which directly contributes to light emission, cannot be changed largely in either case of the single crystalline or the polycrystal; thus, there is some limitation on improvement in output of a laser by increasing the concentration of the dopant. However, in the case of ceramic, the size of the medium can be significantly increased as compared with the case of the single crystalline; thus, drastic improvement in output of a laser can be realized.

In addition, in the case of ceramic, a medium with a parallelepiped shape or a rectangular parallelepiped shape can be easily formed. When a medium having such a shape is used and oscillated light is made travel in a zigzag manner inside the medium, a path of the oscillated light can be made long. Therefore, amplification is increased, and a laser beam can be oscillated at high output. Further, since a cross section of a laser beam emitted from the medium having such a shape has a quadrangular shape, it has an advantage over a circular

beam in being shaped into a linear beam. By shaping a laser beam emitted in such a manner by using an optical system, a linear beam having a length of 1 mm or less on a lateral side and a length of several mm to several m on a longitudinal side can be easily obtained. Furthermore, when a medium is uniformly irradiated with excited light, energy distribution of a linear beam becomes uniform in a longitudinal direction.

A semiconductor film is irradiated with this linear beam, so that the whole surface of the semiconductor film can be annealed more uniformly. When uniform annealing is needed from one end to the other end of the linear beam, ingenuity such as arrangement in which slits are provided in both ends of the linear beam to shield light at a portion where energy is attenuated is necessary.

When a semiconductor film is annealed using the thus obtained linear beam having uniform intensity and an electronic device is formed by using this semiconductor film, characteristics of the electronic device are favorable and uniform.

As the method for crystallizing the amorphous semiconductor film by heating with an element which promotes crystallization of the semiconductor film, an amorphous semiconductor film (also referred to as an amorphous silicon film) is doped with a metal element which promotes crystallization of the semiconductor film, and then heat treatment is performed so that the amorphous semiconductor film is crystallized with the doped region as a nucleus.

Alternatively, an amorphous semiconductor film can be crystallized by performing irradiation with strong light instead of heat treatment. In this case, one or a combination of infrared light, visible light, and ultraviolet light can be used. Typically, light emitted from a halogen lamp, a metal halide lamp, a xenon arc lamp, a carbon arc lamp, a high pressure sodium lamp, or a high pressure mercury lamp is used. A lamp light source is lighted for 1 to 60 seconds, preferably 30 to 60 seconds, and such lighting is repeated 1 to 10 times, preferably 2 to 6 times. The light emission intensity of the lamp light source is decided as appropriate, so that the semiconductor film is instantaneously heated up to approximately 600 to 1000° C. Note that when necessary, heat treatment may be performed in order to discharge hydrogen contained in the amorphous semiconductor film having an amorphous structure before irradiation with strong light. Alternatively, crystallization may be performed by both heat treatment and irradiation with strong light.

After the heat treatment, the crystalline semiconductor film may be irradiated with the laser light in the atmospheric air or an oxygen atmosphere in order to increase the degree of crystallinity (a ratio of crystalline components in the whole volume of the film) of the crystalline semiconductor film and to correct defects which remain in crystalline grains. The laser light can be selected from the aforementioned laser light.

The doped elements are needed to be removed from the crystalline semiconductor film, and the method is described below.

First, a surface of the crystalline semiconductor film is treated with a solution containing ozone (typically, ozone water), so that a barrier layer formed of an oxide film (called chemical oxide) having a thickness of 1 to 10 nm is formed on the surface of the crystalline semiconductor film. The barrier layer functions as an etching stopper when only a gettering layer is selectively removed in a subsequent step.

Then, a gettering layer containing a rare gas element is formed as a gettering site over the barrier layer. Here, a semiconductor film containing a rare gas element is formed as the gettering layer by a CVD method or a sputtering method.

When the gettering layer is formed, the sputtering conditions are controlled as appropriate so that a rare gas element is added to the gettering layer. The rare gas element may be one or more of helium (He), neon (Ne), argon (Ar), krypton (Kr), and xenon (Xe).

Note that when the gettering layer is formed by using a source gas containing phosphorus, which is an impurity element, or by using a target containing phosphorus, gettering can be performed by utilizing the coulomb force of phosphorus in addition to gettering using the rare gas element. In gettering, a metal element (such as nickel) tends to move to a region having a high concentration of oxygen; therefore, the concentration of oxygen contained in the gettering layer is preferably set at, for example, $5 \times 10^{18} \text{ cm}^{-3}$ or higher.

Next, the crystalline semiconductor film, the barrier layer, and the gettering layer are subjected to thermal treatment (e.g., heat treatment or irradiation with strong light), so that the metal element (such as nickel) is gettered; thus, the metal element in the crystalline semiconductor film is lowered in concentration or removed.

Next, a known etching method is performed using the barrier layer as the etching stopper so that only the gettering layer is selectively removed. After that, the barrier layer formed of an oxide film is removed by, for example, an etchant containing hydrofluoric acid.

Here, impurity ions may be doped in consideration of threshold characteristics of a TFT to be manufactured.

Next, a photo resist film (not shown) is applied over the semiconductor film **803** by a coating method, and is exposed to light and developed. A coating method includes a spin coating method, a spray method, a screen printing method, a paint method, or the like. Thus, a resist is formed over the semiconductor film **803**. Then, the semiconductor film **803** is etched using the resist as a mask. Thus, island-shaped semiconductor films **872**, **873**, and **874** in which thin film transistors are formed are formed over the insulating film **802**.

Then, after surfaces of the island-shaped semiconductor films **872** to **874** are cleaned with an etchant containing hydrofluoric acid or the like, a gate insulating film **804** having a thickness of 10 to 200 nm is formed over the island-shaped semiconductor films **872** to **874**. The gate insulating film **804** is formed of an insulating film containing silicon as a main component, such as a silicon oxide film, a silicon nitride film, a silicon oxide film containing nitrogen, or a silicon nitride film containing oxygen. Further, the gate insulating film may have a single-layer structure or a stacked-layer structure. Note that the gate insulating film **804** is also formed over the insulating film **802**.

After the gate insulating film **804** is formed, gate electrodes **865**, **866**, **867**, and **868**; an electrode **869**; impurity regions **807a**, **807b**, **808a**, **808b**, **809a**, **809b**, **810a**, **810b**, **813a**, **813b**, **813c**, **814a**, **814b**, **814c**, and **814d**; and channel formation regions **895**, **896**, and **897** (**897a** and **897b**) are formed (see FIG. 15D).

The gate electrode **865** of a TFT **827** includes a lower gate electrode **805a** and an upper gate electrode **806a**. The gate electrode **866** of a TFT **829** includes a lower gate electrode **805b** and an upper gate electrode **806b**. The gate electrode **867** of a TFT **825** includes a lower gate electrode **805c** and an upper gate electrode **806c**, and the gate electrode **868** of the TFT **825** includes a lower gate electrode **805d** and an upper gate electrode **806d**.

The electrode **869** includes a lower electrode **861** and an upper electrode **862**.

Each of the impurity regions **807a** and **807b** is a source region or a drain region of the TFT **827**. The impurity regions **808a** and **808b** are low concentration impurity regions of the

TFT **827**. The channel formation region **895** is located between the impurity regions **808a** and **808b**.

Each of the impurity regions **809a** and **809b** are a source region or a drain region of the TFT **829**. The impurity regions **810a** and **810b** are low concentration impurity regions of the TFT **829**. The channel formation region **896** is located between the impurity regions **810a** and **810b**.

Each of the impurity regions **813a** and **813c** are a source region or a drain region of the TFT **825**. The impurity region **813b** is formed in the same step as the impurity regions **813a** and **813c**. The impurity regions **814a**, **814b**, **814c**, and **814d** are low concentration impurity regions of the TFT **825**. The channel formation region **897a** is located between the impurity regions **814a** and **814b**. The channel formation region **897b** is located between the impurity regions **814c** and **814d**.

In this embodiment, the impurity regions **809a**, **809b**, **810a**, **810b**, **813a** to **813c**, and **814a** to **814d** are n-type impurity regions, and include an impurity element imparting n-type conductivity, such as phosphorus (P) or arsenic (As). The impurity regions **809a**, **809b**, and **813a** to **813c** are high concentration impurity regions, and they have impurity concentrations higher than those of the impurity regions **810a**, **810b**, and **814a** to **814d**, which are low concentration impurity regions.

In this embodiment, the impurity regions **807a**, **807b**, **808a**, and **808b** are p-type impurity regions, and include an impurity element imparting p-type conductivity, such as boron (B). The impurity regions **807a** and **807b** are high concentration impurity regions, and they have impurity concentrations higher than those of the impurity regions **808a** and **808b**, which are low concentration impurity regions.

That is, the TFTs **829** and **825** are n-channel transistors, and the TFT **827** is a p-channel transistor.

A manufacturing method of the gate electrodes **865** to **868** and the electrode **869** is described below.

After the gate insulating film **804** is formed, the gate insulating film **804** is cleaned. Then, a first conductive film and a second conductive film are formed in this order over the gate insulating film **804**. For example, the first conductive film is a tungsten film and the second conductive film is a tantalum nitride film.

Next, a photo resist film is applied over the second conductive film, and is exposed to light and developed. Thus, a resist is formed over the second conductive film. Then, by using the resist as a mask, the first conductive film and the second conductive film are etched under a first condition, and further, the second conductive film is etched under a second condition. Thus, the lower gate electrode **805a** and the upper gate electrode **806a** are formed over the island-shaped semiconductor film **872**; the lower gate electrode **805b** and the upper gate electrode **806b** are formed over the island-shaped semiconductor film **873**; the lower gate electrode **805c** and the upper gate electrode **806c**, and the lower gate electrode **805d** and the upper gate electrode **806d** are formed over the island-shaped semiconductor film **874**.

Inclined angles of side surfaces of the lower gate electrodes **805a** to **805d** are more moderate than inclined angles of side surfaces of the upper gate electrodes **806a** to **806d**.

In addition, the lower electrode **861** and the upper electrode **862** are formed at the same time.

Thereafter, the photo resist film is removed.

The impurity regions **807a**, **807b**, **808a**, **808b**, **809a**, **809b**, **810a**, **810b**, **813a** to **813c**, and **814a** to **814d** may be formed by introducing impurities in a self-aligned manner by using the gate electrodes **865** to **868** as masks, or may be formed by introducing impurities using a resist mask.

Thereafter, an insulating film (not shown) covering almost all surface is formed. The insulating film is, for example, a silicon oxide film formed by a plasma CVD method.

Next, heat treatment is performed on the island-shaped semiconductor films **872** to **874** to activate the impurity elements doped therewith. The heat treatment is performed by a rapid thermal annealing method (RTA method) using a lamp light source, irradiation of a YAG laser or an excimer laser from the back surface, heat treatment using a furnace, or a combination of these methods.

By the heat treatment, the impurity elements are activated, and simultaneously the element (e.g., a metal element such as nickel) which is used as a catalyst for crystallizing the island-shaped semiconductor films **873** and **874** are gettered in the impurity regions **809a**, **809b**, and **813a** to **813c** including a high concentration impurity (such as phosphorus), and a nickel concentration mainly in a portion to be the channel formation regions **896**, **897a**, and **897b** in the island-shaped semiconductor films **873** and **874** is reduced. As a result, the crystallinity of the channel formation regions is improved. Accordingly, an off-current value of the TFT is reduced and high electron field-effect mobility can be obtained. Thus, a TFT having favorable characteristics can be obtained.

Next, an insulating film **815** is formed over the entire surface including above the island-shaped semiconductor films **872** to **874**. The insulating film **815** is, for example, a silicon nitride film formed by a plasma CVD method.

Then, a planarization film to be an interlayer insulating film **816** is formed over the insulating film **815**. As the interlayer insulating film **816**, a light-transmitting inorganic material (e.g., silicon oxide, silicon nitride, or silicon nitride containing oxygen); a photosensitive or non-photosensitive organic material (e.g., polyimide, acrylic, polyamide, polyimide amide, resist, or benzocyclobutene); a stacked-layer structure thereof; or the like is used. Alternatively, as another light-transmitting film used for the planarization film, an insulating film formed of a SiOx film containing an alkyl group obtained by a coating method, such as an insulating film formed using silica glass, an alkylsiloxane polymer, an alkylsilsesquioxane polymer, a hydrogen silsesquioxane polymer, a hydrogen alkylsilsesquioxane polymer, or the like can be used. Examples of siloxane-based polymers include coating insulating film materials such as PSB-K1 and PSB-K31 (product of Toray industries, Inc.) and ZRS-5PH (product of Catalysts & Chemicals Industries Co., Ltd.). The interlayer insulating film **816** may be a single-layer film or a multi-layer film.

Next, a photo resist film (not shown) is applied over the interlayer insulating film **816**, and is exposed to light and developed. Thus, a resist is formed over the interlayer insulating film **816**. Then, the interlayer insulating film **816**, the insulating film **815**, and the gate insulating film **804** are etched using the resist as a mask. Accordingly, contact holes **817a**, **817b**, **817c**, **817d**, **817e**, **817f**, **817g**, and **817h** are formed in the interlayer insulating film **816**, the insulating film **815**, and the gate insulating film **804**.

The contact hole **817a** is located over the impurity region **807a**. The contact hole **817b** is located over the impurity region **807b**. The contact hole **817c** is located over the impurity region **809a**. The contact hole **817d** is located over the impurity region **809b**. The contact hole **817e** is located over the impurity region **813a**. The contact hole **817f** is located over the impurity region **813c**. The contact hole **817g** is located over the conductive film **801**. The contact hole **817h** is located over the electrode **869**.

Thereafter, the resist is removed.

Next, as shown in FIG. 16B, a first conductive film **875** is formed in the contact holes **817a** to **817h** and over the inter-

layer insulating film **816**. The first conductive film **875** is a light-transmitting conductive film, such as an indium tin oxide film, a film of indium tin oxide containing silicon, or a film formed using a target in which zinc oxide of 2 to 20 wt % is mixed with indium oxide. Then, a second conductive film **876** is formed over the first conductive film **875**. The second conductive film **876** is, for example, a metal film.

Next, a photo resist film **820** is applied over the second conductive film **876**. Then, a reticle **840** is provided above the photo resist film **820**. The reticle **840** has a structure where semi-transparent films **841a**, **841b**, **841c**, **841d**, **841e**, **841f**, and **841g** are formed over a glass substrate, and light shielding films **842a**, **842b**, **842c**, **842d**, **842e**, **842f**, and **842g** are formed over the semi-transparent films **841a**, **841b**, **841c**, **841d**, **841e**, **841f**, and **841g**, respectively. The semi-transparent film **841a** and the light shielding film **842a** are located above the contact hole **817a**. The semi-transparent film **841b** and the light shielding film **842b** are located above the contact hole **817b**. The semi-transparent film **841c** and the light shielding film **842c** are located above the contact hole **817c**. The semi-transparent film **841d** and the light shielding film **842d** are located above the contact hole **817d**. The semi-transparent film **841e** and the light shielding film **842e** are located above the contact hole **817e**. The semi-transparent film **841f** and the light shielding film **842f** are located above the contact hole **817f**. The semi-transparent film **841g** and the light shielding film **842g** are located above the contact holes **817g** and **817h**.

Next, the photo resist film **820** is exposed to light using the reticle **840** as a mask. Thus, the photo resist film **820** is exposed to light except for portions below the light shielding films **842a** to **842g** and a lower layer of portions below the semi-transparent films **841a** to **841g**. Note that portions which are not exposed to light are denoted by regions **821a**, **821b**, **821c**, **821d**, **821e**, **821f**, and **821g**.

Next, as shown in FIG. 17A, the photo resist film **820** is developed. Thus, portions of the photo resist film **820**, which are exposed to light, are removed, and resists **822a**, **822b**, **822c**, **822d**, **822e**, **822f**, and **822g** are formed. The resist **822a** is located above the contact hole **817a**. The resist **822b** is located above the contact hole **817b**. The resist **822c** is located above the contact hole **817c**. The resist **822d** is located above the contact hole **817d**. The resist **822e** is located above the contact hole **817e**. The resist **822f** is located above the contact hole **817f**. The resist **822g** is located above the contact holes **817g** and **817h**.

Then, as shown in FIG. 17B, the first conductive film **875** and the second conductive film **876** are etched using the resists **822a** to **822g** as masks. Thus, the first conductive film **818** and the second conductive film **819** in regions which are not covered with the resists **822a** to **822g** are removed.

Thereafter, the resists **822a** to **822g** are removed.

In such a manner, an electrode **881** having a lower electrode **824a** and an upper electrode **823a**, an electrode **882** having a lower electrode **824b** and an upper electrode **823b**, an electrode **883** having a lower electrode **824c** and an upper electrode **823c**, an electrode **884** having a lower electrode **824d** and an upper electrode **823d**, an electrode **885** having a lower electrode **824e** and an upper electrode **823e**, an electrode **886** having a lower electrode **824f** and an upper electrode **823f**, and an electrode **887** having a lower electrode **863** and an upper electrode **864** are formed with one resist and one etching treatment.

The electrodes **881** to **887** may be electrically connected to each other by forming an additional wiring or may be formed as wirings. In the latter case, the electrodes **881** to **887** are described as the wirings **881** to **887**.

The electrodes **881**, **882**, **883**, **884**, **885**, and **886** are electrically connected to the impurity regions **807a**, **807b**, **809a**, **809b**, **813a**, and **813c**, respectively. The electrode **887** is electrically connected to the conductive film **801** and the electrode **869**.

Next, an interlayer insulating film **845** is formed over the interlayer insulating film **816** and the electrodes **881** to **887** (see FIG. 17C). The interlayer insulating film **845** may be formed of a material similar to that of the interlayer insulating film **816**.

Next, a contact hole reaching the electrode **886** is formed in the interlayer insulating film **845**. Then, pixel electrodes **891** (**891a**, **891b**, **891c**, **891d**, and the like) which are electrically connected to the electrode **886** through the contact hole are formed (see FIG. 18). The pixel electrodes **891** is formed of a light-transmitting material, and a material similar to that of the conductive film **875** may be used. Grooves **892** (**892a**, **892b**, **892c**, and the like) are formed in the pixel electrodes **891**. FIGS. 4, 7, 8A to 8D, and 9A to 9D may be used for shapes of the pixel electrodes **891** and the grooves **892**.

Thereafter, a first alignment film **826** is formed. In such a manner, an active matrix substrate is formed.

Note that the TFTs **827** and **829** are formed in a gate signal line driver circuit **854**. The TFTs separately formed are shown in FIG. 14B; however, the electrodes **882** and **883** may be electrically connected so that the TFTs **827** and **829** may be formed as a CMOS circuit.

Further, a first terminal electrode **838a** and a second terminal electrode **838b** (shown in FIG. 14B) which connect the active matrix substrate and the outside are formed.

Thereafter, as shown in a plan view of FIG. 14A and a cross-sectional view along a line K-L of FIG. 14B, an organic resin film such as an acrylic resin film is formed over the active matrix substrate. Then, the organic resin film is selectively removed by etching with the use of a mask film. Thus, a columnar spacer **833** is formed over the active matrix substrate. Next, after a sealing material **834** is formed in a sealing region **853**, a liquid crystal is dropped on the active matrix substrate. Before the liquid crystal is dropped, a protective film may be formed over the sealing material to prevent the sealing material and the liquid crystal from reacting with each other.

Thereafter, an opposite substrate **830** provided with a color filter **832** and a second alignment film **831** is provided opposite to the active matrix substrate, and the two substrates are attached by the sealing material **834**. At this time, the active matrix substrate and the opposite substrate **830** are attached with a uniform space therebetween by the spacer **833**. Next, the space between the substrates is completely sealed by a sealing material (not shown). Thus, a liquid crystal **846** is sealed between the active matrix substrate and the opposite substrate.

Next, one or both of the active matrix substrate and the opposite substrate are cut into a desired shape when needed. Further, polarizing plates **835a** and **835b** are provided. Note that a retardation plate may be provided between the substrate **800** and the polarizing plate **835a**, and between the opposite substrate **830** and the polarizing plate **835b**. Furthermore, a retardation plate may be provided on surfaces of the polarizing plates **835a** and **835b**, which are opposite to surfaces in contact with the substrate, instead of between the substrate and the polarizing plate.

Next, a flexible printed circuit (hereinafter referred to as an FPC) **837** is connected to the second terminal electrode **838b** provided in an external terminal connection region **852** through an anisotropy conductive film **836**.

A structure of a liquid crystal display module formed in such a manner is described. A pixel region **856** is located at the center of the active matrix substrate. A plurality of pixels are formed in the pixel region **856**. In FIG. **14A**, the gate signal line driver circuits **854** for driving gate signal lines are provided above and below the pixel region **856**. A source signal line driver circuit **857** for driving source signal lines is provided in a region between the pixel region **856** and the FPC **837**. The gate signal line driver circuit **854** may be provided on only one side of the pixel region **856**. An arrangement position of the gate signal line driver circuit **854** may be selected as appropriate in consideration of the substrate size or the like of the liquid crystal display module. Note that the gate signal line driver circuits **854** are preferably provided symmetrically with the pixel region **856** therebetween considering operation reliability, efficiency of driving, and the like. Signals are input from the FPC **837** to each driver circuit.

Embodiment 2

A liquid crystal display module according to Embodiment 1 is described with reference to FIGS. **19A**, **19B**, **20A**, and **20B**. A structure of a pixel portion **930** in each drawing is similar to the structure of the pixel region **856** in Embodiment 1, and a plurality of pixels are formed over the substrate **100**.

FIG. **19A** is a plan view of a liquid crystal display module. FIG. **19B** is a circuit diagram of a source driver (also referred to as a source signal line driver circuit) **910**. As shown in FIG. **19A**, both the source driver **910** and a gate driver (also referred to as a gate signal line driver circuit) **920** are formed over the substrate **100** same as the pixel portion **930**. As shown in FIG. **19B**, the source driver **910** includes a plurality of thin film transistors **912** for selecting the source signal line to which a video signal input is transmitted, and a shift register **911** for controlling the plurality of thin film transistors **912**.

FIG. **20A** is a plan view of a liquid crystal display module. FIG. **20B** is a circuit diagram of a plurality of analog switch TFTs **940**. As shown in FIG. **20A**, the liquid crystal display module includes the plurality of analog switch TFTs **940** formed over the substrate **100** and an IC **950** formed separately from the substrate **100**. The IC **950** and the plurality of analog switch TFTs **940** are electrically connected by an FPC **960**, for example.

The IC **950** is formed using a single crystalline silicon substrate, for example. The IC **950** controls the plurality of analog switch TFTs **940** and inputs a video signal to the plurality of analog switch TFTs **940**. The plurality of analog switch TFTs **940** for selecting the source signal line to which a video signal input is transmitted, based on a control signal from the IC.

According to the invention, a liquid crystal display device with a wide viewing angle and lower manufacturing cost than a conventional liquid crystal display device can be provided.

In the invention, since a conductive film is formed over an entire surface of a substrate, an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a semiconductor device with high reliability can be obtained.

In the invention, when a semiconductor device including a top-gate thin film transistor is formed, a potential of a back gate is stabilized; thus, a semiconductor device with high reliability can be obtained.

Embodiment 3

Examples where the invention is applied to an electronic device are described with reference to FIGS. **21A** to **21H**.

Each electronic device is provided with any of the display devices or the display modules in the aforementioned embodiment modes and embodiments.

Examples of electronic devices include cameras such as a video camera and a digital camera, a goggle-type display (a head-mounted display), a navigation system, an audio reproducing device (such as car audio components), a computer, a game machine, a portable information terminal (such as a mobile computer, a mobile phone, a mobile game machine, and an electronic book), an image reproducing device provided with a recording medium (specifically, a device for reproducing a recording medium such as a digital versatile disc (DVD) and having a display for displaying the reproduced image), and the like. FIGS. **21A** to **21H** show specific examples of these electronic devices.

FIG. **21A** shows a monitor of a television receiving device or a personal computer, which includes a housing **2001**, a support base **2002**, a display portion **2003**, speaker portions **2004**, a video input terminal **2005**, and the like. As the display portion **2003**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. A monitor in the invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional monitor. Further, in a display portion of a monitor in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a monitor with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is formed in a monitor of the invention, a potential of a back gate is stabilized; thus, a monitor with high reliability can be obtained.

FIG. **21B** shows a digital camera. An image receiving portion **2103** is provided in the front side of a main body **2101**. A shutter button **2106** is provided at the upper portion of the main body **2101**. A display portion **2102**, operation keys **2104**, and an external connection port **2105** are provided at the backside of the main body **2101**. As the display portion **2102**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. A digital camera in the invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional digital camera. Further, in a display portion of a digital camera in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a digital camera with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is formed in a digital camera of the invention, a potential of a back gate is stabilized; thus, a digital camera with high reliability can be obtained.

FIG. **21C** shows a notebook personal computer. A main body **2201** is provided with a keyboard **2204**, an external connection port **2205**, and a pointing device **2206**. A housing **2202** including a display portion **2203** is attached to the main body **2201**. As the display portion **2203**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. A computer in the invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional computer. Further, in a display portion of a computer in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a computer with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is

formed in a computer of the invention, a potential of a back gate is stabilized; thus, a computer with high reliability can be obtained.

FIG. 21D shows a mobile computer, which includes a main body **2301**, a display portion **2302**, a switch **2303**, operation keys **2304**, an infrared port **2305**, and the like. An active matrix display device is provided in the display portion **2302**. As the display portion **2302**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. A computer in the invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional computer. Further, in a display portion of a computer in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a computer with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is formed in a computer of the invention, a potential of a back gate is stabilized; thus, a computer with high reliability can be obtained.

FIG. 21E shows an image reproducing device. A main body **2401** is provided with a display portion B **2404**, a recording medium reading portion **2405**, and an operation key **2406**. A housing **2402** including a speaker portion **2407** and a display portion A **2403** is attached to the main body **2401**. As each of the display portion A **2403** and the display portion B **2404**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. An image reproducing device in the invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional image reproducing device. Further, in a display portion of an image reproducing device in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, an image reproducing device with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is formed in an image reproducing device of the invention, a potential of a back gate is stabilized; thus, an image reproducing device with high reliability can be obtained.

FIG. 21F shows an electronic book. A main body **2501** is provided with an operation key **2503**. A plurality of display portions **2502** are attached to the main body **2501**. As the display portions **2502**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. An electronic book in the invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional electronic book. Further, in a display portion of an electronic book in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, an electronic book with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is formed in an electronic book of the invention, a potential of a back gate is stabilized; thus, an electronic book with high reliability can be obtained.

FIG. 21G shows a video camera. A main body **2601** is provided with an external connection port **2604**, a remote control receiving portion **2605**, an image receiving portion **2606**, a battery **2607**, an audio input portion **2608**, operation keys **2609**, and an eyepiece portion **2610**. A housing **2603** including a display portion **2602** is attached to the main body **2601**. As the display portions **2602**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. A video camera in the

invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional video camera. Further, in a display portion of a video camera in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a video camera with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is formed in a video camera of the invention, a potential of a back gate is stabilized; thus, a video camera with high reliability can be obtained.

FIG. 21H shows a mobile phone, which includes a main body **2701**, a housing **2702**, a display portion **2703**, an audio input portion **2704**, an audio output portion **2705**, an operation key **2706**, an external connection port **2707**, an antenna **2708**, and the like. As the display portions **2703**, any of the display devices or the display modules in the aforementioned embodiment modes and embodiments is used. A mobile phone in the invention has a wide viewing angle and can be formed at low manufacturing cost compared with a conventional mobile phone. Further, in a display portion of a mobile phone in the invention, a conductive film is formed over an entire surface of a substrate, so that an impurity from the substrate can be prevented from being mixed into an active layer. Thus, a mobile phone with high reliability can be obtained. Moreover, when a display portion including a top-gate thin film transistor is formed in a mobile phone of the invention, a potential of a back gate is stabilized; thus, a mobile phone with high reliability can be obtained.

This application is based on Japanese Patent Application serial No. 2006-297009 filed in Japan Patent Office on Oct. 31, 2006, the entire contents of which are hereby incorporated by reference.

What is claimed is:

1. A liquid crystal display device comprising:

a common electrode;

a wiring over and electrically connected to the common electrode;

a first insulating film over the common electrode and the wiring;

a pixel electrode over the first insulating film;

a liquid crystal over the common electrode and the pixel electrode;

a transistor electrically connected to the pixel electrode;

a gate wiring electrically connected to the transistor; and a source wiring electrically connected to the transistor, wherein the common electrode overlaps the gate wiring, the wiring, a semiconductor film of the transistor, the source wiring, and the pixel electrode,

wherein the wiring comprises a copper film or a stacked structure in which an aluminum film is sandwiched between molybdenum films,

wherein the pixel electrode comprise a plurality of openings,

wherein the first insulating film is provided over the transistor,

wherein each of the common electrode and the pixel electrode is a light-transmitting conductive film, and

wherein an orientation of the liquid crystal is configured to be controlled by an electric field between the common electrode and the pixel electrode.

2. The liquid crystal display device according to claim 1, wherein the source wiring comprises a curved portion, and wherein each of the plurality of openings has a shape along the curved portion of the source wiring.

3. The liquid crystal display device according to claim 1, comprising a second insulating film between the common

91

electrode and the wiring, wherein the gate wiring and the wiring are on and in contact with the second insulating film.

4. The liquid crystal display device according to claim 1, comprising a conductive film electrically connecting the common electrode and the wiring.

5. The liquid crystal display device according to claim 1, wherein the semiconductor film comprising indium, gallium, and zinc.

6. The liquid crystal display device according to claim 1, wherein the common electrode does not comprise an opening.

7. The liquid crystal display device according to claim 1, wherein the semiconductor film is provided over the gate wiring.

8. The liquid crystal display device according to claim 1, wherein the gate wiring is provided over the semiconductor film.

9. A liquid crystal display device comprising:

a common electrode;

a wiring over and electrically connected to the common electrode;

a first insulating film over the common electrode and the wiring;

a pixel electrode over the first insulating film;

a liquid crystal over the common electrode and the pixel electrode;

a transistor electrically connected to the pixel electrode;

a gate wiring electrically connected to the transistor; and

a source wiring electrically connected to the transistor, wherein the common electrode overlaps the gate wiring, the wiring, a semiconductor film of the transistor, the source wiring, and the pixel electrode,

wherein the wiring comprises a copper film or a stacked structure in which an aluminum film is sandwiched between molybdenum films,

92

wherein the pixel electrode comprise a plurality of openings,

wherein the gate wiring is parallel to the wiring,

wherein the first insulating film is provided over the transistor,

wherein each of the common electrode and the pixel electrode is a light-transmitting conductive film, and

wherein an orientation of the liquid crystal is configured to be controlled by an electric field between the common electrode and the pixel electrode.

10. The liquid crystal display device according to claim 9, wherein the source wiring comprises a curved portion, and wherein each of the plurality of openings has a shape along the curved portion of the source wiring.

11. The liquid crystal display device according to claim 9, comprising a second insulating film between the common electrode and the wiring, wherein the gate wiring and the wiring are on and in contact with the second insulating film.

12. The liquid crystal display device according to claim 9, comprising a conductive film electrically connecting the common electrode and the wiring.

13. The liquid crystal display device according to claim 9, wherein the semiconductor film comprising indium, gallium, and zinc.

14. The liquid crystal display device according to claim 9, wherein the common electrode does not comprise an opening.

15. The liquid crystal display device according to claim 9, wherein the semiconductor film is provided over the gate wiring.

16. The liquid crystal display device according to claim 9, wherein the gate wiring is provided over the semiconductor film.

* * * * *

UNITED STATES PATENT AND TRADEMARK OFFICE
CERTIFICATE OF CORRECTION

PATENT NO. : 8,964,156 B2
APPLICATION NO. : 14/322999
DATED : February 24, 2015
INVENTOR(S) : Hajime Kimura

Page 1 of 1

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

In the specification

Column 31, line 66, replace "2086" with --208b--;
Column 32, line 56, replace "2076" with --207b--;
Column 33, line 54, replace "2076" with --207b--;
Column 37, line 65, after "29G" insert --,--;
Column 65, line 7, replace " $(|V_3|,$ " with -- $(|V_1|,$ --;
Column 65, line 18, replace "voltage $|V_3|$ " with --voltage $|V_1|$ --;
Column 65, line 18, replace " $|V_2|$ which" with -- $|V_2|$, which--;
Column 65, line 19, replace "TR₃ and" with --TR₁ and--;
Column 80, line 13, after "YAG" replace ";" with --,--;
Column 82, line 65, replace "8076" with --807b--;
Column 85, line 40, replace "8226" with --822b--; and
Column 85, line 41, replace "8176" with --817b--.

Signed and Sealed this
Third Day of November, 2015



Michelle K. Lee
Director of the United States Patent and Trademark Office

专利名称(译)	液晶显示装置和电子设备		
公开(公告)号	US8964156	公开(公告)日	2015-02-24
申请号	US14/322999	申请日	2014-07-03
[标]申请(专利权)人(译)	株式会社半导体能源研究所		
申请(专利权)人(译)	半导体能源研究所有限公司.		
当前申请(专利权)人(译)	半导体能源研究所有限公司.		
[标]发明人	KIMURA HAJIME		
发明人	KIMURA, HAJIME		
IPC分类号	G02F1/1343 G02F1/1368 G02F1/139 G02F1/1362		
CPC分类号	G02F1/136286 G02F1/134363 G02F1/13439 G02F1/1362 G02F1/133553 G02F2001/134372 G02F2001/136231 G09G3/20 G09G3/342 G09G3/3659 G09G3/3685 G09G2300/0876 G09G2310/0235 G09G2310/024 G09G2310/027 G09G2310/0275 G09G2310/0297 G09G2320/0233 G09G2320/0252 G09G2320/0261 G09G2320/106 G09G2340/0435 G09G2340/16 G09G2352/00 H01L27/1214 H01L27/1218 H04N9/3102 G02F1/133345 G02F1/1337 G02F1/134309 G02F1/136277 G02F1/1368		
代理机构(译)	FISH & RICHARDSON P.C.		
审查员(译)	NGUYEN, 龚便		
优先权	2006297009 2006-10-31 JP 12/977217 2012-03-06 US 11/923128 2011-01-18 US		
其他公开文献	US20140313445A1		
外部链接	Espacenet USPTO		

摘要(译)

提供一种半导体器件，液晶显示器件和电子器件，其具有宽视角，并且与传统的制造步骤相比，制造步骤的数量，掩模的数量和制造成本降低。液晶显示装置包括形成在基板一侧的整个表面上的第一电极；形成在第一电极上的第一绝缘膜；在第一绝缘膜上形成薄膜晶体管；在薄膜晶体管上形成第二绝缘膜；第二电极形成在第二绝缘膜上并具有多个开口；和第二电极上的液晶。液晶由第一电极和第二电极之间的电场控制。

